

# BASIC COMPLIANCE REPORT

## Calculation Type: New Build (As Built)



Property Reference	2 The Ridgeway				Issued on Date	04/03/2025
Assessment Reference	001		Prop Type Ref	3322		
Property	2 The Ridgeway, Woodley, Reading, RG5 3QD					
SAP Rating	86 B	DER	14.13	TER	14.20	
Environmental	84 B	% DER<TER	0.46			
CO <sub>2</sub> Emissions (t/year)	3.64	DFEE	51.31	TFEE	59.92	
General Requirements Compliance	Pass	% DFEE<TFEE	14.37			
Assessor Details	Mr. Nick Gill, Nick Gill, Tel: 01444 657 756, info@pebble-energy.com				Assessor ID	AW10-0001
Client						

### SUMMARY FOR INPUT DATA FOR New Build (As Built)

#### Criterion 1 – Achieving the TER and TFEE rate

##### 1a TER and DER

Fuel for main heating	Mains gas		
Fuel factor	1.00 (mains gas)		
Target Carbon Dioxide Emission Rate (TER)	14.20	kgCO <sub>2</sub> /m <sup>2</sup>	
Dwelling Carbon Dioxide Emission Rate (DER)	14.13	kgCO <sub>2</sub> /m <sup>2</sup>	Pass
	-0.07 (-0.5%)	kgCO <sub>2</sub> /m <sup>2</sup>	

##### 1b TFEE and DFEE

Target Fabric Energy Efficiency (TFEE)	59.92	kWh/m <sup>2</sup> /yr	
Dwelling Fabric Energy Efficiency (DFEE)	51.31	kWh/m <sup>2</sup> /yr	
	-8.6 (-14.4%)	kWh/m <sup>2</sup> /yr	Pass

#### Criterion 2 – Limits on design flexibility

##### Limiting Fabric Standards

##### 2 Fabric U-values

Element	Average	Highest	
External wall	0.23 (max. 0.30)	0.23 (max. 0.70)	Pass
Floor	0.17 (max. 0.25)	0.23 (max. 0.70)	Pass
Roof	0.18 (max. 0.20)	0.18 (max. 0.35)	Pass
Openings	1.38 (max. 2.00)	1.40 (max. 3.30)	Pass

##### 2a Thermal bridging

Thermal bridging calculated from linear thermal transmittances for each junction

##### 3 Air permeability

Air permeability at 50 pascals	4.84 (measured in this dwelling)	
Maximum	10.0	Pass

##### Limiting System Efficiencies

##### 4 Heating efficiency

Main heating system	Boiler system with radiators or underfloor - Mains gas Data from database Ideal VOGUE MAX SYSTEM 32  Efficiency: 89.4% SEDBUK2009 Minimum: 88.0%	Pass
Secondary heating system	None	

# BASIC COMPLIANCE REPORT

## Calculation Type: New Build (As Built)



### 5 Cylinder insulation

Hot water storage	Measured cylinder loss: 2.04 kWh/day Permitted by DBSCG 2.24	Pass
Primary pipework insulated	Yes	Pass

### 6 Controls

Space heating controls	Time and temperature zone control	Pass
Hot water controls	Cylinderstat	Pass
	Independent timer for DHW	Pass
Boiler interlock	Yes	Pass

### 7 Low energy lights

Percentage of fixed lights with low-energy fittings	100	%	
Minimum	75	%	Pass

### 8 Mechanical ventilation

Not applicable

## Criterion 3 – Limiting the effects of heat gains in summer

### 9 Summertime temperature

Overheating risk (Thames Valley)	Slight	Pass
Based on:		
Overshading	Average	
Windows facing North	28.83 m <sup>2</sup> , No overhang	
Windows facing South	14.00 m <sup>2</sup> , No overhang	
Windows facing West	4.20 m <sup>2</sup> , No overhang	
Air change rate	0.00 ach	
Blinds/curtains	Dark-coloured curtain or roller blind, closed 100% of daylight hours	

## Criterion 4 – Building performance consistent with DER and DFEE rate

### Air permeability and pressure testing

#### 3 Air permeability

Air permeability at 50 pascals	4.84 (measured in this dwelling)	
Maximum	10.0	Pass

### 10 Key features

Thermal bridging y-value	0.028	W/m <sup>2</sup> K
--------------------------	-------	--------------------

*This report has not been submitted through the Elmhurst Energy members' portal, therefore results are subject to change when the dwelling is completed.*

# DWELLING SIGN OFF REPORT



## Section 1: Dwelling Information

**Dwelling Address** (Please confirm final postal address and post code of the dwelling.)

House Name	2 The Ridgeway	
House Number		
Postcode	RG5 3QD	
Street	Woodley	
Locality		
Town	Reading	
County		

**Dwelling Orientation** South (Please confirm orientation of main entrance door of the dwelling.)

Comments

**Terrain Type** Suburban

**Property Type** House, Detached

Comments

**Overshading (called Sunlight/shade in assessment)** Average or unknown

Comments

## Section 2: Dwelling Construction Details

**Thermal Mass Parameter** Simple calculation

Thermal Mass 100.00 kJ/m<sup>2</sup>K

Comments

### External Walls

Type Cavity Wall

Construction

U-value 0.23 W/m<sup>2</sup>K U-value calculations should be provided to verify the u-value entered in the survey.

Gross Area 283.78 m<sup>2</sup>

Type Timber Frame

Construction

U-value 0.19 W/m<sup>2</sup>K U-value calculations should be provided to verify the u-value entered in the survey.

Gross Area 1.80 m<sup>2</sup>

Comments

### External Roofs

Type External Slope Roof

Construction

U-value 0.18 W/m<sup>2</sup>K U-value calculations should be provided to verify the u-value entered in the survey.

Gross Area 174.00 m<sup>2</sup>

# DWELLING SIGN OFF REPORT



Type	External Flat Roof		
Construction			
U-value	0.16	W/m <sup>2</sup> K	U-value calculations should be provided to verify the u-value entered in the survey.
Gross Area	60.00	m <sup>2</sup>	

Comments

--

## Heat Loss Floors

Type	Ground Floor - Solid		
Construction			
U-value	0.15	W/m <sup>2</sup> K	U-value calculations should be provided to verify the u-value entered in the survey.
Area	156.00	m <sup>2</sup>	
Type	Exposed Floor - Solid		
Construction			
U-value	0.23	W/m <sup>2</sup> K	U-value calculations should be provided to verify the u-value entered in the survey.
Area	50.40	m <sup>2</sup>	

Comments

--

## Opening Types

Description	Type	Glazing	Frame Type	U Value (W/m <sup>2</sup> K)
Entrance	Half Glazed Door	Double Low-E Soft 0.05		1.40
Solid door	Solid Door			1.40
Window	Window	Double Low-E Soft 0.05		1.40
Roof window	Roof Window	Double Low-E Soft 0.05		1.30

Comments

--

## Openings

# DWELLING SIGN OFF REPORT



Name	Opening Type	Location	Orientation	Area (m²)
Entrance	Half Glazed Door	[1] External walls	South	3.68
Utility	Half Glazed Door	[1] External walls	East	2.06
Garage	Solid Door	[1] External walls	South	4.12
Lounge	Window	[1] External walls	South	2.03
Kitchen	Window	[1] External walls	West	2.94
Breakfast	Window	[1] External walls	North	10.50
Living	Window	[1] External walls	North	7.14
Gym	Window	[1] External walls	North	4.05
Bedroom	Window	[1] External walls	South	2.03
Master bedroom	Window	[1] External walls	South	2.18
Room 2	Window	[1] External walls	South	3.30
Bathroom	Window	[1] External walls	South	1.16
Bedroom 4	Window	[1] External walls	South	3.30
En-suite	Window	[1] External walls	West	1.26
Bedroom 5	Window	[1] External walls	North	1.90
Landing	Window	[1] External walls	North	1.16
Bedroom 3	Window	[1] External walls	North	1.90
Master bedroom	Window	[1] External walls	North	2.18
RL01	Roof Window	[1] Roof	East	1.46
RL02	Roof Window	[1] Roof	North	1.46
RL03	Roof Window	[1] Roof	South	1.46
RL04	Roof Window	[2] Flat roof	Horizontal	10.80

Comments

## Thermal Bridging

Calculate Bridges

### List of Bridges

Bridge Type	Source Type	Length (m)	Psi (W/mK)	Reference
E2 Other lintels (including other steel lintels)	Independently assessed	34.91	0.026	
E3 Sill	Independently assessed	30.22	0.023	
E4 Jamb	Independently assessed	65.30	0.018	
E5 Ground floor (normal)	Independently assessed	62.30	0.068	
E20 Exposed floor (normal)	Table K1 - Default	14.00	0.320	
E21 Exposed floor (inverted)	Table K1 - Default	14.00	0.320	
E6 Intermediate floor within a dwelling	Independently assessed	42.00	0.001	
E24 Eaves (insulation at ceiling level - inverted)	Table K1 - Default	11.40	0.240	
E11 Eaves (insulation at rafter level)	Independently assessed	51.50	0.018	
E13 Gable (insulation at rafter level)	Independently assessed	14.20	0.039	
E16 Corner (normal)	Independently assessed	32.30	0.040	
E17 Corner (inverted – internal area greater than external area)	Independently assessed	11.60	-0.082	

Y-value

0.028

W/m²K

Comments

Where specific construction details have been used documentary evidence should be provided to the SAP assessor, usually in the form of signed checklists.

## Pressure Testing

Yes

# DWELLING SIGN OFF REPORT



As Built AP<sub>50</sub>

4.84

m<sup>3</sup>/(h.m<sup>2</sup>) @ 50 Pa

Where an air pressure test has been carried out a copy of the test certificate should be forwarded to the SAP assessor.

Comments

## Section 3: Dwelling Systems

### Fans, Open Fireplaces, Flues

	MHS	SHS	Other	Total
Number of Chimneys	0		0	0
Number of open flues	0		0	0
Number of intermittent fans				6
Number of passive vents				0
Number of flueless gas fires				0

Comments

### Internal Lighting

Total number of light fittings	25	
Total number of L.E.L. fittings	25	
Percentage of L.E.L. fittings	100.00	%

Comments

### External Lighting

External lights fitted	Yes
Light and motion sensor	Yes

Comments

### Electricity Tariff

Standard

Comments

### Main Heating 1

	Database
Fuel Type	Mains gas
Main Heating	Mains gas BGB Post 98 Regular condens. with auto ign.
Efficiency (Split Efficiencies)	89.4 %
Brand, Model	Ideal, VOGUE MAX SYSTEM
Flue Type	Balanced
Fan Assisted Flue	Yes
Heat Emitter	Radiators and Underfloor
Flow Temperature	36° - 45°C

Comments

### Heating Controls

Description	CBI Time and temperature zone control
-------------	---------------------------------------

# DWELLING SIGN OFF REPORT



Boiler Interlock

Delayed Start Stat

Compensator

Comments

Main Heating 2

Comments

Water Heating System

Water Heating

Supplementary Immersion

Comments

Hot Water Cylinder

Independent Time Control

Cylinder Stat

Insulation Type

Insulation Thickness

Cylinder Volume

Measured Loss


Pipes insulation

Comments

## Section 4: Dwelling Renewable Energy

## Section 5: Declaration

I confirm that all details provided are true to the best of my knowledge.

Signed .....  .....

Date ..... 01/05/2025 .....