KEY

Existing Vegetation to be retained with RPA's shown refer to ACD Drawings for further details

Ancient Woodland (with 15m Woodland Buffer shown)

Existing Emm Brook

Existing Public Rights of Way

Proposed SWDR planting - not to be counted towards BNG

Formal circular route: For pedestrians
Compacted self binding 'Breedon Golden Amber' gravel (or similar approved). 2m wide with timber edgings with 0.5m wide mown grass edge

Informal surfaced footpath: For pedestrians
Compacted self binding 'Breedon Golden Amber' gravel (or similar approved). 1.5m wide with timber edging

Informal surfaced footpath: For pedestrians
Compacted self binding 'Breedon Golden Amber' gravel (or similar approved). 1.5m wide with no edgings. Length of footpath to come forward when sports hub is operational.

East-West Pedestrian cycle route
3m wide flexible bonded aggregate footpath e.g KBI Flexistone in Cappuccino (or similar approved) Flexistone to form edging.

Informal mown path / mown path edges: Formed by regular mowing. 1m wide with no edging.

Path through Ancient Woodland: Refer to detail on sheet 2 for pedestrians and in-frequent vehicular maintenance access. 2.5m wide no dig footpath (e.g cellweb) within root protection area to be timber edged filled with breedon angular chippings in golden amber (or similar approved)

Path through root protection areas: Refer to detail on sheet 2 for pedestrians 2m wide no dig footpath (e.g cellweb) within root protection area to be timber edged to be filled with breedon angular chippings in golden amber (or similar approved)

Boardwalk ramp to bridges
Hardwood timber boardwalks to provide ramp to bridges. To be 2m or 3.6m wide to match the bridge crossing width. Refer to technical drawings A389-ANG-111 - 114 for further details.

Pedestrian crossing point (2 no):
2m wide - each briding point to consist of steel girders spanning crossing set on concrete foundation with hardwood timber decking boards with antislip insets to form tread. Handrails to each side - to consist of vertical posts attached to steel girder with 3 horizontal rails. Refer to technical drawings A389-ANG-111 - 114 for further details.

Maintenance/pedestrian crossing point (2 no):
3.6m wide to allow maintenance vehicles to cross- each briding point to consist of steel girders spanning crossing set on concrete foundation with hardwood timber decking boards to form tread. Handrails to each side - to consist of vertical posts attached to steel girder with 3 horizontal rails. Refer to technical drawings A389-ANG-111 - 114 for further details.

Timber litter bin: (6 no.)
120L Okehampton Redwood litter bin, Broxap (BX17 4030), bolt down fixing (or similar approved)

Dog waste bin: (6 no.)
40L Sirius dog waste bin, Broxap (BX45 2591-PM) in Moss Green (RA 6005) to be root fixed (or similar approved)

Picnic Bench and Table (9 no.)
Cheshunt 6 person (CHS 4), bolt down fixing (or similar approved)

Seat: (18 no.)
Cheshunt seat with backrest 2 person (CHS4), bolt down fixing (or similar approved)

Welcome/Information Board: (3 no.)
Timber information board with map and information about the SANG. e.g Musketeer twin leg wooden lectern supplied by Fitzpatrick Woolmer or similar approved. To be installed with submerged fixings set into concrete footings as per manufacturer's specification. Content to be confirmed and agreed with WBC prior to installation

Play Space Information Board: (3 no.)
Aluminium information board to be fixed to playground fencing near to gates with information to be agreed with WBC prior to installation

Wayfinding: (10 no.)
Timber finger posts showing distances and direction to points of interest within and outside of the SANG such as play spaces, neighbourhood centre, neighbouring SANG and walking routes. eg Timber waymarker supplied by Woodscape or similar approved. To be engraved with painted lettering. To be set in concrete footings. Content to be confirmed and agreed with WBC prior to installation

Public Art (4no.)
Details of design and location to be confirmed in line with the public art strategy.

Mounding:
Earth mounding, maximum height 1m with a maximum 1:4 gradients

Dog Beach:
Area of gravel with gentle gradient to allow easy access for dogs to water

Gateway Feature: (1 no.)
Design to be confirmed in consulation with Ludgrove School

Boundary treaments

Dog Proof Fencing:
1.2m high post and rail fence with mesh

Kissing gate: (12 no.) For pedestrians, pushchairs and wheelchairs
Timber with self-closing mechanism, to be fitted with agricultural wire fencing stock eg Jackson Fencing Mobility Kissing Gate 1.5m wide (or similar approved)

Field gate and access: (3 no.)
Timber field gate for maintenance access, 3.6m wide, 1.2m high (with lock) and self-closing pedestrian access gate 1.5m wide, 1.2m high. Both gates are to be fitted with agricultural wire fencing stock.

Fence to Play Space:
Timber playground fencing eg Jackson Wooden Playground Fencing (or similar approved) 1.05m high with natural finish.

Gate to Play Space: (3no.)
Timber play gate with steel frame eg Jackson Fencing Playtime Gate (or similar approved) inward opening with self closing operation with natural finish to timber gate and powder coating to steel frame.

Height Restriction Barrier (1no.)
2.1m high height restrictor barrier 6m wide with single leaf opening for larger vehicles. eg Jacksons Fencing Height restricton barrier in black

Timber knee rail:
0.6m high timber knee rail e.g Jackson Fencing wooden knee rail fencing (or similar approved)

Scattered Trees
Proposed native tree planting

Scattered Trees
Proposed native feature tree planting

Traditional Orchard
Proposed orchard tree planting

Other broadleaved woodland
to provide a varied woodland structure with diverse species

Mixed Scrub
Woodland edge planting

Mixed Scrub
Proposed native shrub/scrub planting

Sustainable Drainge System
Proposed native shrub planting within SWDR basin

Sustainable Drainge System
Proposed defensible shrub planting within SWDR basin

Introduced shrub
Ornamental planting around LLAP

Native species rich hedgerow

Native species rich hedgerow planting with trees

Other Neutral Grassland
Proposed wildlower meadow (e.g. Emorsgate EM3 Special General Purpose Meadow Mixture)

Proposed Purple Moor Grass and Rush Pasture e.g Emorsgate EM8 Meadow Mixture for Wetlands with plug plants

Other Neutral Grassland
Proposed flowering lawn e.g Emorsgate EL1 with bulb plug planting

Other Neutral GrasslandProposed long mown grass (e.g. Emorsgate EM2 Standard General Purpose Meadow Mixture)


Modified Grassland Mown amenity grass

Existing grassland to be retained and made good within the sports hub safeguarded route

River enhancements Pre-planted coir rolls along water channel e.g Green-Tech Coir Log Rolls in 200mm. To be located on the eastern side of the Emm Brook

Bulb planting

Owl Nesting Box (location to be confirmed by ecologist on site prior to installation)



Refer to drawing P19-0052_09 Sheet 3

Woodland Mix (1947 m²)
49 no. Acer campestre (10%)
49 no. Corylus avellana (10%)
49 no. Crataegus monogyna (10%)
49 no. Populus tremula (10%)
37 no. Prunus avium (7.5%)
49 no. Quercus robur (t) (10%)
24 no. Quercus robur (5%)
49 no. Sorbus aucuparia (10%)
49 no. Sorbus torminalis (10%)
37 no. Tilia cordata (7.5%)
49 no. Viburnum opulus (10%)

1 no. Malus sylvestris
2 no. Sorbus aucuparia
3 no. Carpinus betulus
1 no. Fagus sylvatica
2 no. Tilia cordata
1 no. Fagus sylvatica
150 no. Juncus effusus
150 no. Molinia caerulea
1 no. Prunus avium

Native Scrub Planting - Wet (394 m²)
99 no. Crataegus monogyna (25%)
59 no. Frangula alnus (15%)
39 no. Salix cinerea (10%)
79 no. Salix purpurea (20%)
39 no. Salix viminalis (10%)
79 no. Viburnum opulus (20%)

Defensible Shrub Planting to SuDS Feature (145 m2)
174 no. Berberis darwinii (30%)
232 no. Crataegus monogyna (40%)
58 no. Ilux aquifolium (10%)
39 no. Prunus spinosa (15%)
29 no. Rosa arvensis (5%)

SWDR PLANTING REFER TO WMHP-TG-SRWG1-DR-LS-3008 for further details

Coir planting logs

Woodland Mix (855 m²)
21 no. Acer campestre (10%)
21 no. Corylus avellana (10%)
21 no. Crataegus monogyna (10%)
21 no. Populus tremula (10%)
16 no. Prunus avium (7.5%)
21 no. Quercus robur (t) (10%)
11 no. Quercus robur (5%)
21 no. Sorbus aucuparia (10%)
21 no. Sorbus torminalis (10%)
16 no. Tilia cordata (7.5%)
21 no. Viburnum opulus (10%)

3 no. Acer campestre
2 no. Quercus robur
2 no. Salix caprea
2 no. Populus nigra betulifolia
144 no. Juncus effusus
144 no. Molinia caerulea
2 no. Malus sylvestris
2 no. Tilia cordata
1 no. Fagus sylvatica
Dog beach
3 no. Corylus avellana (ms)
Dog beach
126 no. Juncus effusus
126 no. Molinia caerulea
2 no. Prunus avium
3 no. Acer campestre
Emm Brook
1 no. Two person seat
1 no. Fagus sylvatica
3 no. Populus nigra betulifolia
1 no. Two person seat
3 no. Ulmus 'New Horizon'

Woodland Mix (2873 m²)
71 no. Acer campestre (10%)
71 no. Corylus avellana (10%)
71 no. Crataegus monogyna (10%)
71 no. Populus tremula (10%)
53 no. Prunus avium (7.5%)
71 no. Quercus robur (t) (10%)
35 no. Quercus robur (5%)
71 no. Sorbus aucuparia (10%)
71 no. Sorbus torminalis (10%)
53 no. Tilia cordata (7.5%)
71 no. Viburnum opulus (10%)

1 no. Wayfinding
2 no. Carpinus betulus
2 no. Sorbus aucuparia
2 no. Carpinus betulus
2 no. Populus tremula
1 no. Two person seat
1 no. Quercus robur
1 no. Tilia cordata
Coir planting logs
1 no. Tilia cordata
1 no. Tilia cordata
2 no. Fagus sylvatica
3 no. Quercus robur
1 no. Tilia cordata
2440 no. Leucojum aestivum
489 no. Juncus effusus
489 no. Molinia caerulea
3 no. Acer campestre
1 no. Path through RPA
Native Hedgerow Mix (107 lin. m)
80 no. Acer campestre (15%)
107 no. Corylus avelana (20%)
107 no. Crataegus monogyna (20%)
27 no. Frangula alnus (5%)
54 no. Malus sylvestris (10%)
27 no. Prunus spinosa (5%)
54 no. Rhamnus cathartica (10%)
27 no. Rosa canina (5%)
27 no. Salix caprea (5%)
27 no. Ulex europaeus (5%)

Woodland Mix (6801 m²)
170 no. Acer campestre (10%)
170 no. Corylus avellana (10%)
170 no. Crataegus monogyna (10%)
170 no. Populus tremula (10%)
128 no. Prunus avium (7.5%)
170 no. Quercus robur (t) (10%)
85 no. Quercus robur (5%)
170 no. Sorbus aucuparia (10%)
170 no. Sorbus torminalis (10%)
128 no. Tilia cordata (7.5%)
170 no. Viburnum opulus (10%)

1 no. Malus sylvestris
1 no. Prunus avium
1 no. Two person seat
148 no. Juncus effusus
148 no. Molinia caerulea
Native Shrub Planting (720 m²)
144 no. Corylus avellana (20%)
252 no. Crataegus monogyna (35%)
72 no. Frangula alnus (10%)
72 no. Ilex aquifolium (10%)
36 no. Prunus spinosa (5%)
36 no. Rosa arvensis (5%)
36 no. Rosa canina (5%)
72 no. Viburnum opulus (10%)

Woodland Edge Mix (2105 m²)
185 no. Cornus avellana (20%)
185 no. Crataegus monogyna (20%)
93 no. Frangula alnus (10%)
93 no. Ilex aquifolium (10%)
46 no. Prunus spinosa (5%)
93 no. Rhamnus cathartica (10%)
46 no. Ribes uva-crispa (5%)
46 no. Rosa arvensis (5%)
46 no. Rosa canina (5%)
93 no. Viburnum opulus (10%)

3 no. Sorbus aucuparia
1 no. Ulmus 'New Horizon'
Native Hedgerow Mix (277 lin. m)
208 no. Acer campestre (15%)
277 no. Corylus avelana (20%)
277 no. Crataegus monogyna (20%)
69 no. Frangula alnus (5%)
139 no. Malus sylvestris (10%)
69 no. Prunus spinosa (5%)
139 no. Rhamnus cathartica (10%)
69 no. Rosa canina (5%)
69 no. Salix caprea (5%)
69 no. Ulex europaeus (5%)

1 no. Salix alba
1 no. Tilia cordata
1 no. Two person seat
1 no. Sorbus aucuparia
1 no. Tilia cordata

Woodland Edge Mix (853 m²)
75 no. Cornus avellana (20%)
75 no. Crataegus monogyna (20%)
38 no. Frangula alnus (10%)
38 no. Ilex aquifolium (10%)
19 no. Prunus spinosa (5%)
38 no. Rhamnus cathartica (10%)
19 no. Ribes uva-crispa (5%)
19 no. Rosa arvensis (5%)
19 no. Rosa canina (5%)
38 no. Viburnum opulus (10%)

Refer to NBS Hard and Soft Landscape Specification P19-0052_63 for further details.

Note: Final locations for all benches, picnic tables, litter bins, dog waste bins, and information boards to be confirmed in the field before final installation.

Refer to drawing P19-0052_09 Sheet 5

Holme Park SANG - Holme Park SANG - Detailed Soft Landscaping Proposals Sht4of7

| PEGASUSGROUP.CO.UK | TEAM/DRAWN BY: ASK | APPROVED BY: IBD | DATE: 12/08/2026 | SCALE: 1:500@A1 | DRWG: P19-0052_EN_139-04C | CLIENT: Kier Ventures Ltd and Miller Homes |

PEGASUS GROUP