

notes

All dimensions must be checked by the contractor before commencing work on site.
No deviation from this drawing will be permitted without the prior written consent of the Architect.
This drawing is to be read with all relevant Morse Webb Ltd, Structural, M&E and Specialist drawings, reports and specifications. Any discrepancies in dimensions or details on or between these drawings / reports / specifications should be brought to the attention of Morse Webb Ltd in writing for clarification.
Refer to S.Eng drawings and documents for specified repairs to existing timber structure.

Key

Areas to be affected by opening up works,

Areas for paint removal system to be tested.



Infill panel to be investigated externally to determine render and brickwork. 300mm² internal drylining removed above skirting level to correspond with external works to infill panel.

Sill plate below IP09 and timber frame to the right of IP09 to be investigated externally to determine effective product and method to remove existing impervious paint finish.

Paint and render on plinth removed between sill plate and ground level. Area below IP09 to be removed.

01/22.08.2024 Areas for test paint removal shown
00/24.04.2024 LBC Application
revision/date note



morsewebb

architects

The Byre The Street Bramley Hampshire RG26 5DE
T: 01256 587888 W: www.morsewebb.co.uk

project

1 Radstock Farm Cottages, Earley

title

Front (SW) Elevation Opening Up

scale	status	
1:50@A3	PLANNING	
job no.	dwg no.	status/revision
972	SK01	PL01

© Morse Webb Ltd

01 FRONT (SOUTH-WEST) ELEVATION OPENING UP

1:50

