



Infrastruct CS Ltd
The Stable
High Cogges Farm
High Cogges
Nr Witney
Oxon
OX29 6UN

FLOOD RISK ASSESSMENT

Scheme name:
Transformer, Crane House, Molly Millar's Lane,
Wokingham, Berks, RG41 2QP

Document reference: **6314-MILL-ICS-XX-RP-C-07.001**

Report Prepared By:
Reno Sam Ireanius
MSc, B.Tech, GMICE

Report Checked By:
Richard White
BSc (Hons), CEnv, CWem, IEng, MCIWEM

Report Authorised By:
Mateo Blanco
MEng CEng MICE

March 2026
Project Number: **6314**



Original Date:	23rd April 2025
Project Number:	6314
Project Name:	Transformer, Crane House, Molly Millar's Lane, Wokingham, Berks, RG41 2QP
Prepared By:	Reno Ireanius
Prepared For:	E T Planning

Document Revision Record

Issue	Checked By	Date	Description
P01	RJW	23 rd April 2025	Initial Issue
P02	RJW	8 th May 2025	Location clarified
P03	RJW	26 th September 2025	EA comments added. Level raised.
P04	RJW	12 th February 2026	Flood compensation section added
P05	RJW	24 th March 2026	Development boundary updated

Foreword

This document has been prepared solely as a Flood Risk Assessment for the Client, E T Planning. No responsibility or liability will be accepted for any use that is made of this document other than by the Client for the purpose for which it was written. The conclusions resulting from this study and contained within this report are not necessarily indicative of future conditions or operating practices at or adjacent to the site.

No person other than the client may copy use or rely on the contents of this document without prior permission.

Some of the information presented within this report is based on third-party information which is believed to be correct; no liability will be accepted for any discrepancies inaccuracies, mistakes or omissions in such information. The report assesses the flood risk in relation to the requirements of the Environment Agency and as such assesses the site for a specific flood event and not all flood events. The contents of this document must not be copied or reproduced in whole or in part without the written consent of Infrastruct CS Ltd.



Table of Contents

1.0	SUMMARY	5
2.0	INTRODUCTION.....	6
2.1	COMMISSION	6
2.2	GUIDANCE	6
2.3	AIMS AND OBJECTIVES.....	6
3.0	SITE DETAILS.....	7
3.1	LOCATION.....	7
3.2	GRID REFERENCE	9
3.3	TOPOGRAPHY AND SITE DESCRIPTION	9
3.4	GROUND CONDITIONS	9
3.5	GROUNDWATER	11
3.6	EXISTING WATERCOURSES.....	11
3.7	ENVIRONMENT AGENCY GROUNDWATER AND AQUIFER PROTECTION	12
4.0	PROPOSED DEVELOPMENT	13
5.0	LOCAL PLANNING POLICY AND GUIDANCE	14
5.1	NATIONAL PLANNING POLICY AND GUIDANCE	14
5.2	WOKINGHAM BOROUGH LOCAL PLAN.....	16
6.0	FLOOD RISK POLICY	17
6.1	ENVIRONMENT AGENCY FLOOD MAP	17
6.2	FLOOD MODELLING RESULTS FOR THE DEVELOPMENT SITE.....	17
6.3	LEVEL FOR LEVEL FLOOD COMPENSATION MODELLING.....	20
6.4	PROPOSED TRANSFORMER LEVELS	21
6.5	THE NATIONAL PLANNING POLICY FRAMEWORK	21
6.6	FLOOD ZONE DEFINITION.....	22
6.7	FLOOD ZONES – TABLE 1 PPG.....	22
6.8	FLOOD RISK VULNERABILITY CLASSIFICATION - EXTRACT FROM TABLE 2 PPG	23
6.9	FLOOD RISK VULNERABILITY & FLOOD ZONE COMPATIBILITY TABLE	23
7.0	OTHER SOURCES OF FLOOD RISK TO THE DEVELOPMENT	24
7.1	FLOODING FROM OVERLAND FLOWS.....	24
7.2	FLOODING FROM RISING GROUNDWATER	25
7.3	FLOODING FROM THE LOCAL SEWERAGE NETWORK	26
7.4	FLOODING FROM RESERVOIRS, CANALS & OTHER ARTIFICIAL SOURCES.....	27
8.0	RECOMMENDATIONS AND CONCLUSION	27
9.0	REFERENCES & BIBLIOGRAPHY	27
	APPENDIX A - TOPOGRAPHIC SURVEY	28
	APPENDIX B - DEVELOPMENT PROPOSALS.....	29
	APPENDIX C - FLOOD ZONE MAP	30
	APPENDIX D - PRODUCT 4 REPORT	31
	APPENDIX E - EA COMMENTS 03/09/2025.....	32



APPENDIX F - FLOOD COMPENSATION MAP	33
---	----

1.0 Summary

A Flood Risk Assessment (FRA) and drainage strategy has been undertaken to accompany the planning application for the placement of a new transformer at Crane House, Molly Millar's Lane, Wokingham, Berks, RG41 2QP. Infrastruct CS Ltd has prepared this report on behalf of E T Planning in accordance with the guidelines set out in the National Planning Policy Framework.

The following table is an overview of the flood risk assessment for the proposed development of the site, based upon currently available information, and finds the following –

ITEM	RESPONSE
Site Location	The proposed transformer location is within an industrial estate accessed from Molly Millar's Lane in Wokingham, Berkshire, which is bound to the east by the 'North Downs Line' railway, with Molly Millar's Lane to the south and Ashville Way to the North. The site is 0.5 miles south of Wokingham Railway Station. The approximate grid reference is 480690E, 167934N.
Size and Current Land Usage	The proposed transformer location is approximately 20m² in plan and is currently a portion of the car park area.
Flood Zone	The proposed transformer location falls entirely within Flood Zone 2, which is classified as medium probability of flooding.
Fluvial Flood Risk	Medium – Refer to Section 6.1
Overland Flood Risk	Low – Refer to Section 7.1
Groundwater Flood Risk	Low – Refer to Section 7.2
Sewerage Flood Risk	Low – Refer to Section 7.3
Artificial Flood Risk	Low – Refer to Section 7.4
Proposed Development	The current proposals involve the placement of a new transformer between the Intersurgical building and its car park.

Based on this assessment, it is concluded that in accordance with the Flood risk vulnerability and flood zone compatibility table in Section 6.7 of the Planning Practice Guidance document, the report considers the proposed development appropriate.



2.0 Introduction

2.1 Commission

ET Planning has commissioned Infrastruct CS Ltd, to prepare a Flood Risk Assessment (FRA) to support a planning application for a new transformer at Crane House, Molly Millar's Lane, Wokingham, Berks, RG41 2QP.

2.2 Guidance

This flood risk assessment has been compiled in accordance with the recommendations of the National Planning Policy Framework (NPPF) and the Planning Practice Guidance (PPG).

2.3 Aims and Objectives

The purpose of this flood risk assessment is to assess the potential flood risks by and to the proposed development. It will identify the flood risk zone, potential sources of flood risk and will be used to support the proposed planning application.

3.0 Site Details

3.1 Location

The site is within an industrial estate accessed from Molly Millar's Lane in Wokingham, Berkshire, which is bound to the east by the 'North Downs Line' railway, with Molly Millar's Lane to the south and Ashville Way to the North. The site is 0.5 miles south of Wokingham Railway Station. The proposed transformer location is to the north of the Intersurgical building.




Figure 3.1.1 - Site Context



Figure 3.1.2 - Site location




Figure 3.1.3 - Image from Google Earth



Figure 3.1.4 - Image from Google Earth



Figure 3.1.5 – Image from Google Earth

3.2 Grid Reference

The Ordnance Survey National grid reference for the centre of the site is:

480690E, 167934N (Nat Grid SU 80690 67934)

3.3 Topography and Site Description

The proposed transformer location covers an approximate area of 20 m² and is situated at Crane House, Molly Millar's Lane, Wokingham, Berks, RG41 2QP.

The current topographic levels of the proposed transformer location is flat. Refer to the Appendix for a copy of the topographic survey.

3.4 Ground Conditions

To date, no intrusive ground investigation has taken place on-site; however, reference to the Geological Survey of Great Britain indicates the following strata:

Superficial deposits: Alluvium - Clay, silt, sand, and gravel. Sedimentary superficial deposit formed between 11.8 thousand years ago and the present during the Quaternary period.

Head - Clay, silt, sand and gravel. Sedimentary superficial deposit formed between 2.588 million years ago and the present during the Quaternary period.




Figure 3.4.1 – Superficial Deposit map from BGS online

Bedrock geology: London Clay Formation - Clay, silt and sand. Sedimentary bedrock formed between 56 and 47.8 million years ago during the Palaeogene period.



Figure 3.4.2 – Bedrock Deposit map from BGS online

Intrusive site investigations carried out adjacent/near the development and shown on the British Geological Survey database (BGS ID: 432324, BGS Ref: SU86NW5, British NGR: 480860,167900) Showed the following strata:

NATURE OF STRATA (and any additional remarks).	THICKNESS		DEPTH	
	Feet.	Inches.	Feet.	Inches.
Blue Clay	272	-	272	-
Brown Clay	21	-	293	-
Red Clay	5	-	298	-
Silver Sand	17	-	315	-
Grey Sand	3	-	318	-
Loamy Sand	7	-	325	-
Sand and thin Clay band	2	-	327	-
Blue Clay	4	-	331	-
Claystone and Sand	11	-	342	-
Chalk	695	-	1037	-
Sandstone	36	-	1073	-
Blue Marly Sandstone	58	-	1131	-
Gault				
London Clay	272	-	272	-
Reading Bed	73	6	345	6
Upper Chalk	324	6	670	-
Middle Chalk	170	-	840	-
Lower Chalk	194	-	1034	-
Upper Green Sand	56	-	1090	-
Gault	310	-	1400	-

Figure 3.4.2 – Borehole Records from British Geological Survey (BGS ID: 432324, BGS Ref: SU86NW5)

3.5 Groundwater

Boreholes carried out in the vicinity of the site found groundwater within the trial pits at 12.2mbgl. Further in-situ testing is required to confirm the groundwater depth within the site. The anticipated strata for the site do not lend itself to groundwater flooding, with the clay soils acting as a natural aquiclude.

3.6 Existing Watercourses

The nearest main river watercourses to the site are Emm Brook (directly to the south of the existing parking serving Brook House) and Barkham Brook (1.8km to the south-west), tributaries of the River Loddon which is located 4.8km north-west of the site.




Figure 3.6 – Local Rivers

3.7 Environment Agency Groundwater and Aquifer Protection

Reference to the Environment Agency Groundwater Protection Zone Map shows the area is sited outside all groundwater protection zone. The Environment Agency has defined Source Protection Zones (SPZs) for groundwater sources such as wells, boreholes, and springs used for public drinking water supply. These zones show the risk of contamination from any activities that might cause pollution in the area. The closer the activity, the greater the risk.




Figure 3.7.1 – Groundwater Protection Zones

The Environment Agency uses the zones to set up pollution prevention measures in areas at a higher risk and to monitor the activities of potential polluters nearby.

A study of the aquifer maps on the Environment Agency website revealed the site to be located within a Secondary A superficial aquifer and bedrock aquifer.

Secondary A - permeable layers capable of supporting water supplies at a local rather than strategic scale and, in some cases, forming an important source of base flow to rivers. These are generally aquifers formerly classified as minor aquifers;




Figure 3.7.2 – Aquifer Designation Map – Superficial




Figure 3.7.3 – Aquifer Designation Map – Bedrock

4.0 Proposed Development

The current proposals involve the placement of a new transformer between the Intersurgical building and its car park. The proposed development plans can be found in Appendix B.

5.0 Local Planning Policy and Guidance

5.1 National Planning Policy and Guidance

The NPPF sets out government's planning policies for England and how these are expected to be applied. The NPPF seeks to ensure that flood risk is taken into account at all stages in the planning process and is appropriately addressed.

Footnote 63 of the NPPF states that a site-specific flood risk assessment should be submitted for all development proposed in flood zone 2 and flood zone 3 whilst in flood zone 1, an assessment should accompany all proposals involving:

- sites of 1 ha or more;
- land identified as having critical drainage problems or as being at increased flood risk in future;
- or land that may be subject to other sources of flooding, where its development would introduce a more vulnerable use.

NPPF paragraph 170 states that “inappropriate development in areas at risk of flooding should be avoided by directing development away from areas at highest risk (whether existing or future). Where development is necessary in such areas, the development should be made safe for its lifetime without increasing flood risk elsewhere”.

Paragraph 172 of the NPPF states that all plans should apply a sequential, risk-based approach to the location of development – taking into account all sources of flood risk and the current and future impacts of climate change – so as to avoid, where possible, flood risk to people and property. They should do this, and manage any residual risk, by:

- a) applying the sequential test and then, if necessary, the exception test as set out below;
- b) safeguarding land from development that is required, or likely to be required, for current or future flood management;
- c) using opportunities provided by new development and improvements in green and other infrastructure to reduce the causes and impacts of flooding, (making as much use as possible of natural flood management techniques as part of an integrated approach to flood risk management); and
- d) where climate change is expected to increase flood risk so that some existing development may not be sustainable in the long-term, seeking opportunities to relocate development, including housing, to more sustainable locations.

NPPF paragraph 173 states that “a sequential risk-based approach should also be taken to individual applications in areas known to be at risk now or in future from any form of flooding, by following the steps set out below”.

NPPF paragraph 176 states that “applications for some minor development and changes of use⁶² should also not be subject to the sequential test, nor the exception test set out below, but should still meet the requirements for site-specific flood risk assessments set out in footnote 63”.

NPPF paragraph 178 states that the application of the exception test should be informed by a strategic or sitespecific flood risk assessment, depending on whether it is being applied during plan production or at the application stage. To pass the exception test it should be demonstrated that:

- a) the development would provide wider sustainability benefits to the community that outweigh the flood risk; and
- b) the development will be safe for its lifetime taking account of the vulnerability of its users, without increasing flood risk elsewhere, and, where possible, will reduce flood risk overall.

NPPF Paragraph 179 states that “both elements of the exception test should be satisfied for development to be permitted”.

NPPF paragraph 181 states that “When determining any planning applications, local planning authorities should ensure that flood risk is not increased elsewhere. Where appropriate, applications should be supported by a site-specific flood-risk assessment.

Development should only be allowed in areas at risk of flooding where, in the light of this assessment (and the sequential and exception tests, as applicable) it can be demonstrated that:

- a) within the site, the most vulnerable development is located in areas of lowest flood risk, unless there are overriding reasons to prefer a different location;
- b) the development is appropriately flood resistant and resilient such that, in the event of a flood, it could be quickly brought back into use without significant refurbishment;
- c) it incorporates sustainable drainage systems, unless there is clear evidence that this would be inappropriate;
- d) any residual risk can be safely managed; and
- e) safe access and escape routes are included where appropriate, as part of an agreed emergency plan.

NPPF paragraph 182 states that applications which could affect drainage on or around the site should incorporate sustainable drainage systems to control flow rates and reduce volumes of runoff, and which are proportionate to the nature and scale of the proposal.

These should provide multifunctional benefits wherever possible, through facilitating improvements in water quality and biodiversity, as well as benefits for amenity. Sustainable drainage systems provided as part of proposals for major development should:

- a) take account of advice from the Lead Local Flood Authority;
- b) have appropriate proposed minimum operational standards; and
- c) have maintenance arrangements in place to ensure an acceptable standard of operation for the lifetime of the development.

5.2 Wokingham Borough Local Plan

CP1- Sustainable development

Planning permission will be granted for development proposals that:

- 1) Maintain or enhance the high quality of the environment;
- 2) Minimise the emission of pollutants into the wider environment;
- 3) Limit any adverse effects on water quality (including groundwater);
- 4) Ensure the provision of adequate drainage;
- 5) Minimise the consumption and use of resources and provide for recycling;
- 6) Incorporate facilities for recycling of water and waste to help reduce per capita water consumption;
- 7) Avoid areas of best and most versatile agricultural land;
- 8) Avoid areas where pollution (including noise) may impact upon the amenity of future occupiers;
- 9) Avoid increasing (and, where possible, reduce) risks of or from all forms of flooding (including from groundwater);
- 10) Provide attractive, functional, accessible, safe, secure and adaptable schemes;
- 11) Demonstrate how they support opportunities for reducing the need to travel, particularly by private car in line with CP6 and
- 12) Contribute towards the goal of reaching zero-carbon developments⁴¹ as soon as possible by:
 - a) Including appropriate on-site renewable energy features and
 - b) Minimising energy and water consumption by measures including the use of appropriate layout and orientation, building form, design and construction, and design to take account of microclimate to minimise carbon dioxide emissions through giving careful consideration to how all aspects of development form.

6.0 Flood Risk Policy

6.1 Environment Agency Flood Map

The flood map for the development site shown below suggests that the proposed transformer location falls within:

Flood Zone 2, which is defined as land assessed as having between a 1 in 100 (1%) and 1 in 1,000 (0.1%) annual probability of river flooding; or land having between a 1 in 200 (0.5%) and 1 in 1,000 (0.1%) annual probability of sea flooding.




Figure 6.1 - Environment Agency © 2017 - Flood Zone map

It is, therefore, the consideration of this FRA that the site has a medium risk of flooding from fluvial sources.

6.2 Flood Modelling Results for the Development Site

As part of the information gathering exercise, a product 4 flood data request was made from the Environment Agency. This document provided specific flood level nodes for the development site, which could then be related to the detailed topographic survey, so an actual flood impact assessment of the site could be made.

The data provided by the Environment Agency was modelled using the Loddon (Lower Tribs) 2007 detailed mapping project and undertaken with the ESTRY TUFLOW modelling software. The site was then further assessed using five model areas: Emm Brook (Wokingham), Emm Brook (Upstream), Ashridge Stream, Waterloo Road Stream. (See full document in Appendix D).




Figure 6.2.1 – Product 4 Report – Node Location

For the basis of this report, the site will be solely assessed on the 1 in 100yr and 1 in 100yr event plus climate change in accordance with the NPPF recommendations.

As such the Environment Agencies flood model for the development site provided the following levels for the 1 in 100yr and 1 in 100yr event plus climate change:

Floodplain Reference	1 in 20yr	1 in 100yr	1 in 100yr + 20% climate change	1 in 100yr + 35% climate change	1 in 100yr + 70% climate change	1 in 1000yr
06324LO_MN_Emm2.61R1.1	49.40m	49.76m	49.94m	-	-	-
06324LO_MN_Emm2.62a.2	49.43m	49.76m	50.00m (25%)	-	-	-
06324LO_MN_Emm2.62a.1	49.53m	49.86m	50.03m	-	-	-

As the Product 4 report issued by the Environmental Agency lacks detailed information, the precise extent of Flood Zone 2 remains uncertain. Also, we have interpolated the flood levels to establish a level margin between Flood Zones 3a and 3b.

As illustrated in Image 6.2.2, the flood levels for various return periods have been overlaid onto the topographic survey. Based on this analysis, the proposed transformer location falls within Flood Zone 2, which is considered a safe placement. Additionally, to further enhance safety measures, the transformer will be elevated 600mm above ground level.

The transformer is considered essential infrastructure meaning a higher central allowance should be used. The DEFRA website suggests that for the 2080s event, climate change values of 14% should be used for the central allowance and 23% for the higher central for the Loddon (Lower Tribs). The SFRA for Wokingham puts the value for the Emm Brook as 25% for the 2030s higher central. In line with guidance from the EA a flood level has been interpolated.




Figure 6.2.2 – Flood Zone map created using civil 3D from product 4 report

Therefore, this FRA states that the site is generally at a *medium* risk of flooding from fluvial sources. However, raising the proposed transformer at 50.30m, 300mm above the 1 in 100 year + 25% event without affecting the floodplain will significantly lower this risk to *very low*.

6.3 Level for Level Flood Compensation Modelling

The proposed transformer will be installed on a raised platform to ensure it remains operational during flood events, including the 1 in 100-year fluvial flood with a 25% allowance for climate change. While the raised platform initially displaces a small volume of floodwater, a detailed level-for-level flood compensation assessment has been undertaken in accordance with Planning Practice Guidance (Flood Risk and Coastal Change). This assessment demonstrates that the proposed regrading immediately to the north of the transformer (shown as the yellow area in Figure 6.3.2) increases the floodplain storage to 4.291m³.

This increase in floodplain storage ensures no net loss of floodplain capacity and provides a small enhancement to the floodplain's ability to store water during extreme flood events, thereby contributing positively to flood risk management. See Appendix F for the Flood Compensation Map.




Figure 6.3.1 – Level for level flood compensation map – Existing




Figure 6.3.2 - Level for level flood compensation map – Proposed

Flood Slice	Existing Volume A (m3) Fig 6.3.1	Proposed Volume B (m3) Fig 6.3.2	Total Volume Gain within band B-A (m3)
50.00m – 49.90m	1040.701	1041.100	+0.399
49.90m – 49.80m	957.486	960.108	+2.622
49.80m – 49.70m	855.047	856.043	+0.996
49.70m – 49.60m	789.199	789.464	+0.265
49.60m – 49.50m	744.650	744.659	+0.009
49.50m – 49.40m	714.081	714.081	0.000
49.40m – 49.30m	693.747	693.747	0.000
49.30m – 49.20m	675.633	675.633	0.000
49.20m – 49.10m	659.972	659.972	0.000
49.10m – 49.00m	641.455	641.455	0.000
49.00m – 48.90m	618.995	618.995	0.000
48.90m – 48.80m	590.079	590.079	0.000
48.80m – 48.70m	543.466	543.466	0.000
48.70m – 48.60m	493.427	493.427	0.000
48.60m – 48.50m	399.147	399.147	0.000
48.50m – 48.40m	197.005	197.005	0.000
48.40m – 48.30m	97.002	97.002	0.000
48.30m – 48.20m	64.063	64.063	0.000
48.20m – 48.10m	43.177	43.177	0.000
48.10m – 48.00m	27.628	27.628	0.000
48.00m – 47.90m	17.881	17.881	0.000
47.90m – 47.80m	10.624	10.624	0.000
47.80m – 47.70m	5.450	5.450	0.000
47.70m – 47.60m	2.287	2.287	0.000
47.60m – 47.50m	0.698	0.698	0.000
47.50m – 47.40m	0.084	0.084	0.000
47.40m – 47.30m	0.000	0.000	0.000
Total	10,882.984	10,887.275	+ 4.291

Table 6.3.1 – Flood Level Comparison

6.4 Proposed Transformer Levels

The transformer should be set higher than 50.30m, which is 300mm above the 1 in 100 years + 20% event.

6.5 The National Planning Policy Framework

The National Planning Policy Framework (NPPF) and the accompanying Planning Practice Guidance (PPG) gives direction for development with respect to flooding. These documents promote a sequential approach to encourage development away from areas that may be or are susceptible to flooding. In doing so it categorizes flood zones in the context of their probability of flooding, as shown in the table within Section 6.3 below.

6.6 Flood Zone Definition

The National Planning Policy Framework Definition of Flood Zones

Flood zone	Fluvial	Tidal	Probability of flooding
1	< 1 in 1000 year	<1 in 1000 year	Low probability
2	Between < 1 in 1000 year and 1 in 100 year	Between <1 in 1000 year and 1 in 200 year	Medium Probability
3a	> 1 in 100 year	> 1 in 200 year	High probability
3b	Either > 1 in 30 (3.3%) or as agreed between the EA and the LPA	Either > 1 in 30 or as agreed between the EA and the LPA	Functional flood plain

6.7 Flood Zones – Table 1 PPG

(Note: These Flood Zones refer to the probability of river and sea flooding, ignoring the presence of defences)

Zone 2 - Medium Probability	
Definition	
	Land having between a 1 in 100 and 1 in 1,000 annual probability of river flooding; or land having between a 1 in 200 and 1 in 1,000 annual probability of sea flooding.
Appropriate uses	
	Essential infrastructure and the water-compatible, less vulnerable and more vulnerable uses of land and essential infrastructure in (Table 2 NPPF) are appropriate in this zone. Subject to the Sequential Test being applied, the highly vulnerable uses in Table 2 are only appropriate in this zone if the Exception Test is passed.
FRA requirements	
	All development proposals in this zone should be accompanied by a FRA.
Policy aims	
	In this zone, developers and local authorities should seek opportunities to reduce the overall level of flood risk in the area through the layout and form of the development, and the appropriate application of sustainable drainage techniques.

6.8 Flood Risk Vulnerability Classification - Extract from Table 2 PPG

Essential infrastructure

- Essential transport infrastructure (including mass evacuation routes) which has to cross the area at risk.
- Essential utility infrastructure which has to be located in a flood risk area for operational reasons, including infrastructure for electricity supply including generation, storage and distribution systems; including electricity generating power stations, grid and primary substations storage; and water treatment works that need to remain operational in times of flood.
- Wind turbines.
- Solar farms.

6.9 Flood Risk Vulnerability & Flood Zone Compatibility Table

Vulnerability classification flood zone	Essential infrastructure	Highly vulnerable	More vulnerable	Less vulnerable	Water compatible
1	✓	✓	✓	✓	✓
2	✓	Exception test required	✓	✓	✓
3a †	Exception test required (†)	X	Exception test required	✓	✓
3b *	Exception test required (*)	X	X	X	✓ (*)

✓ Development is appropriate X development is not appropriate

Notes to table 2:

- This table does not show the application of the Sequential Test which should be applied first to guide development to the lowest flood risk areas; nor does it reflect the need to avoid flood risk from sources other than rivers and the sea;
- The Sequential and Exception Tests do not need to be applied to those developments set out in National Planning Policy Framework footnote 62. The Sequential and Exception Tests should be applied to 'major' and 'non major' development;
- Some developments may contain different elements of vulnerability and the highest vulnerability category should be used, unless the development is considered in its component parts.

“†” In Flood Zone 3a essential infrastructure should be designed and constructed to remain operational and safe in times of flood.

“*” In Flood Zone 3b (functional floodplain) essential infrastructure that has passed the Exception Test, and water-compatible uses, should be designed and constructed to:

- remain operational and safe for users in times of flood;
- result in no net loss of floodplain storage;
- not impede water flows and not increase flood risk elsewhere.

The above table, taken from PPG (Table 3), confirms that the proposed transformer location within Flood Zone 2 is an appropriate development.

7.0 Other Sources of Flood Risk to The Development

In addition to the potential for assessing flooding from fluvial and tidal sources NPPF also requires that consideration is given to other mechanisms for flooding:

- Flooding from land – intense rainfall, often in short duration, that is unable to soak into the ground or enter drainage systems, can run rapidly off land and result in local flooding.
- Flooding from groundwater – occurs when water levels in the ground rise above the surface elevations.
- Flooding from sewers – In urban areas, rainwater is frequently drained into surface water sewers or sewers containing both surface and wastewater sewers known as combined sewers. Flooding can result causing surcharging when the sewer is overwhelmed by heavy rainfall.
- Flooding from reservoirs, canals and other artificial sources – Non-natural or artificial sources of flooding can result from sources such as reservoirs, canals lakes etc, where water is held above natural ground levels.

7.1 Flooding from Overland Flows

The risk of flooding due to overland flood flows is low by the Environment Agency. The surface water flood data for the site, shown below, indicates that there is high flood risk to the north of the site, but very low risk to the proposed transformer location.




Fig 7.1.1 – Environment Agency © 2017 - Flood Risk from Surface Water map




Figure 7.1.2 – Surface Water Flood Zone Map from ArcGIS Map

It is, therefore, the consideration of this FRA that the site has a **low** risk of flooding from overland flows.

7.2 Flooding from Rising Groundwater

Groundwater flooding is dependent on local variations in topography, geology and soils. The causes of groundwater flooding are generally understood; however it is difficult to predict the actual location, timing and extent of groundwater flooding without comprehensive datasets.

There is a lack of reliable measured datasets to undertake flood frequency analysis and even with datasets, this analysis is complicated due to the non-independence of groundwater level data. Surface water flooding incidents are sometimes mistaken for groundwater flooding incidents, such as where runoff via infiltration seeps from an embankment, rather than locally high groundwater levels.

Section 3.5 of this report confirms that boreholes carried out in the vicinity of the site and, found groundwater at approximate depths of 12.2mbgl. Further testing is recommended to establish the groundwater levels along the whole site so the infiltration capacity if the SuDS features is not affected.

The Strategic Flood Risk Assessment by Wokingham Borough Council includes a map, that illustrates areas vulnerable to groundwater flooding (Figure 7.2). It indicates that the proposed site has a lower susceptibility to groundwater flooding.




Figure 7.2 – Area susceptible to groundwater flooding – SFRA by Wokingham Borough Council

It is, therefore, the consideration of this FRA that the site has a **low** risk of flooding from rising groundwater levels.

7.3 Flooding from the Local Sewerage Network

Sewer flooding generally results in localised short-term flooding caused by intense rainfall events overloading the capacity of sewers. Flooding from sewers can also occur as a result of blockage, poor maintenance or structural failure.

As the site is at a higher elevation than the road, it is likely that any sewer flooding would be contained within the public highway, away from the development.

It should be noted that much of the wider adopted sewer network dates back even to Victorian times, some of which is of unknown capacity and condition. More recent sewers are likely to have been designed to the guidelines in 'Sewers for Adoption' (WRC, 2006). These sewers tend to have a design standard of up to the 1 in 30 year storm event, although in many cases, it is thought that this design standard is not achieved, especially in privately owned systems.

There is, therefore, potential that parts of the existing sewer system could surcharge during large, high intensity rainstorm events resulting in frequent flooding, particularly if the systems are combined and if climate change forecasts are correct.

The on-site drainage has been subject to a CCTV survey, showing the sewers to generally be in a good condition.

The surface Water system, discharging to the Emm Brook appears to be in an acceptable condition, taking flows from the immediate surroundings.

According to the EA and Wokingham Borough Council, the nearest land drainage flooding incidents to the site are located at Denmark Street (A321) approximately 515m northeast and one at Barkham Road approximately 550m northwest of the site.

Localised flooding is possible if the capacity of the existing drainage network is exceeded.

It is, therefore, the consideration of this FRA that the site has a **low** risk of flooding by surcharging of the local sewer network.

7.4 Flooding from Reservoirs, Canals & Other Artificial Sources

Reservoirs in the UK have an extremely good safety record. The EA is the enforcement authority for the Reservoirs Act 1975 in England and Wales. All large reservoirs must be inspected and supervised by reservoir panel engineers. It is assumed that these reservoirs are regularly inspected, and essential safety work is carried out. These reservoirs therefore present a minimal risk.

Flooding may result from the failure of engineering installations including flood defence, land drainage pumps, sluice gates and floodgates. Hard defences may fail through the slow deterioration of structural components such as the rusting of sheet piling, erosion of concrete reinforcement and toe protection or the failure of ground anchors. This deterioration can be difficult to detect, so that failure, when it occurs, is often sudden and unexpected. Failure is more likely when the structure is under maximum stress, such as extreme fluvial events.

It must be noted that the EA have mapped the maximum flood extent in the event of reservoir breach. Their maps are an absolute worst-case scenario, which assumes reservoirs are full at the time of breach, that there are no emergency reservoir operating measures and that lots of different reservoirs fail at the same time.

There are no known reservoirs, canals or other artificial sources in the vicinity of the site.

It is, therefore, the consideration of this FRA that the site has a low risk of flooding by reservoirs, canals or other artificial sources.

8.0 Recommendations and Conclusion

Flood risk to the site has been assessed, and where risks have been deemed above low, mitigation measures have been proposed to reduce the risk to the site.


Therefore, in line with the recommendations of the National Planning Policy Framework, the development site lies within land classified as flood zone 2, which is considered at a medium risk of flooding, and therefore appropriate for a development of this nature. Having assessed the other forms of flood risk to and from the development site, this report finds that the site is not considered at high risk from any other sources of flooding.

9.0 References & Bibliography

- The National Planning Policy Framework December 2024
- Planning Practice Guidance.
- Environment Agency - Rainfall-Runoff Management for Developments
- Environment Agency indicative flood maps <https://flood-map-for-planning.service.gov.uk/>
- Environment Agency indicative groundwater source protection zone maps <http://www.natureonthemap.naturalengland.org.uk/MagicMap.aspx>
- Environment Agency indicative Aquifer designation maps <https://magic.defra.gov.uk/>
- <https://www.bgs.ac.uk/information-hub/borehole-records/>
- <https://geologyviewer.bgs.ac.uk/>
- Wokingham Borough Local Plan Strategic Flood Risk Assessment.
- Flood Estimation Handbook



Appendix A - Topographic Survey






Appendix B - Development Proposals







Emm Brook


PRESTIGE
CHAUFFEURS OF...

Google Maps





Appendix C - Flood Zone Map



- NOTES**
1. All dimensions and levels are in metres unless otherwise noted
 2. This drawing is to be read in conjunction with the relevant Architect's/Engineer's drawings, specifications and CDM documentation
 3. This drawing has been produced electronically and may have been photo reduced or enlarged when copied. Work to figured dimensions only (DO NOT SCALE - EXCEPT FOR PLANNING PURPOSES). All dimensions to be checked on site. Any errors or omissions to be reported to the engineer immediately.
 4. This drawing contains coloured lines / information that may not be clear if reproduced in black and white.
 5. Digital copies of this plan can only be considered accurate if supplied directly by Infrastruct CS Ltd.

	Flood Zone 2
	Flood Zone 3a
	Flood Zone 3b

P03	RSI	RJW	Proposed transformer location levels updated	24/03/26
P02	RSI	RJW	Flood Zone 2 levels changed	16/10/25
P01	RSI	RJW	Initial issue	23/04/25
REV	DRAWN	CHECK	REVISION COMMENTS	ISSUE DATE

DRAWING TITLE	SHEET NO.
Flood Zone Classification	1/1

PROJECT
Ready Power House,
Molly Millar's Lane, Wokingham,
RG41 2QP

CLIENT	 Infrastruct CS Ltd
ENGINEER	RJW
DRAWN	RSI
APPROVED	MBD

SCALE @ A1 1:500							0m 12.5m 25.0m			ENGINEER RJW	
PROJECT NUMBER 6314		STATUS S2		ISSUE PURPOSE INFORMATION			DRAFT RSI		This Drawing, Part of Contract No. 1000		

**Proposed
Transformer
Location**



Appendix D - Product 4 Report

Product 4 (Detailed Flood Risk) for **RG41 2RZ**

Our Ref: **THM352474**

Product 4 is designed for developers where Flood Risk Standing Advice FRA (Flood Risk Assessment) Guidance Note 3 Applies. This is:

- i) "all applications in Flood Zone 3, other than non-domestic extensions less than 250 sq metres; and all domestic extensions", and
- ii) "all applications with a site area greater than 1 ha" in Flood Zone 2.

Product 4 includes the following information:

Ordnance Survey 1:25k colour raster base mapping;
Flood Zone 2 and Flood Zone 3;
Relevant model node locations and unique identifiers (for cross referencing to the water levels, depths and flows table);
Model extents showing *defended* scenarios;
FRA site boundary (where a suitable GIS layer is supplied);
Flood defence locations (where available/relevant) and unique identifiers; (supplied separately)
Flood Map flood storage areas (where available/relevant);
Historic flood events outlines (where available/relevant, not the Historic Flood Map) and unique identifiers;

Statutory (Sealed) Main River (where available within map extents);

A table showing:

- i) Model node X/Y coordinate locations, unique identifiers, and levels and flows for *defended* scenarios.
- ii) Flood defence locations unique identifiers and attributes; (supplied separately)
- iii) Historic flood events outlines unique identifiers and attributes; and
- iv) Local flood history data (where available/relevant).

Please note:

If you will be carrying out computer modelling as part of your Flood Risk Assessment, please request our guidance which sets out the requirements and best practice for computer river modelling.

This information is based on that currently available as of the date of this letter. You may feel it is appropriate to contact our office at regular intervals, to check whether any amendments/ improvements have been made. Should you re-contact us after a period of time, please quote the above reference in order to help us deal with your query.

This information is provided subject to the enclosed notice which you should read.

This letter is not a Flood Risk Assessment. The information supplied can be used to form part of your Flood Risk Assessment. Further advice and guidance regarding Flood Risk Assessments can be found on our website at:



<https://www.gov.uk/guidance/flood-risk-assessment-local-planning-authorities>

If you would like advice from us regarding your development proposals you can complete our pre application enquiry form which can be found at:

<https://www.gov.uk/government/publications/pre-planning-application-enquiry-form-preliminary-opinion>

Flood Map for Planning centred on RG41 2RZ

Created on 12/04/2024 REF: THM352474



Legend

- Site
- Statutory Main Rivers
- Flood Map - Flood defences
- Flood Map - Flood Storage Areas
- Flooding from rivers or sea (FZ3)
- Extent of extreme flood (FZ2)

Flooding from rivers or sea without defences (Flood Zone 3) shows the area that could be affected by flooding:

- from the sea with a 1 in 200 or greater chance of happening each year
- or from a river with a 1 in 100 or greater chance of happening each year.

The Extent of an extreme flood (Flood Zone 2) shows the extent of an extreme flood from rivers or the sea with up to a 1 in 1000 chance of occurring each year.

Defence information

Defence Location: No defences on Main River

Description: This location is not currently protected by any formal defences and we do not currently have any flood alleviation works planned for the area. However we continue to maintain certain watercourses and the schedule of these can be found on our internet pages.

Model information

THM352474

Model: Loddon (Lower) 2009

Description: The information provided is taken from the Lower Loddon Detailed Flood Risk Mapping study which was completed in January 2009. This model is a 1D-2D model using ESTRY-TUFLOW. The model was originally built in 2007 but the hydrology was updated and model rerun in 2009. The model was re-run for more return periods on the main Loddon than on some of the tributaries.

River Channel Model: ESTRY 1D model of Lower Loddon, Old Loddon, St. Patricks Stream, River Thames (from Sonning to Marsh Lock), Twyford Brook, Billingbear Brook and Emm Brook (from Toutley Bridge to Loddon), Barkham Brook, Ashridge Stream, Waterloo Road Stream and Upper Emm Brook (from Nine Mile Ride to Toutley Bridge)

Model design runs (Main River Loddon):

1 in 5 / 20% Annual Exceedance Probability (AEP); 1 in 20 / 5% AEP; 1 in 50 / 2% AEP; 1 in 100 / 1% AEP; 1 in 1000 / 0.1% AEP; and 1 in 100+20% / 1% AEP plus 20% increase in flows

Mapped outputs (main River Loddon):

1 in 5 / 20% AEP; 1 in 20 / 5% AEP; 1 in 50 / 2% AEP; 1 in 100 / 1% AEP, 1 in 100+20% / 1% AEP plus 20% increase in flows, and 1 in 1000 / 0.1% AEP

Model design runs (tributaries – Emm Brook (Wokingham), Emm Brook (Upstream), Ashridge Stream, Waterloo Road Stream, Barkham Brook):

1 in 5 / 20% Annual Exceedance Probability (AEP); 1 in 20 / 5% AEP; 1 in 100 / 1% AEP; and 1 in 100+20% / 1% AEP plus 20% increase in flows

Mapped outputs (tributaries):

1 in 5 / 20% AEP; 1 in 20 / 5% AEP, 1 in 100 / 1% AEP and 1 in 100+20% / 1% AEP plus 20% increase in flows

Model accuracy:

Levels $\pm$ 250mm

Modelled in-channel flood flows and levels

THM352474

The modelled flood levels and flows for the closest most appropriate model node points for your site that are within the river channel are provided below:

				Flood Levels (mAOD)											
Node label	Model	Easting	Northing	20% AEP	5% AEP	3.3% AEP	1% AEP	1% AEP (+10% increase in flows)	1% AEP (+15% increase in flows)	1% AEP (+20% increase in flows)	1% AEP (+25% increase in flows)	1% AEP (+35% increase in flows)	1% AEP (+70% increase in flows)	0.1% AEP	
06324LO_MN_Emm2.58.1	Loddon (Lower) 2009	480632	167984	48.89	49.38		49.74			49.92					
06324LO_MN_Emm2.61R1.1	Loddon (Lower) 2009	480693	167995	48.91	49.40		49.76			49.94					
06324LO_MN_Emm2.62a.2	Loddon (Lower) 2009	480753	167970	48.97	49.43		49.76			49.95					
06324LO_MN_Emm2.62a.1	Loddon (Lower) 2009	480758	167967	49.08	49.53		49.86			50.03					
06324LO_MN_Emm2.62u.1	Loddon (Lower) 2009	480797	167961	49.10	49.54		49.86			50.04					
06324LO_MN_Emm2.64R1.1	Loddon (Lower) 2009	480820	167969	49.16	49.60		49.92			50.10					
06324LO_MN_Emm2.65a.1	Loddon (Lower) 2009	480844	167976	49.20	49.63		49.97			50.16					


				Flood Flows (m3/s)										
Node label	Model	Easting	Northing	20% AEP	5% AEP	3.3% AEP	1% AEP	1% AEP (+10% increase in flows)	1% AEP (+15% increase in flows)	1% AEP (+20% increase in flows)	1% AEP (+25% increase in flows)	1% AEP (+35% increase in flows)	1% AEP (+70% increase in flows)	0.1% AEP
06324LO_MN_Emm2.58.1	Loddon (Lower) 2009	480632	167984											
06324LO_MN_Emm2.61R1.1	Loddon (Lower) 2009	480693	167995											
06324LO_MN_Emm2.62a.2	Loddon (Lower) 2009	480753	167970											
06324LO_MN_Emm2.62a.1	Loddon (Lower) 2009	480758	167967											
06324LO_MN_Emm2.62u.1	Loddon (Lower) 2009	480797	167961											
06324LO_MN_Emm2.64R1.1	Loddon (Lower) 2009	480820	167969											
06324LO_MN_Emm2.65a.1	Loddon (Lower) 2009	480844	167976											

Note:
Due to changes in guidance on the allowances for climate change, the percentage increase in river flows above should no longer to be used for development design purposes. The data included in this Product can be used for interpolation of levels as part of an intermediate level assessment.

For further advice on the new allowances please visit
<https://www.gov.uk/guidance/flood-risk-assessments-climate-change-allowances>

Detailed FRA Map centred on RG41 2RZ

Created on 12/04/2024 REF: THM352474



Legend

- Model Nodes
- Site
- Statutory Main Rivers
- 20% AEP flood extent
- 5% AEP flood extent
- 1% AEP flood extent
- 1%+20% AEP flood extent
- 0.1% AEP flood extent

AEP = Annual Exceedance Probability
The probability of a flood of a particular magnitude, or greater, occurring in any given year

Where available climate change extents have been calculated with an additional flow added to an AEP event. An example of how this is written is 1%+20% AEP.

Historic flood data

THM352474

Our records show that the area of your site has been affected by flooding.
Information on the floods that have affected your site is provided in the table below:



Flood Event Code	Flood Event Name	Start Date	End Date	Source of Flooding	Cause of Flooding
EA0619470300383	06MarchSpring1947	01/01/1947	12/12/1947	main river	channel capacity exceeded (no raised defences)
EA062007030127	Thames SE area July 200	20/07/2007	21/07/2007	main river	channel capacity exceeded (no raised defences)

Please note the Environment Agency maps flooding to land not individual properties. Floodplain extents are an indication of the geographical extent of a historic flood. They do not provide information regarding levels of individual properties, nor do they imply that a property has flooded internally.

Start and End Dates shown above may represent a wider range where the exact dates are not available.

Historic Flooding Map centred on RG41 2RZ

Created on 12/04/2024 REF: THM352474



Legend

- Site
- Statutory Main Rivers
- 1947
- 2007

Flooding from rivers or sea without defences (Flood Zone 3) shows the area that could be affected by flooding:

- from the sea with a 1 in 200 or greater chance of happening each year
- or from a river with a 1 in 100 or greater chance of happening each year.

The Extent of an extreme flood (Flood Zone 2) shows the extent of an extreme flood from rivers or the sea with up to a 1 in 1000 chance of occurring each year.



Appendix E - EA Comments 03/09/2025

Wokingham Borough Council
Development Control
PO Box 157
Wokingham
Berkshire
RG40 1WR

Our ref: WA/2025/132493/01-L01
Your ref: 251907
Date: 03 September 2025

Dear Sir/Madam

Full Application For The Erection Of An Electricity Transformer And Housing Enclosure, Following Demolition Of Existing Smoking Shelter.

Crane House And Unit 1 The Business Cent Molly Millars Lane Wokingham RG41 2RZ

Thank you for consulting us on this application on 19 August 2025. We have reviewed the application in line with our planning remit, including the following documents:

- Flood Risk Assessment - Ready Power House, Molly Millar's Lane, Wokingham, Berks, RG41 2QP (ref: 6314-MILL-ICS-XX-RP-C-07.001) [April 2025]
- Site & Location Plans – Drawing Number BA 0270 50/04, Rev A [Aug 2025]
- Existing Floor Plan - Drawing Number BA 0270 50/01 [June 2025]
- Existing Elevations & Site Plans - Drawing Number BA 0270 50/02 [June 2025]
- Proposed Plans and Elevations - Drawing Number BA 0270 50/03 [June 2025]
- Planning and Design and Access Statement – Erection of an electricity transformer to the rear of Crane House [5th August 2025].

This site is located within Flood Zones 1, 2 and 3 according to the Flood Map for Planning. This is defined as areas having a low, medium and high probability of flooding respectively in accordance with Table 1 'Flood Risk' of the Planning Practice Guidance (PPG). The site lies upon a Secondary A superficial aquifer.

Environment Agency position

In the absence of an adequate flood risk assessment (FRA) we **object** to this application and recommend that planning permission is refused.

Reason

On 25 March 2025, we published updated Flood Zones alongside other datasets for use in development. Planners and flood risk professionals – find out more at [Development planning \(including Flood Map for Planning\)](#). Guidance for developers is available through the [Town and Country Planning Association](#) [New national flood and coastal erosion risk information - Town and Country Planning Association](#)

The submitted FRA (ref: 6314-MILL-ICS-XX-RP-C-07.001) does not comply with the requirements for site-specific flood risk assessments, as set out in paragraphs 20 to 21 of the Flood Risk and Coastal Change Planning Practice Guidance and its site-specific flood risk assessment checklist.

In particular, the FRA fails to:

- take the impacts of climate change into account
 - Different climate change allowances have been used to assess future flood risk than those advised in 'Flood risk assessments: climate change allowances'
 - Flood risk mitigation measures to address flood risk for the lifetime of the development included in the design are inadequate because they will not make the development resilient to the flood levels for the 2080s Higher Central allowance. Consequently, the development proposes inadequate finished floor levels.

Overcoming our objection

To overcome our objection, the applicant should submit a revised FRA which addresses the points highlighted above.

If this cannot be achieved, we are likely to maintain our objection. Please re-consult us if a revised FRA is submitted and we will respond within 21 days of re-consultation.

Specifically, the FRA will need to:

- calculate an appropriate allowance for climate change using those advised in 'Flood risk assessments: climate change allowances'
- demonstrate that finished floor levels are set above the 1% AEP plus climate change flood level to reduce the risk of flooding to people and property

Climate change, Finished Floor Levels and Floodplain Compensation – advisory note

The applicant has used the 1% annual exceedance probability 20% Climate Change allowance event to assess the site which is the Central allowance for this catchment. However, as the development is classed as 'essential infrastructure' the Higher Central allowance should be used.

The applicant may extrapolate the provided P4 data to find a level for the correct climate change scenario. This value should then be used as the design flood level and overlain on a topo map.

If the applicant can submit a clearer, more legible, topo map than currently submitted within the FRA, with the correct design flood extent overlain, this would allow us to verify whether the development is within the design flood event or outside of it.

Should the development be within the design flood event, the applicant will be required to set finished floor levels accordingly and provide the necessary floodplain compensation.

Land contamination

The current or previous use(s) of the development site relating to engineering works relating to electrical and electronic manufacturing, suggest that the land may be affected

by contamination. Land contamination can harm human health, soils, ecosystems, property, drinking waters supplies, groundwater and surface water.

Land contamination is a material planning consideration. The planning decision should ensure that the site is suitable for its proposed use, considering any risks from contamination and any proposed land remediation. The planning application should therefore be supported by adequate site investigation information, prepared by a competent person. After remediation is carried out, as a minimum, the land should not be capable of being determined as contaminated land under Part IIA of the Environmental Protection Act 1990. This approach is supported by paragraph 196 of the National Planning Policy Framework.

The current or previous use(s) of the site may present an unacceptable risk of contamination that could be mobilised during site works and construction, potentially leading to pollution of controlled waters. Controlled waters are particularly sensitive in this location because the proposed development site is located upon a secondary aquifer A.

As such, should our objection be overcome, we will request that a groundwater and contaminated land condition is applied.

Where a site is affected by contamination responsibility for securing a safe development rests with the developer and/or landowner. Developers should:

- Follow the risk management framework provided in Land Contamination: Risk Management, when dealing with land affected by contamination
- Consider using the National Quality Mark Scheme for Land Contamination Management which involves the use of competent persons to ensure that land contamination risks are appropriately managed
- Refer to the contaminated land pages on gov.uk for more information

Advice to Applicant - Other Consents

As you are aware we also have a regulatory role in issuing legally required consents, permits or licences for various activities. We have not assessed whether consent will be required under our regulatory role and therefore this letter does not indicate that permission will be given by the Environment Agency as a regulatory body.

The applicant should contact 03708 506 506 or consult our website to establish if consent will be required for the works they are proposing. Please see www.gov.uk/guidance/check-if-you-need-an-environmental-permit.

This includes any proposal to undertake work in, over, under, or within 8 metres of the top of the bank of a designated Main River, called a Flood Risk Activity permit.

Final comments

Thank you again for consulting us on this application. Our comments are based on the best available data and the information as presented to us.

If you are minded to approve the application contrary to our objection, please contact us to explain why material considerations outweigh our objection. This will allow us to make further representations. Should our objection be removed, it is likely we will recommend the inclusion of condition(s) on any subsequent approval.

Should you require any additional information, or wish to discuss these matters further, please do not hesitate to contact me on the number below. Please quote our reference number in any future correspondence.

Yours faithfully


Sarah Warriss-Simmons
Planning Advisor

Direct dial 0203 025 9855

Direct e-mail Planning_THM@environment-agency.gov.uk



Appendix F - Flood Compensation Map



- NOTES
1. All dimensions and levels are in metres unless otherwise noted
 2. This drawing is to be read in conjunction with the relevant Architect's/Engineer's drawings, specifications and CDM documentation
 3. This drawing has been produced electronically and may have been photo reduced or enlarged when copied. Work to figured dimensions only (DO NOT SCALE - EXCEPT FOR PLANNING PURPOSES). All dimensions to be checked on site. Any errors or omissions to be reported to the engineer immediately.
 4. This drawing contains coloured lines / information that may not be clear if reproduced in black and white.
 5. Digital copies of this plan can only be considered accurate if supplied directly by Infrastruct CS Ltd.

SURFACE LEVEL DATA					
NUMBER	MINIMUM LEVEL	MAXIMUM LEVEL	COLOUR	AREA	VOLUME
1	0.00	0.10		626.147m2	1040.701m3
2	0.10	0.20		1040.320m2	957.486m3
3	0.20	0.30		840.214m2	855.047m3
4	0.30	0.40		529.457m2	789.199m3
5	0.40	0.50		377.178m2	744.650m3
6	0.50	0.60		233.536m2	714.081m3
7	0.60	0.70		190.583m2	693.747m3
8	0.70	0.80		167.474m2	675.633m3
9	0.80	0.90		157.694m2	659.972m3
10	0.90	1.00		213.862m2	641.455m3
11	1.00	1.10		229.000m2	618.995m3
12	1.10	1.20		402.891m2	590.079m3
13	1.20	1.30		472.693m2	543.466m3
14	1.30	1.40		584.567m2	493.427m3
15	1.40	1.50		1491.266m2	399.147m3
16	1.50	1.60		1891.933m2	197.005m3
17	1.60	1.70		467.032m2	97.002m3
18	1.70	1.80		235.001m2	64.063m3
19	1.80	1.90		191.455m2	43.177m3
20	1.90	2.00		116.221m2	27.628m3
21	2.00	2.10		83.231m2	17.881m3
22	2.10	2.20		62.141m2	10.624m3
23	2.20	2.30		41.327m2	5.450m3
24	2.30	2.40		22.750m2	2.287m3
25	2.40	2.50		10.107m2	0.698m3
26	2.50	2.60		2.718m2	0.084m3
27	2.60	2.70		0.000m2	0.000m3

P01	RSI	RJW	Initial issue	12/02/26				
REV	DRAWN	CHECK	REVISION COMMENTS	ISSUE DATE				
DRAWING TITLE				SHEET NO.				
Flood Compensation - Existing VS Flood Zone 2 Level				1/1				
PROJECT								
Ready Power House, Molly Millars Lane, Wokingham, RG41 2QP								
CLIENT								
ET Planning		Infrastruct CS Ltd						
SCALE @ A1								
1:500								
PROJECT NUMBER		STATUS	ISSUE PURPOSE	ENGINEER				
6314		S2	INFORMATION	RJW				
PROJECT		ORIGIN	PHASE	LEVEL	TYPE	ROLE	NO.	REVISION
MILL		ICS	01	XX	DR	C	0011	P01

- NOTES
1. All dimensions and levels are in metres unless otherwise noted
 2. This drawing is to be read in conjunction with the relevant Architect's/Engineer's drawings, specifications and CDM documentation
 3. This drawing has been produced electronically and may have been photo reduced or enlarged when copied. Work to figured dimensions only (DO NOT SCALE - EXCEPT FOR PLANNING PURPOSES). All dimensions to be checked on site. Any errors or omissions to be reported to the engineer immediately.
 4. This drawing contains coloured lines / information that may not be clear if reproduced in black and white.
 5. Digital copies of this plan can only be considered accurate if supplied directly by Infrastruct CS Ltd.


Landscape area lowered to accommodate flood storage

Proposed Transformer Location

DESIGNER NOTE
The transformer is proposed at 50.30m, which is 300mm above the 1 in 100 years + 20% event

SURFACE LEVEL DATA

NUMBER	MINIMUM LEVEL	MAXIMUM LEVEL	COLOUR	AREA	VOLUME
1	0.00	0.10		606.116m2	1041.100m3
2	0.10	0.20		1031.227m2	960.108m3
3	0.20	0.30		860.449m2	856.043m3
4	0.30	0.40		533.915m2	789.464m3
5	0.40	0.50		377.814m2	744.659m3
6	0.50	0.60		233.536m2	714.081m3
7	0.60	0.70		190.583m2	693.747m3
8	0.70	0.80		167.474m2	675.633m3
9	0.80	0.90		157.694m2	659.972m3
10	0.90	1.00		213.862m2	641.455m3
11	1.00	1.10		229.000m2	618.995m3
12	1.10	1.20		402.891m2	590.079m3
13	1.20	1.30		472.693m2	543.466m3
14	1.30	1.40		584.567m2	493.427m3
15	1.40	1.50		1491.266m2	399.147m3
16	1.50	1.60		1891.933m2	197.005m3
17	1.60	1.70		467.032m2	97.002m3
18	1.70	1.80		235.001m2	64.063m3
19	1.80	1.90		191.455m2	43.177m3
20	1.90	2.00		116.221m2	27.628m3
21	2.00	2.10		83.231m2	17.881m3
22	2.10	2.20		62.141m2	10.624m3
23	2.20	2.30		41.327m2	5.450m3
24	2.30	2.40		22.750m2	2.287m3
25	2.40	2.50		10.107m2	0.698m3
26	2.50	2.60		2.718m2	0.084m3
27	2.60	2.70		0.000m2	0.000m3

P01	RSI	RJW	Initial issue	12/02/26
REV	DRAWN	CHECK	REVISION COMMENTS	ISSUE DATE
DRAWING TITLE				SHEET NO.
Flood Compensation				1/1
Proposed VS Flood Zone 2 Level				
PROJECT				
Ready Power House, Molly Millar's Lane, Wokingham, RG41 2QP				
CLIENT		 Infracore CS Ltd		
ET Planning				
SCALE @ A1				ENGINEER
1:500				RJW
				DRAFT
PROJECT NUMBER				RSI
6314				APPROVED
STATUS				MBD
S2				
ISSUE PURPOSE				
INFORMATION				
PROJECT	ORIGIN	PHASE	LEVEL	TYPE
MILL	ICS	01	XX	DR
C				
0012	P01			
NO.				REVISION