

Appendix B - Schedule of work

Two Trees to the rear of Thornbury Green, on the A321 roadside, Twyford, RG10 9RH

Cedar. (no tag).

See Appendix C that recommends “if the tree is retained we must significantly reduce by 66% the branch overhanging the street light and highway.” Also see Appendix D VISUAL TREE INSPECTION AND DECAY DETECTION

Appendix D, Visual Tree Inspection and Decay Detection is very relevant when considering the reduction of the limb on the Cedar.

Proposed work: Reduce limb over road by 10 metres leaving a final length of 5 metres.

Tag No. 144. Lime. Reduce back to previous reduction points.

See Appendix C “The tree has previously been reduced at 4-6 metres. The re- growth is now becoming untidy with excessive end weight.”

Proposed work: Reduce to lower old cuts:

- height by 7 metres leaving final height of 5 metres
- width by 3 metres leaving a final width of 5 metres