



◇ BLOCK PLAN @ 1:500

Notes:

The existing garage, boundary fencing and changes in ground level provide effective physical separation between the construction area and retained trees/hedgerows. These features prevent construction access into the adjoining planted areas, therefore additional protective fencing is not considered necessary.

Construction materials, plant and machinery shall be stored on existing hardstanding or gravel areas wherever practicable. Where access or temporary storage on soft ground adjacent to trees or hedgerows is unavoidable, suitable temporary ground protection shall be installed before access takes place. Ground protection shall be appropriate to the anticipated loading and shall prevent compaction or disturbance of the underlying soil.

Existing trees and hedgerows shall be retained and protected from accidental damage throughout construction. No branches or roots shall be cut or removed without prior agreement where such works could affect retained trees.

Rev.	Date	Description	Author	NOTES	SEPT 2026	26-GPC-PL-00.2
				1. This drawing is copyright of: Bastion. Reproduction is only to take place with our written authority. 2. These Plans are subject to 'Planning and Building Regulation Approval' or any other statute in law before building commences. 3. Any structural work where mentioned on the drawing is subject to a qualified structural and civil engineer calculations before building work commences. 4. All drawings marked preliminary or planning are not to be built or manufactured from. 5. If any discrepancies are found in the drawings these are to be brought to the attention of Bastion for rectification. 6. Boundary line indicative only. Exact location must be determined on site before building work commences. 7. Bastion is a trading name of CAD UP LTD.	1:200	(@A3)
						TREE PROTECTION PLAN