NOTES:
Based upon the Ordnance Survey map with permission of The Controller of Her Majesty's Stationery Office, © Crown Copyright.
Aspect Landscape Planning Ltd, West Court, Hardwick Business Park, Noral Way, Banbury OX16 2AF.
Licence 100045345

Copyright reserved

1:250 @ A1
0m 2m 4m 10m

KEY:

- Site Boundary
- Existing Trees
- Existing Shrubs
- Proposed Multistem Trees
- Proposed Trees (to be positioned 2m from highway boundary and 1m from kerb edge)
- Proposed Native Hedge (Caned and Rabbit guards added with 50mm bark mulch)
- Proposed Ornamental Hedge (Initially clipped to 0.5m high and subsequently maintained at 0.6m high, offset 0.5m from back of highway boundary with a 0.5m bark mulch strip)
- Proposed Feature Shrub
- Proposed Climbers (Fixed onto pressure-treated golden brown timber fan trellis - Dimensions: H1055 x W614mm.)
- Proposed Ornamental Shrubs (50mm Bark mulch to be included around planting)
- Proposed Native Shrub Planting (50mm Bark mulch to be included around planting)
- Proposed Bulb Planting (Scattered Randomly where to be planted)
- Proposed Premium Grade Turf (150mm min gravel strip with timber edge to be installed along building edge) Turf Rolls to plot frontages
- Proposed Amenity Grass Seed Flowering Lawn Mixture. Sown at 40kg/ha. Strong Lawn Grass Mixture. Sown on mown grass pathways at 250kg/ha.
- Proposed Wildflower Mix General Purpose Meadow Mixture. Sown at 40kg/ha
- Proposed WetWildflower Mix Meadow Mixture for wetlands. Sown at 40kg/ha
- Small 30mm Decorative Gravel overlaid over geotextile membrane (Gravel to be agreed with Bellway before Installation and include a timber edge)
- Proposed Root Barrier
- Proposed Mown Grass Footpath 1.2m wide
- Proposed Tarmac Footpath
- Proposed Short Span Timber Bridge Finish: FSC Certified Treated Hardwood Width: 2000mm Min. Length: 3000mm
- Proposed Timber Bench Finish: Treated Softwood timber Size/: L2000mm W580mm H770mm Root Fixed Length 300mm
- Canopied Litter Bin Size: Ø560mm H900mm Fixing: Set of 4 Shield Anchor Bolts for Installation Fixed onto Tarmac Capacity: 90 Litres
- Natural Boulders Approx. L1.2m x W0.8m x H0.8m / 1200kg
- Proposed 1.2m High Black Vertical Railing
- 450mm HighTimber Square Bollard BX17 Domed-Square Bollard Size:200x750mm Supplier: Broxap
- Visplay
- Proposed Rocks / Boulders Mixed Glacial Boulders or similar approved Supplier: CED Stone Landscape Size: Mix of approximately 200kg, 800kg &1200kg
- Proposed Small 20mm Decorative Gravel Flint ECOGravel or similar approved Supplier: CED Stone Landscape Size: 20mm Average coverage: 10m²/Tonne at 50mm depth

NB: Decorative Bark mulch to be supplied in 30-40mm chip size and applied at a depth of 50mm around landscaping to restrict weed growth and retain moisture.

REV	DATE	NOTE	Drawn	Chk'd
L	05.02.2026	Updated to latest layout	ML	SP
K	05.02.2026	Updated to latest layout	ML	SP
J	02.02.2026	Updated to latest layout	ML	SP
I	11.12.2025	Updated to latest layout	WT	SP
H	12.12.2025	Updated to latest layout	WT	SP
G	15.04.2025	Updated to latest layout & officer comments	SP	CW
F	27.03.2025	Rain garden added	SP	CW
E	20.03.2025	Updated to comments	SP	CW
D	21.03.2024	Updated to latest layout & officer comments	SP	CW
C	22.08.2024	Street lighting and tree locations updated to comments	SP	CW
B	19.08.2024	Reviewed Mix and Shrub planting in Client comments & POS boundary treatment	CW	CW
A	15.08.2024	Updated to comments	SP	CW

aspect landscape planning

TITLE
Land North of Arborfield Road, Shinfield
Planting Plan 4 of 6

CLIENT
Bellway Homes Limited (Thames Valley)

SCALE	DATE	DRAWN	CHK'D
1:250@A1	JUL 2024	SP	CW

DRAWING NUMBER
8395.PP.1.4

REVISION
L