KEY

Planning Red Line

Proposed 2m hoggin footpath with timber edging

Proposed 3m hoggin footpath with timber edging

Proposed existing access track to be retained and made good where required

Proposed no dig path construction through existing RPAs

Feature paving to be contemporary in style e.g Marshalls Conservation X Paving in a mixture of sizes 900x300mm and 900x600mm. Textured finish in a mixture of charcoal and silver grey or similar approved

Proposed contemporary timber slatted bench e.g Broxap Litchard Seat with FSC treated softwood timber slats (or similar approved) with two slat backrest. Framework to be finished in Anthracite Grey RAL 7016. To be root fixed

Proposed contemporary timber slatted picnic bench e.g Litchard Picnic Unit with FSC Treated Softwood Slats. Framework tox be finished in Anthracite Grey RAL 7016. To be surface mounted (or similar approved)

Proposed steel framed timber seat to be root fixed. e.g Broxap Roslin Steel Framed Timber Seat (or similar approved)

Proposed timber seat to be root fixed e.g Broxap Hatton Rustic 4 Slat Seat (or similar approved)

Proposed galvanised steel dual litter and recycling bin to be ground fixed e.g. Derby Double Recycling Bin by Broxap (or similar approved)

Proposed galvanised steel litter bin to be ground fixed e.g. Eco Steel Litter Bin with pyramid lid (or similar approved) in black RAL 9005

Proposed post mounted dog waste bin, post to be root fixed e.g Broxap 400, Sirius Dog Waste bin (or similar approved) in red RAL 3020

Proposed cycle stand to be root fixed, galvanised steel and polyester powder coated colour RAL 7016 e.g Curve Cycle Stand by Broxap (or similar approved) height 800mm and width 980mm. To be set within hard standing to match the adjacent path.

Proposed 450mm height timber knee rail e.g. Jacksons Fencing Diamond Wood Rail Fence (or similar approved)

Proposed 1.5m height timber post and rail fence with 1.8m between posts e.g Jacksons Fencing Square Post and Rail Fencing (or similar approved) with three sawn square horizontal rails

Proposed 700mm height steel knee rail e.g Gretna single rail by Broxap (or similar approved) to be root fixed with galvanised steel rail tube

Proposed fixed stainless steel bollard e.g Broxap Mitred Top Sheffield Stainless Steel Bollard (or similar approved). To be root fixed. 1000mm above ground height

Play Area

Proposed play equipment - refer to play specification on P24-2506_EN_01

Proposed play safety surfacing - to be a wet pour surface suitable for childrens play (e.g. RubbaSmart by Play Smart UK) and laid to the critical fall heights and extent as specified by the manufacturer. All play safety surfaces to be laid to BS EN1176 + BS EN 1177. The rubber mulch surfaces will be a mixture of red, blue and buff

Proposed play boulders to be naturally smooth or have a slightly rough surface with no sharp edges. Stone must not be slippery when wet. To be sustainable sourced - locally where possible. To be set 1/3 into the ground.

Proposed play log stepping stones and seats - to be locally sourced where possible. To be a range of sizes between 200mm and 400mm width and 100 and 300mm high. To be set 1/3 into the ground

Play area information board - timber information board to provide information regarding the play space including dogs must be kept on lead and no dog fouling. Content to be provided in co-ordination with LPA and developer

Allotments

Proposed 2m high weldmesh fence incorporating rabbit proof mesh installed sufficiently below adjacent ground level beneath the security fence to prevent animals burrowing under the security fence with lockable pedestrian and vehicular gate

Proposed 1.4m wide timber edged hoggin footpath

Proposed allotment car park with 4 spaces to be surfaced with tarmacadam with pcc kerb for vehicular movement

Proposed water supply via water trough (engineer to confirm supply). Trough to be self filling

Ground level allotment plots - sizes shown on plan.
Allotment Plots Specification
- Allotments are to be managed and maintained by a management company. They will be responsible for the maintenance of all communal areas and vacant plots.
- The allotment will be implemented in one phase with grassland seeding and hedgerow and tree planting carried out within the appropporate planting season.
- Ground level plots are to be marked out with timber edge or timber pegs at each corner.
- Ground level plots are to be be levelled and cultivated to a depth of 100mm removing all weeds, debris, litter and stones over 25mm diameter.

Basins and Rain Gardens

Proposed timber steps to basin - timber edged with non slip edge top to be sown with basin grassland as required

Proposed boulders within basin. Glacially shaped boulders in a range of sizes between 600mm-700mm in a mixture of light grey and light brown

Feature paving to create steps amongst planting contemporary in style e.g Marshalls Conservation X Paving in 900x600mm. Textured finish in a mixture of charcoal and silver grey (or similar approved)

Notes:
Refer to NBS P24-2506_EN_005 for further details
Refer to ALP drawings 7371-MJA-SW-XX-DR-C-008 - PL1 - Surfacing Plan for further details on hard landscaping

R11 - Phase 2B South Wokingham SDL - Detailed POS Hard Landscaping Proposals (Sheet 4 of 4)

PEGASUS GROUP

| PEGASUSGROUP.CO.UK | TEAM/DRAWN BY: ASK | APPROVED BY: IBD | DATE: 07/07/2025 | SCALE: 1:500@A1 | DRWG: P24-2506_EN_04-04B | CLIENT: Kier Property Developments Limited |

© Pegasus Planning Group Limited. © Crown copyright and database rights OS 100042093. Promap. Licence number 100020449. EmapSite Licence number 0100031673. Terms & Conditions @ pegasusgroup.co.uk