



0 2 4 6 8 10 meters

LEGEND

APPLICATION SITE

Planting Proposals

- SEMI-MATURE TREE
- EXTRA HEAVY STANDARD TREE
- STANDARD TREE
- MULTI-STEM TREE
- AMENITY GRASS SEEDING/TURFING
- ORNAMENTAL SHRUBS
- HEDGEROW

NB: For details of planting refer to CSA689/121-125

Hardworks

- BITUMINOUS MACADAM SURFACE** - to footpaths
- BITUMINOUS MACADAM SURFACE** - to footpaths
- CONCRETE BLOCK PAVING** - to shared surfaces
- POROUS CONCRETE BLOCK PAVING**
- CONCRETE BLOCK PAVING** - to related tables
- CONCRETE PAVING SLABS** - to dwelling access paths
- SQUARE CHANNEL KERB**

Boundary Treatment

- BRICK WALL**
- CLOSE BOARD FENCING**
- FEATURE FENCING**
- RUSTIC POST AND RAIL FENCING**
- ESTATE RAILING**
- SQUARE TIMBER ROLLERS**

Notes:

- For P5 Soft Landscape Proposals, see CSA689/121-125
- For P5 Hard Landscape Proposals, see CSA689/126
- All surface materials are to be installed as specified or equal or approved specification to be agreed with Landscape Architect
- All block paved parking bays to be demarcated using 75mm kerbs
- Any parking bays in macadam areas to receive permeable drainage
- The extent and specification of permeable paving surfaces is subject to available drainage design. All permeable paving areas will require an impermeable block also to allow the installation of buried services, the location of which shall be determined at the technical design stage
- Kerbs are generally to be 100mm high to engineering specification
- Block edge finishing to be demarcated with 100mm PC concrete on kerb

A	23/06/25	JG	Engineering Coordinated Update
Rev	Date	By	Description

Drawing Status

FOR PLANNING

CSA
environmental

Dolies Barns, High Street,
Asthall, Hertfordshire SG7 5NT

T 01462 743647
e asthall@csaenvironmental.co.uk
w csaenvironmental.co.uk

Project Parcel P5 Hogwood Farm,
Finchampslead

Title Hard Landscape Proposals
Sheet 3 of 3

Client CALA Homes Thames Ltd

Scale	1:200 @ A0	Drawn	JS
Date	June 2024	Checked	JG
Drawing No	CSA/6689/123	Rev	A