

Key

- Survey boundary.
- T1 — Tree with numbered reference. Canopy spread and BS5837:2012 tree quality category as shown below.
- T1# — Tree (location estimated) with numbered reference. Canopy spread and BS5837:2012 tree quality category.
- T1* — Tree off-site with numbered reference. Canopy spread and BS5837:2012 tree quality category.
- G1 — Vegetation group with numbered reference. Canopy extents and BS5837:2012 tree quality category as shown below.
- H1 — Hedge with numbered reference. Width and BS5837:2012 tree quality category as shown below.

BS 5837:2012 Tree Quality Categories - Table 1

- Category A - High quality
- Category B - Moderate quality
- Category C - Low quality
- Category U - Unsuitable for retention

- Tree outside of survey area (Shown for context only)
- Root protection area (RPA) Calculated in accordance with Section 4.6 - BS5837:2012
- Tree to be removed with numbered reference. Canopy spread and BS5837:2012 tree quality category.
- Vegetation group or hedge to be removed with numbered reference. Canopy spread and BS5837:2012 tree quality category.
- Ancient Woodland (© Natural England Copyright 2018)
- 15m Offset from Ancient Woodland (line taken from Natural England GIS Database)
- 15m Offset from suggested Aged Woodland
- T1 — Tree protected by Tree Preservation Order issued by Wokingham District Council number reference relates to the various TPO Schedules.
- Temporary protective fencing in accordance with Section 6.2 - BS5837:2012. See inset details for example barriers.
- Proposed earthworks within radial RPA zone of retained tree. Porous / permeable materials only.
- T866 — Proposed active management of existing trees, including mature Poplar and Ash (suffering from Ash Die Back), refer to AIA report for further details.

NOTES:

- Refer to RPS Tree Survey Report & Schedule for further details.
- Survey based on a visual inspection from the ground and is not intended as a full arboricultural inspection.
- Plan produced in accordance with recommendations set out in BS 5837:2012 - 'Trees in Relation to design, demolition and construction'.
- Due to the legal protection afforded to breeding birds vegetation removal should not take place during the bird nesting period; generally, although not restricted to, March - August inclusive.
- Survey based upon topographic survey produced by CALA in Feb 2024.
- Pedestrian/ vehicular emergency access routes to be maintained at all times.
- All protective fencing to be completed and approved by LPA / CA prior to commencement of any site works
- All works to conform with requirements of:
 - BS 3998:2010 - Tree Works
 - BS 5837:2012 - Trees in relation to design, demolition and construction


© 2019 RPS Group


Notes


1. This drawing has been prepared in accordance with the scope of RPS's appointment with its client and is subject to the terms and conditions of that appointment. RPS accepts no liability for any use of this document other than by its client and only for the purposes for which it was prepared and provided.
2. If received electronically it is the recipients responsibility to print to correct scale. Only written dimensions should be used.
3. Where applicable Ordnance Survey (c) Crown Copyright 2019

All rights reserved. Licence number 0100031673

KEY PLAN (NTS)







Rev	Description	Date	Initial	Checked
E	Updated to latest layout, WDC amends noted.	10/11/20 24	DC	DC
D	Updated to layout	12/06/20 24	DC	DC
C	Updated layout	30/12/18 99	CP	DC
B	Tree survey update	11/03/20 24	DC	DC
A	First Issue	22/12/17	SH	DC

MAKING COMPLEX EASY

Lakesbury House, Hiltingbury Road, Chandlers Ford, Hampshire SO53 5SS

T: 02380 810 440 **E:** rpsso@rpsgroup.com

Client: CALA Homes

Project: Hogwood Farm
Finchampstead

Title: Tree Protection and Removal Plan

Status	Drawn By	PM/Checked by
Planning	SH	DC

Job Ref	Scale @ A1	Date Created
JSL2891	1:500	May 2024

Drawing Number: 771

Rev: E

rpsgroup.com

P:\2800 Series\JSL2891 - Hogwood\Tech\Acad\Current\JSL2891_770 P4_5 TPP Exploded revF.dwg