

38 No. Ligustrum ovalifolium 5-7.5L

1 No. Malus 'Evereste' S

21 No. Ligustrum ovalifolium 5-7.5L

1 No. Malus 'Red Sentinel' MS

23 No. Ligustrum ovalifolium 5-7.5L

PLANTING MIX A

- 8 No. Anemone x hybrida 'Honorine Jobert' 15% 2L
- 10 No. Astrantia major 'Shaggy' 20% 2L
- 8 No. Geranium Rozanne 15% 2L
- 5 No. Hebe 'Green Globe' 10% 5L
- 5 No. Helleborus argutifolius 'Silver Lace' 10% 2L
- 5 No. Hydrangea paniculata Little Lime 10% 5L
- 5 No. Polystichum setiferum 10% 2L
- 5 No. Sarcococca confusa 10% 5L

House 1

House 2

7 No. Sarcococca confusa 5L

5 No. Osmanthus delavayi 5L

21 No. Ligustrum ovalifolium 5-7.5L

8 No. Hydrangea arborescens 'Annabelle' 5L

4 No. Osmanthus delavayi 5L

17 No. Escallonia 'Red Hedger' 5L

17 No. Ligustrum ovalifolium 5-7.5L

PLANTING MIX B

- 4 No. Alchemilla mollis 15% 2L
- 4 No. Anemone x hybrida 'Honorine Jobert' 15% 2L
- 3 No. Aster frikartii 'Monch' 10% 2L
- 4 No. Geranium Rozanne 15% 2L
- 3 No. Hebe 'Green Globe' 10% 5L
- 3 No. Hydrangea paniculata Little Lime 10% 5L
- 3 No. Philadelphus 'Manteau d'Hermine' 10% 5L
- 4 No. Rudbeckia 'Goldsturm' 15% 2L

9 No. Cotoneaster 'Coral Beauty' 3L

21 No. Ligustrum ovalifolium 5-7.5L

BUCKS COPSE

PROPOSED PLANTING SCHEDULE

TREES					
Number	Species	Height	Girth	Density	Specification
1	Malus 'Evereste'	250-300cm	8-10cm	Counted	Standard : Clear Stem 150-175 : BR
1	Malus 'Red Sentinel'	200-250cm		Counted	Multi-Stemmed : 3 Stems : BR or : RB
Total : 2					

HEDGES					
Number	Species	Height	Density	Specification	
17	Escallonia 'Red Hedger'	60-90cm	0.35Ctr	Hedge stock : Bushy : C	
170	Ligustrum ovalifolium	80-100cm	0.35Ctr	Hedging stock : Bushy : Leader With Laterals : BR or : C	
Total : 187					

SHRUBS					
Number	Species	Height	Pot Size	Density	Specification
9	Cotoneaster 'Coral Beauty'	25-30cm	3L	4/m ²	Branched : C
11	Hebe 'Green Globe'	30-40cm	5L	3/m ²	Bushy : C
8	Hydrangea arborescens 'Annabelle'	40-60cm	5L	2.5/m ²	Bushy : C
11	Hydrangea paniculata Little Lime	40-60cm	5L	3/m ²	Bushy : C
9	Osmanthus delavayi	40-60cm	5L	3/m ²	Bushy : C
3	Philadelphus 'Manteau d'Hermine'	30-40cm	5L	3/m ²	Bushy : C
15	Sarcococca confusa	40-60cm	5L	3/m ²	Bushy : C
Total : 66					

HERBACEOUS					
Number	Species	Height	Pot Size	Density	Specification
4	Alchemilla mollis	2L	3/m ²	C : Full Pot	
16	Anemone x hybrida 'Honorine Jobert'	2L	3/m ²	C : Full Pot	
3	Aster frikartii 'Monch'	2L	3/m ²	C : Full Pot	
15	Astrantia major 'Shaggy'	2L	3/m ²	C : Full Pot	
16	Geranium Rozanne	2L	3/m ²	C : Full Pot	
8	Helleborus argutifolius 'Silver Lace'	2L	3/m ²	C : Full Pot	
4	Rudbeckia 'Goldsturm'	2L	3/m ²	C : Full Pot	
Total : 66					

FERNS					
Number	Species	Pot Size	Density	Specification	
8	Polystichum setiferum	2L	3/m ²	C : Full Pot	
Total : 8					





TABLE A Land at Bucks Copse, Barkham Road, Wokingham RG41 2RD Landscape Maintenance Schedule														Project ref: 1113	
Activity	Frequency Per Areas	Years	J	F	M	A	M	J	J	A	S	O	N	D	Comments
Soft Landscape Elements															
Tree Care & Planting															
Check tree supports, stakes and ties monthly, adjust when required	Monthly	1 to 5													
Replace any damaged tree stakes and ties	As required	1 to 5													
Remove debris and ties	As required	1 to 5													
Mulch Control around base of trees (surrounds 30cm radius)	Monthly	1 to 5													
Tree inspection for damage and disease	Annually	1 to 5													
Remove dead / dying twigs from during the planting season	Annually	1 to 5													
For new trees planted within 12 months	Monthly	1 to 5													
Water new tree planting. Refer to watering guide in Landscape Maintenance & Management Plan 1.1. Weekly throughout the growing season (April to end of September). Set maximum levels during this period to ensure adequate watering is being provided. Refer to the watering guide in Landscape Maintenance & Management Plan 1.1 for more information on watering. Refer to the watering guide in Landscape Maintenance & Management Plan 1.1 for more information on watering.	Weekly	1 to 5													
Top up compostable bark mulch to maintain a depth of 75mm around the base (to March / April and September / October)	Twice a year	1 to 5													
Prick & remove control	When required	1 to 5													
General Training for the removal of dead / broken branches	When required	1 to 5													
For damaged planting to be substituted to any new trees within the first 30 months post planting (except for the removal of dead / broken branches)	N/A	4 to 5													
Assessment of condition and structure of new tree planting	Annually	All years													
Hedge Planting															
Mulch Control around base of shrubs	Twice a year	1 to 5													
Water new hedge/rose planting. Increase watering during drought conditions	Twice a year	1 to 5													
Remove dead or damaged shrubs/rose species	Annually	1 to 5													
Remove dead or damaged shrubs/rose species	Annually	1 to 5													
For new new planting as required	As required	1 to 5													
Mulch control	As required	1 to 5													
Top up compostable bark mulch to maintain a depth of 75mm around the base (to March / April and September / October)	Twice a year	1 to 5													
Prick & remove control	When required	1 to 5													
Train and tie the new hedges/hedges	When required	Year 1 - ongoing													
Formative pruning to maintain health and structural tidiness	When required	Year 1 - ongoing													
Ornamental Shrub Planting															
Top up compostable bark mulch to maintain a depth of 75mm around the base (to March / April and September / October)	Twice a year	1 to 5													
Mulch Control by hand watering to all planted areas	Twice a year	1 to 5													
Remove dead or damaged shrubs/rose species	Annually	1 to 5													
Remove dead or damaged shrubs/rose species	Annually	1 to 5													
Water new planting. Increase watering during drought conditions	Twice a year	1 to 5													
Prick & remove control	When required	1 to 5													
Top up compostable bark mulch to maintain a depth of 75mm around the base (to March / April and September / October)	Twice a year	1 to 5													
Prick & remove control	When required	1 to 5													
Formative pruning to maintain health and structural tidiness	N/A	Year 1 - ongoing													
Species Rich Grass Areas															
Cut the sward regularly during the growing season and remove cuttings from the site	Twice a year	4 to 6													
Remove fallen leaves by hand raking or leaf blower	Annually	Year 1 - ongoing													
Control weeds and grass as required	As required	1 to 5													

NOTES

Copyright: This drawing is the property of Bradford-Smith Landscape Architect. It must not be copied or reproduced or passed to a third party without written consent of Bradford Smith Ltd.
Dimensions: Only figured dimensions are to be taken from this drawing. All contractors must visit site and be responsible for taking and checking all dimensions related to the works shown on the drawing. All levels in meters.
Utilities/Highways/Environment: It is the responsibility of the client or their contractor to liaise with Utility Providers, Highways Authority's and Environment Agency and to ensure that all approvals are in place. It is the responsibility of the contractor to locate all underground services prior to construction.
Drawings: All drawings and levels to be checked on site prior to the construction works commencing on site. All drawings shall be read in conjunction with relevant landscape specifications.
Discrepancies: Any discrepancy on the drawings shall be referred to the CA immediately.

LEGEND

SOFT LANDSCAPING WORKS

-  Existing Vegetation: retained and managed
-  Proposed Medium & Small Tree Planting
-  Proposed Informal Hedgerow Planting
-  Proposed Low Clipped Hedgerow Planting
-  Proposed Ornamental Planting
-  Proposed Ornamental Planting: Maintained Below 600mm high.
-  Proposed Amenity Grass Areas: Species rich grass mix; WFT-Species-Rich-26 Lawn supplied by Wildflower Turf or similar equivalent

PLANNING

Revisions

BRADFORD-SMITH LANDSCAPE ARCHITECT	Scale	1:100 @ A2
	Date	06-10-2025
	Status	Planning Condition 7
	Drawn by	MS
5 Thorold Road Farnham Surrey GU9 7JY T: 01252 714607 E: mo@bradfordsmith.co.uk		Client
		Mr Steve Brant

Project Land at Bucks Copse, Barkham Road, Wokingham, RG41 2RD		
Drawing Title DETAILED PLANTING PLAN & SCHEDULE - Planning Condition 7		
Drawing Number 1113-LA-P-02	Revision	PI