Pound Lane & Duffield Road, Sonning

Front Boundary Landscape Enhancement Plan

25-190226 – Rev D

To be read in conjunction with Approved planting plan 251001 C1 of Application No 251129

And to supersede the approved drawing within the TPO area only

Country Estates

KEY

existing woodland TPO outline

NEW PLANTING

Large Species Trees

- English Oak @ 4m tall* x1
- Holm Oak @ 4m tall* x2
- Silver Birch @ 4m tall x2
- Hornbeam @ 4m tall x4
- Field Maple @ 4m tall x4

Mid-Canopy Infill Trees

- Blackthorn @ 2.25m tall x8
- Hazel @ 2.5m tall x13
- Purple Plum @ 2.25m tall x6
- Holly @ 1.75m tall x4
- Amelanchier @ 3m tall x2

Screening Trees

- Bay Trees (laurus nobilis) @ 5-6m tall x9

*Quercus height dependent on availability due to Oak processionary moth restrictions

Closeboard Fence

Masonry Wall

OTHER

Retained TPO Trees

Managed Woodland

Native Bulb Planting within managed woodland

Mix A – Mixed Native Mix Hedge 85m (Front Boundary)

Species	Size	Grouping	% of Mix
Corylus avellana	0.9 - 1.2m Bare root	Groups of 3+	20
Prunus spinosa	0.9 - 1.2m Bare root	Groups of 5+	20
Crataegus monogyna	0.9 - 1.2m Bare root	Groups of 7+	30
Ilex aquifolium	0.9 - 1.2m Bare root	Groups of 3+	10
Viburnum opulus	0.9 - 1.2m Bare root	Groups of 3+	10
Ligustrum vulgare	0.9 - 1.2m Bare root	Groups of 3+	10

Mix N – Front Entrance Planting Bed 22 sq.m

Species	Size	Planted in Rows	% of Mix	Quant.
Rosa Kent	5L Pot	Back Row	15	16
Hebe 'White Gem'	4L Pot	Middle Back Row	25	20
Lavandula 'Hidcote'	3L Pot	Middle Front Row	30	24
Erica darleyensis (white perfection)	1L Pot	Front Row	30	24