



- NOTES
1. The proposed access road is not part of the Natural History Museum works. Refer to the University of Reading planning application for details.
2. All existing trees and associated vegetation to be retained and protected. See Section 10.3's information.
3. All external gates, railings, and boundary treatments around the Service Yard shall be retained and protected. See Section 10.3's information. Unless noted otherwise.
4. All paving make-ups to be in accordance with the Engineer's information.
5. For structural drainage signage, refer to the Engineer's information.
6. All structural details and structural drawings to be provided in the Engineer's information.
7. Structural performance and requirements of gates to be in accordance with the Engineer's information. The structural design of the gate system shall be in accordance with the Landscape Specification (Clause D14) is limited to visual appearance and performance. The final system must be coordinated with the Engineer for structural details and structural drawings to be provided in the Engineer's information. The final system to be agreed with Landscape Architect.
8. All details and structural drawings to be provided in the Engineer's information. The contractor must incorporate positive tree pit drainage in line with the site-wide drainage strategy and Engineer's details.
9. All external gates, railings, and boundary treatments to be retained and protected with planning guidance to minimise light pollution and preserve dark skies. External lighting to be provided in the Engineer's information.
10. HVM (Hostile Vehicle Mitigation) measures and security requirements are subject to final design determination by the Security Consultant, who will advise on the appropriate measures and requirements for gates and gates in the vicinity of the site and location.
11. External lighting details shown on landscape plan, refer to the Engineer's information.
12. External landscape hardscape features to be shown in accordance to landscape plans. Final details to be provided to Ecologist.
13. Footings design for benches, bins, fence and gate posts, steps, walls, and bollards to be provided by the Engineer.
14. All external signage and road marking by others.
15. External water watering points to be shown on the landscape plan. The source of water and required volume to be in accordance with the Engineer's requirements.

- Planning Boundary
- Lease Boundary
- Scope of Works Boundary

Note: The proposed access road is not part of the Natural History Museum application. See University of Reading application for details of the access road.

P04 AMENDMENTS FOR STAGE 4:

1. The swale extension has been updated.
2. *Lonicera* - Honeysuckle introduced as groundcover following the Ecologist's recommendation. The total number of groundcovers is unchanged in the Plant Schedule.

S4 For LAP Review & Authorization

To be read in conjunction with the following documents & drawings						
- RD001-FCB-XX-XX-DR-L-1001 Annotation Legend - Hardworks - RD001-FCB-XX-XX-DR-L-1002 Annotation Legend - Softworks - RD001-FCB-XX-XX-DR-L-1003 Annotation Legend - Section & Details						
- RD001-GRA-XX-XX-SHL-5000 Planting schedule for planting details - RD001-GRA-XX-XX-SHL-4500 Series tree pits details						
P04	02.05.2025	STAGE 4		VDM	KF	
P03	21.02.2025	STAGE 4		VDM	KF	
P02	21.06.2024	TENDER		VDM	KF	
P01	26.04.2024	TENDER		VDM	KF	
Rev.	Date	Description		Drawn	Ch'd	

**grant
associates**
Landscape Architecture, Urban Design, Creative Ecology
22 Milk Street, Bath BA1 1UT
T: +44 (0) 1225 332664, F: +44 (0) 1225 420803
E: info@grant-associates.uk.com

CLIENT
FEILDEN CLEGG BRADLEY STUDIOS

PROJECT

 Natural History Museum

NHM UNLOCKED

THAMES VALLEY SCIENCE PARK

TITLE

SITE WIDE PUBLIC REALM
SOFTWARE - PLANTING BEDS
PLAN 1/2

Scale:	Date:	Drawn:	Checked:	Approved:
1:250@ A1	02/05/2025	VDM	MS	KF
Status:				
STAGE 4				
Drawing Number:				Rev:
RD001-FCB-XX-XX-DR-L-5104				P04