

BEAL Consulting Engineers Ltd		Page 1
Chiltern House Thame Road Haddenham Bucks HP17 8BY	Project 629- Johnson drive Finchampstead	
Date 26/02/2025 12:56 File 629-JOHNSON DRIVE_FEH D...	Designed by Felice Checked by	
XP Solutions	Network 2015.1	

STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for Storm

Pipe Sizes STANDARD Manhole Sizes STANDARD

FEH Rainfall Model	
Return Period (years)	100
Site Location GB 480850 165550	
C (1km)	-0.029
D1 (1km)	0.269
D2 (1km)	0.274
D3 (1km)	0.311
E (1km)	0.304
F (1km)	2.678
Maximum Rainfall (mm/hr)	50
Maximum Time of Concentration (mins)	30
Foul Sewage (l/s/ha)	0.000
Volumetric Runoff Coeff.	0.750
Add Flow / Climate Change (%)	0
Minimum Backdrop Height (m)	0.200
Maximum Backdrop Height (m)	1.500
Min Design Depth for Optimisation (m)	1.200
Min Vel for Auto Design only (m/s)	1.00
Min Slope for Optimisation (1:X)	500

Designed with Level Soffits

Time Area Diagram for Storm

Time (mins)	Area (ha)	Time (mins)	Area (ha)
0-4	0.208	4-8	0.105

Total Area Contributing (ha) = 0.313

Total Pipe Volume (m³) = 3.212

Network Design Table for Storm

« - Indicates pipe capacity < flow

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Auto Design
----	---------------	-------------	----------------	----------------	----------------	--------------------	-----------	-------------	-------------	----------------

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
----	-----------------	----------------	--------------	------------------	----------------------	---------------	-------------------	--------------	--------------	---------------

BEAL Consulting Engineers Ltd		Page 2
Chiltern House Thame Road Haddenham Bucks HP17 8BY	Project 629- Johnson drive Finchampstead	
Date 26/02/2025 12:56 File 629-JOHNSON DRIVE_FEH D...	Designed by Felice Checked by	
XP Solutions	Network 2015.1	

Network Design Table for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Auto Design
1.000	14.600	0.097	150.0	0.082	5.00	0.0	0.600	o	300	
2.000	1.000	0.010	100.0	0.010	5.00	0.0	0.600	o	100	
2.001	1.000	0.010	100.0	0.010	0.00	0.0	0.600	o	100	
2.002	1.000	0.010	100.0	0.010	0.00	0.0	0.600	o	100	
2.003	1.000	0.010	100.0	0.010	0.00	0.0	0.600	o	100	
2.004	1.000	0.350	2.9	0.023	0.00	0.0	0.600	o	150	
3.000	8.000	0.885	9.0	0.094	5.00	0.0	0.600	o	225	
3.001	1.000	0.010	100.0	0.000	0.00	0.0	0.600	o	225	
4.000	1.000	0.000	0.0	0.021	5.00	0.0	0.600	o	100	
4.001	1.500	0.230	6.5	0.017	0.00	0.0	0.600	o	100	
5.000	2.500	0.880	2.8	0.022	5.00	0.0	0.600	o	150	
6.000	1.900	0.024	79.2	0.014	5.00	0.0	0.600	o	100	
6.001	9.700	0.920	10.5	0.000	0.00	0.0	0.600	o	100	
1.001	1.000	0.000	0.0	0.000	0.00	0.0	0.600	o	225	
1.002	29.600	0.197	150.0	0.000	0.00	0.0	0.600	o	225	
1.003	10.100	0.067	150.7	0.000	0.00	0.0	0.600	o	225	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
1.000	50.00	5.19	63.560	0.082	0.0	0.0	0.0	1.28	90.6	11.1
2.000	50.00	5.02	66.210	0.010	0.0	0.0	0.0	0.77	6.0	1.4
2.001	50.00	5.04	65.730	0.020	0.0	0.0	0.0	0.77	6.0	2.7
2.002	50.00	5.07	65.400	0.030	0.0	0.0	0.0	0.77	6.0	4.1
2.003	50.00	5.09	64.950	0.040	0.0	0.0	0.0	0.77	6.0	5.4
2.004	50.00	5.09	64.270	0.063	0.0	0.0	0.0	6.01	106.2	8.5
3.000	50.00	5.03	64.745	0.094	0.0	0.0	0.0	4.38	174.1	12.7
3.001	50.00	5.04	63.860	0.094	0.0	0.0	0.0	1.31	52.0	12.7
4.000	50.00	5.24	64.200	0.021	0.0	0.0	0.0	0.07	0.5«	2.8
4.001	50.00	5.25	64.200	0.038	0.0	0.0	0.0	3.05	23.9	5.1
5.000	50.00	5.01	64.720	0.022	0.0	0.0	0.0	6.02	106.5	3.0
6.000	50.00	5.04	64.910	0.014	0.0	0.0	0.0	0.87	6.8	1.9
6.001	50.00	5.10	64.890	0.014	0.0	0.0	0.0	2.39	18.8	1.9
1.001	50.00	5.38	63.270	0.313	0.0	0.0	0.0	0.12	4.9«	42.4
1.002	50.00	5.85	63.270	0.313	0.0	0.0	0.0	1.07	42.4«	42.4
1.003	50.00	6.01	63.070	0.313	0.0	0.0	0.0	1.06	42.2«	42.4

BEAL Consulting Engineers Ltd		Page 3			
Chiltern House Thame Road Haddenham Bucks HP17 8BY	Project 629- Johnson drive Finchampstead				
Date 26/02/2025 12:56 File 629-JOHNSON DRIVE_FEH D...	Designed by Felice Checked by				
XP Solutions Network 2015.1					
<u>Free Flowing Outfall Details for Storm</u>					
Outfall Pipe Number	Outfall C. Level Name (m)	I. Level (m)	Min I. Level (m)	D,L (mm)	W (mm)
1.003	63.420	63.003	0.000	0	0
<u>Simulation Criteria for Storm</u>					
Volumetric Runoff Coeff 0.750 Additional Flow - % of Total Flow 0.000					
Areal Reduction Factor 1.000 MADD Factor * 10m³/ha Storage 2.000					
Hot Start (mins) 0 Inlet Coefficient 0.800					
Hot Start Level (mm) 0 Flow per Person per Day (l/per/day) 0.000					
Manhole Headloss Coeff (Global) 0.500 Run Time (mins) 60					
Foul Sewage per hectare (l/s) 0.000 Output Interval (mins) 1					
Number of Input Hydrographs 0 Number of Storage Structures 8					
Number of Online Controls 3 Number of Time/Area Diagrams 0					
Number of Offline Controls 0 Number of Real Time Controls 0					
<u>Synthetic Rainfall Details</u>					
Rainfall Model		FSR	Profile Type Summer		
Return Period (years)		100	Cv (Summer) 0.750		
Region England and Wales			Cv (Winter) 0.840		
M5-60 (mm)		18.900	Storm Duration (mins)		30
Ratio R		0.400			
©1982-2015 XP Solutions					

BEAL Consulting Engineers Ltd		Page 4
Chiltern House Thame Road Haddenham Bucks HP17 8BY	Project 629- Johnson drive Finchampstead	
Date 26/02/2025 12:56 File 629-JOHNSON DRIVE_FEH D...	Designed by Felice Checked by	
XP Solutions Network 2015.1		

Online Controls for Storm

Orifice Manhole: 12, DS/PN: 6.001, Volume (m³): 0.8

Diameter (m) 0.035 Discharge Coefficient 0.600 Invert Level (m) 64.890

Complex Manhole: 13, DS/PN: 1.001, Volume (m³): 3.4

Orifice

Diameter (m) 0.120 Discharge Coefficient 0.600 Invert Level (m) 63.270

Weir

Discharge Coef 0.544 Width (m) 0.700 Invert Level (m) 63.720

Hydro-Brake Optimum® Manhole: 14, DS/PN: 1.002, Volume (m³): 2.3

Unit Reference	MD-SHE-0194-1850-0800-1850
Design Head (m)	0.800
Design Flow (l/s)	18.5
Flush-Flo™	Calculated
Objective	Minimise upstream storage
Diameter (mm)	194
Invert Level (m)	63.270
Minimum Outlet Pipe Diameter (mm)	225
Suggested Manhole Diameter (mm)	1200

Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	0.800	18.4
Flush-Flo™	0.308	18.4
Kick-Flo®	0.601	16.1
Mean Flow over Head Range	-	15.2

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake Optimum® as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	6.7	1.200	22.3	3.000	34.7	7.000	52.3
0.200	17.8	1.400	24.1	3.500	37.4	7.500	54.0
0.300	18.4	1.600	25.6	4.000	39.8	8.000	55.8
0.400	18.2	1.800	27.1	4.500	42.2	8.500	57.2
0.500	17.6	2.000	28.5	5.000	44.4	9.000	58.8
0.600	16.1	2.200	29.9	5.500	46.5	9.500	60.5
0.800	18.4	2.400	31.1	6.000	48.5		
1.000	20.5	2.600	32.4	6.500	50.4		

©1982-2015 XP Solutions

BEAL Consulting Engineers Ltd		Page 5
Chiltern House Thame Road Haddenham Bucks HP17 8BY	Project 629- Johnson drive Finchampstead	
Date 26/02/2025 12:56 File 629-JOHNSON DRIVE_FEH D...	Designed by Felice Checked by	
XP Solutions	Network 2015.1	

Storage Structures for Storm

Porous Car Park Manhole: 2, DS/PN: 2.000

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	4.8
Membrane Percolation (mm/hr)	1000	Length (m)	23.7
Max Percolation (l/s)	31.6	Slope (1:X)	25.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	66.210	Cap Volume Depth (m)	0.350

Porous Car Park Manhole: 3, DS/PN: 2.001

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	4.8
Membrane Percolation (mm/hr)	1000	Length (m)	19.5
Max Percolation (l/s)	26.0	Slope (1:X)	45.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	65.730	Cap Volume Depth (m)	0.350

Porous Car Park Manhole: 4, DS/PN: 2.002

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	4.8
Membrane Percolation (mm/hr)	1000	Length (m)	20.2
Max Percolation (l/s)	26.9	Slope (1:X)	55.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	65.400	Cap Volume Depth (m)	0.350

Porous Car Park Manhole: 5, DS/PN: 2.003

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	4.8
Membrane Percolation (mm/hr)	1000	Length (m)	19.2
Max Percolation (l/s)	25.6	Slope (1:X)	35.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	64.950	Cap Volume Depth (m)	0.350


Porous Car Park Manhole: 6, DS/PN: 2.004

Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	4.8
Membrane Percolation (mm/hr)	1000	Length (m)	17.7
Max Percolation (l/s)	23.6	Slope (1:X)	0.0
Safety Factor	2.0	Depression Storage (mm)	5
Porosity	0.30	Evaporation (mm/day)	3
Invert Level (m)	64.270	Cap Volume Depth (m)	0.350

Porous Car Park Manhole: 8, DS/PN: 4.000

Infiltration Coefficient Base (m/hr)	0.00000	Max Percolation (l/s)	58.5
Membrane Percolation (mm/hr)	1000	Safety Factor	2.0

BEAL Consulting Engineers Ltd			Page 6																																																																																																																																																		
Chiltern House Thame Road Haddenham Bucks HP17 8BY		Project 629- Johnson drive Finchampstead																																																																																																																																																			
Date 26/02/2025 12:56 File 629-JOHNSON DRIVE_FEH D...		Designed by Felice Checked by																																																																																																																																																			
XP Solutions		Network 2015.1																																																																																																																																																			
<u>Porous Car Park Manhole: 8, DS/PN: 4.000</u> <table><tr><td>Porosity</td><td>0.30</td><td>Slope (1:X)</td><td>0.0</td></tr><tr><td>Invert Level (m)</td><td>64.200</td><td>Depression Storage (mm)</td><td>5</td></tr><tr><td>Width (m)</td><td>4.3</td><td>Evaporation (mm/day)</td><td>3</td></tr><tr><td>Length (m)</td><td>49.0</td><td>Cap Volume Depth (m)</td><td>0.330</td></tr></table> <u>Porous Car Park Manhole: 11, DS/PN: 6.000</u> <table><tr><td>Infiltration Coefficient Base (m/hr)</td><td>0.00000</td><td>Width (m)</td><td>4.1</td></tr><tr><td>Membrane Percolation (mm/hr)</td><td>1000</td><td>Length (m)</td><td>20.0</td></tr><tr><td>Max Percolation (l/s)</td><td>22.8</td><td>Slope (1:X)</td><td>0.0</td></tr><tr><td>Safety Factor</td><td>2.0</td><td>Depression Storage (mm)</td><td>5</td></tr><tr><td>Porosity</td><td>0.30</td><td>Evaporation (mm/day)</td><td>3</td></tr><tr><td>Invert Level (m)</td><td>64.940</td><td>Cap Volume Depth (m)</td><td>0.350</td></tr></table> <u>Cellular Storage Manhole: 13, DS/PN: 1.001</u> <table><tr><td>Invert Level (m)</td><td>63.270</td><td>Safety Factor</td><td>2.0</td></tr><tr><td>Infiltration Coefficient Base (m/hr)</td><td>0.00000</td><td>Porosity</td><td>0.95</td></tr><tr><td>Infiltration Coefficient Side (m/hr)</td><td>0.00000</td><td></td><td></td></tr></table> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>229.0</td><td>229.0</td><td>0.801</td><td>0.0</td><td>229.0</td></tr><tr><td>0.800</td><td>229.0</td><td>229.0</td><td></td><td></td><td></td></tr></table> <u>Volume Summary (Static)</u> Length Calculations based on True Length <table><tr><th colspan="4">Storage</th></tr><tr><th>Pipe Number</th><th>USMH Name</th><th>Structure Volume (m³)</th><th>Total Volume (m³)</th></tr><tr><td>1.000</td><td>1</td><td>0.000</td><td>0.000</td></tr><tr><td>2.000</td><td>2</td><td>4.725</td><td>4.725</td></tr><tr><td>2.001</td><td>3</td><td>8.617</td><td>8.617</td></tr><tr><td>2.002</td><td>4</td><td>9.073</td><td>9.073</td></tr><tr><td>2.003</td><td>5</td><td>6.615</td><td>6.615</td></tr><tr><td>2.004</td><td>6</td><td>8.921</td><td>8.921</td></tr><tr><td>3.000</td><td>7</td><td>0.000</td><td>0.000</td></tr><tr><td>3.001</td><td>8</td><td>0.000</td><td>0.000</td></tr><tr><td>4.000</td><td>8</td><td>20.859</td><td>20.859</td></tr><tr><td>4.001</td><td>9</td><td>0.000</td><td>0.000</td></tr><tr><td>5.000</td><td>10</td><td>0.000</td><td>0.000</td></tr><tr><td>6.000</td><td>11</td><td>8.610</td><td>8.610</td></tr><tr><td>6.001</td><td>12</td><td>0.000</td><td>0.000</td></tr><tr><td>1.001</td><td>13</td><td>174.113</td><td>174.113</td></tr><tr><td>1.002</td><td>14</td><td>0.000</td><td>0.000</td></tr><tr><td>1.003</td><td>15</td><td>0.000</td><td>0.000</td></tr><tr><td colspan="2">Total</td><td>241.532</td><td>241.532</td></tr></table>				Porosity	0.30	Slope (1:X)	0.0	Invert Level (m)	64.200	Depression Storage (mm)	5	Width (m)	4.3	Evaporation (mm/day)	3	Length (m)	49.0	Cap Volume Depth (m)	0.330	Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	4.1	Membrane Percolation (mm/hr)	1000	Length (m)	20.0	Max Percolation (l/s)	22.8	Slope (1:X)	0.0	Safety Factor	2.0	Depression Storage (mm)	5	Porosity	0.30	Evaporation (mm/day)	3	Invert Level (m)	64.940	Cap Volume Depth (m)	0.350	Invert Level (m)	63.270	Safety Factor	2.0	Infiltration Coefficient Base (m/hr)	0.00000	Porosity	0.95	Infiltration Coefficient Side (m/hr)	0.00000			Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)	0.000	229.0	229.0	0.801	0.0	229.0	0.800	229.0	229.0				Storage				Pipe Number	USMH Name	Structure Volume (m³)	Total Volume (m³)	1.000	1	0.000	0.000	2.000	2	4.725	4.725	2.001	3	8.617	8.617	2.002	4	9.073	9.073	2.003	5	6.615	6.615	2.004	6	8.921	8.921	3.000	7	0.000	0.000	3.001	8	0.000	0.000	4.000	8	20.859	20.859	4.001	9	0.000	0.000	5.000	10	0.000	0.000	6.000	11	8.610	8.610	6.001	12	0.000	0.000	1.001	13	174.113	174.113	1.002	14	0.000	0.000	1.003	15	0.000	0.000	Total		241.532	241.532
Porosity	0.30	Slope (1:X)	0.0																																																																																																																																																		
Invert Level (m)	64.200	Depression Storage (mm)	5																																																																																																																																																		
Width (m)	4.3	Evaporation (mm/day)	3																																																																																																																																																		
Length (m)	49.0	Cap Volume Depth (m)	0.330																																																																																																																																																		
Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	4.1																																																																																																																																																		
Membrane Percolation (mm/hr)	1000	Length (m)	20.0																																																																																																																																																		
Max Percolation (l/s)	22.8	Slope (1:X)	0.0																																																																																																																																																		
Safety Factor	2.0	Depression Storage (mm)	5																																																																																																																																																		
Porosity	0.30	Evaporation (mm/day)	3																																																																																																																																																		
Invert Level (m)	64.940	Cap Volume Depth (m)	0.350																																																																																																																																																		
Invert Level (m)	63.270	Safety Factor	2.0																																																																																																																																																		
Infiltration Coefficient Base (m/hr)	0.00000	Porosity	0.95																																																																																																																																																		
Infiltration Coefficient Side (m/hr)	0.00000																																																																																																																																																				
Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)																																																																																																																																																
0.000	229.0	229.0	0.801	0.0	229.0																																																																																																																																																
0.800	229.0	229.0																																																																																																																																																			
Storage																																																																																																																																																					
Pipe Number	USMH Name	Structure Volume (m³)	Total Volume (m³)																																																																																																																																																		
1.000	1	0.000	0.000																																																																																																																																																		
2.000	2	4.725	4.725																																																																																																																																																		
2.001	3	8.617	8.617																																																																																																																																																		
2.002	4	9.073	9.073																																																																																																																																																		
2.003	5	6.615	6.615																																																																																																																																																		
2.004	6	8.921	8.921																																																																																																																																																		
3.000	7	0.000	0.000																																																																																																																																																		
3.001	8	0.000	0.000																																																																																																																																																		
4.000	8	20.859	20.859																																																																																																																																																		
4.001	9	0.000	0.000																																																																																																																																																		
5.000	10	0.000	0.000																																																																																																																																																		
6.000	11	8.610	8.610																																																																																																																																																		
6.001	12	0.000	0.000																																																																																																																																																		
1.001	13	174.113	174.113																																																																																																																																																		
1.002	14	0.000	0.000																																																																																																																																																		
1.003	15	0.000	0.000																																																																																																																																																		
Total		241.532	241.532																																																																																																																																																		
©1982-2015 XP Solutions																																																																																																																																																					

BEAL Consulting Engineers Ltd		Page 7
Chiltern House Thame Road Haddenham Bucks HP17 8BY		
Project 629- Johnson drive Finchampstead		
Date 26/02/2025 12:56 File 629-JOHNSON DRIVE_FEH D...		
Designed by Felice Checked by		
XP Solutions		Network 2015.1

1 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

Simulation Criteria

Areal Reduction Factor 1.000	Additional Flow - % of Total Flow 0.000
Hot Start (mins) 0	MADD Factor * 10m³/ha Storage 2.000
Hot Start Level (mm) 0	Inlet Coefficient 0.800
Manhole Headloss Coeff (Global) 0.500	Flow per Person per Day (l/per/day) 0.000
Foul Sewage per hectare (l/s) 0.000	

Number of Input Hydrographs 0	Number of Storage Structures 8
Number of Online Controls 3	Number of Time/Area Diagrams 0
Number of Offline Controls 0	Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model	FEH	D3 (1km)	0.311
Site Location GB 480850 165550		E (1km)	0.304
C (1km)	-0.029	F (1km)	2.678
D1 (1km)	0.269	Cv (Summer)	0.950
D2 (1km)	0.274	Cv (Winter)	0.950

Margin for Flood Risk Warning (mm)	300.0
Analysis Timestep 2.5 Second Increment (Extended)	
DTS Status	ON
DVD Status	OFF
Inertia Status	OFF

Profile(s)	Summer and Winter
Duration(s) (mins)	15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440, 2160, 2880, 4320, 5760, 7200, 8640, 10080
Return Period(s) (years)	1, 30, 100
Climate Change (%)	0, 0, 40

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
1.000	1	15 Summer	1	+0%	100/15 Summer				63.659
2.000	2	15 Summer	1	+0%	30/15 Summer				66.255
2.001	3	30 Summer	1	+0%	30/15 Summer				65.789
2.002	4	30 Summer	1	+0%	30/15 Summer				65.472
2.003	5	30 Summer	1	+0%	30/15 Summer				65.036
2.004	6	30 Summer	1	+0%	100/15 Summer				64.309
3.000	7	15 Summer	1	+0%	100/15 Summer				64.804
3.001	8	15 Summer	1	+0%	30/15 Summer				63.998
4.000	8	180 Summer	1	+0%	100/15 Summer				64.225
4.001	9	15 Summer	1	+0%	100/15 Summer				64.231
5.000	10	15 Summer	1	+0%					64.749
6.000	11	30 Summer	1	+0%	30/15 Summer				64.963
6.001	12	60 Winter	1	+0%	30/15 Summer				64.962
1.001	13	360 Summer	1	+0%	30/15 Summer				63.443
1.002	14	360 Summer	1	+0%	100/15 Summer				63.346

©1982-2015 XP Solutions

BEAL Consulting Engineers Ltd		Page 8
Chiltern House Thame Road Haddenham Bucks HP17 8BY	Project 629- Johnson drive Finchampstead	
Date 26/02/2025 12:56 File 629-JOHNSON DRIVE_FEH D...	Designed by Felice Checked by	
XP Solutions	Network 2015.1	

1 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

PN	US/MH Name	Surcharged Flooded		Flow / Cap.	Overflow (l/s)	Pipe Flow (l/s)	Level	
		Depth (m)	Volume (m³)				Status	Exceeded
1.000	1	-0.201	0.000	0.24		17.8	OK	
2.000	2	-0.055	0.000	0.37		1.5	OK	
2.001	3	-0.041	0.000	0.66		2.6	OK	
2.002	4	-0.028	0.000	0.85		3.4	OK	
2.003	5	-0.014	0.000	1.00		3.9	OK	
2.004	6	-0.111	0.000	0.16		5.8	OK	
3.000	7	-0.166	0.000	0.15		20.4	OK	
3.001	8	-0.087	0.000	0.68		20.3	OK	
4.000	8	-0.075	0.000	0.15		0.6	OK	
4.001	9	-0.069	0.000	0.20		2.7	OK	
5.000	10	-0.121	0.000	0.08		4.8	OK	
6.000	11	-0.047	0.000	0.22		0.9	OK	
6.001	12	-0.028	0.000	0.03		0.6	OK	
1.001	13	-0.052	0.000	0.14		4.2	OK	
1.002	14	-0.149	0.000	0.11		4.2	OK	

BEAL Consulting Engineers Ltd		Page 9
Chiltern House Thame Road Haddenham Bucks HP17 8BY	Project 629- Johnson drive Finchampstead	
Date 26/02/2025 12:56 File 629-JOHNSON DRIVE_FEH D...	Designed by Felice Checked by	
XP Solutions	Network 2015.1	

1 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
1.003	15 360	Summer	1	+0%					63.121

PN	US/MH Name	Depth (m)	Surcharged Volume (m³)	Flooded Flow / Cap.	Overflow (l/s)	Pipe Flow (l/s)	Status	Level Exceeded
1.003	15	-0.174	0.000	0.12		4.2	OK	

BEAL Consulting Engineers Ltd		Page 10
Chiltern House Thame Road Haddenham Bucks HP17 8BY	Project 629- Johnson drive Finchampstead	
Date 26/02/2025 12:56 File 629-JOHNSON DRIVE_FEH D...	Designed by Felice Checked by	
XP Solutions	Network 2015.1	

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
 Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000
 Hot Start Level (mm) 0 Inlet Coefficient 0.800
 Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
 Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 8
 Number of Online Controls 3 Number of Time/Area Diagrams 0
 Number of Offline Controls 0 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FEH D3 (1km) 0.311
 Site Location GB 480850 165550 E (1km) 0.304
 C (1km) -0.029 F (1km) 2.678
 D1 (1km) 0.269 Cv (Summer) 0.950
 D2 (1km) 0.274 Cv (Winter) 0.950

Margin for Flood Risk Warning (mm) 300.0
 Analysis Timestep 2.5 Second Increment (Extended)
 DTS Status ON
 DVD Status OFF
 Inertia Status OFF

Profile(s) Summer and Winter
 Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600,
 720, 960, 1440, 2160, 2880, 4320, 5760,
 7200, 8640, 10080
 Return Period(s) (years) 1, 30, 100
 Climate Change (%) 0, 0, 40

US/MH		Return Climate		First (X)	First (Y)	First (Z)	Overflow	Water
PN	Name	Storm	Period	Change	Surcharge	Flood	Overflow	Level
							Act.	(m)
1.000	1 15 Summer		30	+0%	100/15 Summer			63.757
2.000	2 15 Summer		30	+0%	30/15 Summer			66.346
2.001	3 15 Summer		30	+0%	30/15 Summer			65.923
2.002	4 15 Summer		30	+0%	30/15 Summer			65.614
2.003	5 15 Summer		30	+0%	30/15 Summer			65.195
2.004	6 15 Summer		30	+0%	100/15 Summer			64.359
3.000	7 15 Summer		30	+0%	100/15 Summer			64.857
3.001	8 15 Summer		30	+0%	30/15 Summer			64.287
4.000	8 15 Winter		30	+0%	100/15 Summer			64.273
4.001	9 15 Summer		30	+0%	100/15 Summer			64.276
5.000	10 15 Summer		30	+0%				64.772
6.000	11 30 Winter		30	+0%	30/15 Summer			65.058
6.001	12 30 Winter		30	+0%	30/15 Summer			65.055
1.001	13 60 Winter		30	+0%	30/15 Summer			63.670
1.002	14 60 Winter		30	+0%	100/15 Summer			63.421

BEAL Consulting Engineers Ltd		Page 11
Chiltern House Thame Road Haddenham Bucks HP17 8BY	Project 629- Johnson drive Finchampstead	
Date 26/02/2025 12:56 File 629-JOHNSON DRIVE_FEH D...	Designed by Felice Checked by	
XP Solutions	Network 2015.1	

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

PN	US/MH Name	Surcharged Flooded		Flow / Cap.	Overflow (l/s)	Pipe Flow (l/s)	Status	Level Exceeded
		Depth (m)	Volume (m³)					
1.000	1	-0.103	0.000	0.76		57.1	OK	
2.000	2	0.036	0.000	1.57		6.2	SURCHARGED	
2.001	3	0.093	0.000	2.30		9.1	SURCHARGED	
2.002	4	0.114	0.000	2.54		10.0	SURCHARGED	
2.003	5	0.145	0.000	2.83		11.1	SURCHARGED	
2.004	6	-0.061	0.000	0.64		23.8	OK	
3.000	7	-0.113	0.000	0.49		65.6	OK	
3.001	8	0.202	0.000	2.17		64.9	SURCHARGED	
4.000	8	-0.027	0.000	0.88		3.5	OK	
4.001	9	-0.024	0.000	0.92		12.3	OK	
5.000	10	-0.098	0.000	0.26		15.4	OK	
6.000	11	0.048	0.000	0.24		1.1	SURCHARGED	
6.001	12	0.065	0.000	0.06		1.0	SURCHARGED	
1.001	13	0.175	0.000	0.44		13.1	SURCHARGED	
1.002	14	-0.074	0.000	0.33		13.1	OK	

BEAL Consulting Engineers Ltd		Page 12
Chiltern House Thame Road Haddenham Bucks HP17 8BY	Project 629- Johnson drive Finchampstead	
Date 26/02/2025 12:56 File 629-JOHNSON DRIVE_FEH D...	Designed by Felice Checked by	
XP Solutions	Network 2015.1	

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

	US/MH		Return Climate	First (X)	First (Y)	First (Z)	Overflow	Water
PN	Name	Storm	Period	Change	Surcharge	Flood	Overflow	Act. Level
								(m)
1.003	15	60 Winter	30	+0%				63.165

	US/MH	Depth	Volume	Flow /	Overflow	Pipe		Level
PN	Name	(m)	(m³)	Cap.	(l/s)	Flow	Status	Exceeded
						(l/s)		
1.003	15	-0.130	0.000	0.37		13.1	OK	

BEAL Consulting Engineers Ltd		Page 14
Chiltern House Thame Road Haddenham Bucks HP17 8BY	Project 629- Johnson drive Finchampstead	
Date 26/02/2025 12:56 File 629-JOHNSON DRIVE_FEH D...	Designed by Felice Checked by	
XP Solutions	Network 2015.1	

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH Name	Surcharged Flooded		Flow / Cap.	Overflow (l/s)	Pipe Flow (l/s)	Status	Level Exceeded
		Depth (m)	Volume (m³)					
1.000	1	0.593	0.000	0.58		43.5	FLOOD RISK	
2.000	2	0.155	0.000	2.90		11.4	FLOOD RISK	
2.001	3	0.247	0.000	3.62		14.2	FLOOD RISK	
2.002	4	0.263	0.000	3.72		14.7	FLOOD RISK	
2.003	5	0.318	0.000	4.08		16.1	FLOOD RISK	
2.004	6	0.033	0.000	1.05		39.0	SURCHARGED	
3.000	7	0.479	0.000	0.88		117.3	FLOOD RISK	
3.001	8	0.672	0.000	3.92		117.3	SURCHARGED	
4.000	8	0.098	0.000	-2.71		-10.7	SURCHARGED	
4.001	9	0.162	0.000	1.30		17.3	SURCHARGED	
5.000	10	-0.070	0.000	0.56		32.7	OK	
6.000	11	0.215	0.000	0.38		1.6	FLOOD RISK	
6.001	12	0.231	0.000	0.08		1.4	SURCHARGED	
1.001	13	0.953	0.000	0.69		20.7	SURCHARGED	
1.002	14	0.533	0.000	0.47		18.4	SURCHARGED	

