

I am providing the information requested with photos as a guide to the extent of the crown management provided by Beechwood Tree Care, who have done a full site review since our application was submitted and have provided a full quote for the various tree works. I am also providing more information on works to T1, T19 and various yews and holly.

T.10 black walnut

Remove major deadwood, ie branches over 50mm at source and over 300mm in length. Crown reduce by approximately 30% of leaf area (this equates to reducing the existing crown by up to approximately 1.5-2m of the radial crown spread and up to approximately 1.5-2m of the height), see photo for approx crown outline after the reduction as a guide, leaving tree with natural crown shape for species in line with BS3998.

T.13 Sweet Chestnut

Beechwood have assessed this tree and consider the deadwood to be so extensive (see photo) that they recommend section felling in safe and controlled manner to just above ground level. Therefore we are seeking permission to fell the tree.

In addition we are providing update on plans for works to T1 and T19.

T.1 Veteran Sweet Chestnut (photo attached)

Crown reduce by approximately 30% of leaf area (this equates to reducing the existing crown by up to approximately 1.5-2m of the radial crown spread and up to approximately 1.5-2m of the height), leaving tree with natural crown shape for species in line with BS3998.

Remove major deadwood, ie branches over 50mm at source and over 300mm in length.

Replace old cable bracing.

T.19 Sweet Chestnut

Extensive dead wood and decay in the tree. Fell to just above ground level.

Yews and Holly G18, T3, T4, T5 and T6

We would also like to do some trimming back of yew and holly (photos attached) and wonder if this could be given permission as part of this application?

G.18 Yew

Crown reduce lower and mid canopy over the path and raised bed by approximately 30% of leaf area (this equates to reducing the existing crown by up to approximately 0.5m of the radial crown spread), see photo for approx crown outline after the reduction (pls note this image is only a rough guide), leaving tree with natural crown shape for species in line with BS3998.

T.4, T.5, T.6 Yews and Holly

Face trim to leave neat, tidy and relatively round finish over driveway side only.

T.3 Yew

Remove low limb over building back to source. Light prune by no more than 0.5m over driveway. Remove 2 dead stems. Fell elder growing through the middle. Remove climbers from canopy.