

Where a specific area is to be used for access or storage during construction, the 250mm sub base may be replaced with 70mm thick 28mm Dense Asphalt Concrete (DAC) with 150mm thick granular sub base material Type 1 (320mm o/a thickness). The Building Manager's approval must be given to this construction, due to the additional costs.

