

39 Greenwood Road
Crowthorne
Berkshire
RG45 6JS

Preliminary Roost Assessment

Report ref.: R2889_PRA_a

Report Quality Control Information	
Author	Verity West (qualifying member of CIEEM)
Reviewer	Sarah Foot MCIEEM

March 2025



1 Diesel House, Honey Hill, Wokingham, Berkshire RG40 3BL
Telephone: 0118 3271810 Mobile: 07979 403099 E-mail: info@wenman-ecology.co.uk
www.wenman-ecology.co.uk

John Wenman Ecological Consultancy LLP is a limited liability partnership registered in England and Wales with registered number OC339057.
Registered office: 100 New Wokingham Road, Crowthorne, Berkshire RG45 6JP where you may look at a list of members' names.

CONTENTS PAGE

1	EXECUTIVE SUMMARY	3
2	INTRODUCTION	4
2.1	Project Background.....	4
2.2	Site Location and Context.....	4
2.3	Report Objectives	4
3	LEGISLATIVE AND POLICY BACKGROUND	5
3.1	Relevant Legislation.....	5
3.2	Planning Policy	5
3.3	Mitigation Licensing	6
4	SURVEY METHODOLOGY	7
4.1	Desk Study	7
4.2	Building Inspection.....	7
5	SURVEY RESULTS	10
5.1	Desk Study	10
5.2	Building Inspection.....	11
6	DISCUSSION	15
6.1	Assessment of Potential Roost Suitability.....	15
6.2	Assessment of Potential Roost Status	15
7	IMPACT ASSESSMENT	16
7.1	Potential Impacts of Development Proposals	16
7.2	Recommended Actions.....	16
8	REFERENCES	18
	APPENDIX 1 – POTENTIAL SUITABILITY CATEGORIES FOR ROOSTING BATS	19
	APPENDIX 2 – DEFINITION OF BAT ROOST TYPES	20
	APPENDIX 3 – FURTHER SURVEY RATIONALE	21
	APPENDIX 4 – EXISTING PLANNING DRAWINGS.....	22
	APPENDIX 5 – PROPOSED PLANNING DRAWINGS	24

1 EXECUTIVE SUMMARY

- 1.1.1** John Wenman Ecological Consultancy LLP was instructed by Alison Wetherall to undertake a Preliminary Roost Assessment (PRA) for bats at 39 Greenwood Road in Crowthorne, Berkshire. The survey was commissioned to accompany a householder planning application to be submitted to Wokingham Borough Council seeking consent for a first floor front dormer extension.
- 1.1.2** The property had limited potential bat access points leading into the roof void, no bat droppings were found internally and the eaves space was small and cluttered, so the presence of void-dwelling bats was considered highly unlikely. There were limited bat access points to potential crevice roost sites restricted to missing mortar under the end roof tile on the western elevation, above the soffit and a slight gap in the mortar at the western apex verge mortar. No evidence of use by bats was found and furthermore, the proposed works would not impact these potential access points that were deemed to be of negligible potential suitability.
- 1.1.3** The development proposals are considered highly unlikely to result in the death, injury or disturbance of bats; the damage or destruction of a bat roost; or the obstruction of access to a bat roost. As such, a European Protected Species (EPS) mitigation licence would not be required for the planned works to go ahead lawfully. In the unlikely event that bats are encountered during the construction activities, the works must stop immediately and a licensed ecologist should be called to site to attend to the bat and provide advice on how to proceed.
- 1.1.4** This report contains information regarding a mobile species so it will likely be valid for less than 12 months (CIEEM 2019b).
- 1.1.5** Please note that the open gap under the tile offers a suitable nesting location for birds such as the house sparrow or starling and because of the legal protection afforded to nesting wild birds, it is recommended that if the mortar is replaced, it is done outside of the nesting season or following a check by an ecologist to confirm an absence of nesting birds.

2 INTRODUCTION

2.1 Project Background

- 2.1.1** John Wenman Ecological Consultancy LLP was instructed by Alison Wetherall to undertake a Preliminary Roost Assessment (PRA) for bats at 39 Greenwood Road in Crowthorne, Berkshire.
- 2.1.2** The survey was commissioned to accompany a householder planning application to be submitted to Wokingham Borough Council seeking consent for a first floor front dormer extension.

2.2 Site Location and Context

- 2.2.1** The detached residential dwelling with detached garage was located on the southern side of Greenwood Road in Crowthorne, to the south west of Bracknell (OS Grid Ref: SU 83481 64852), surrounded by similar neighbouring properties and associated gardens with scattered and linear trees.
- 2.2.2** In the wider area the Thames Basin Heath Special Protection Area (SPA) is approximately 1,000m to the south east. Heath Lake a Site of Special Scientific Interest (SSSI) and Local Nature Reserve (LNR), is approximately 560m to the north west, with a further three SSSI sites and two LNR site within a 5km radius.
- 2.2.3** Overall the wider area surrounding woodland, wetland and open pasture landscape within a 5km radius of the site, linked by linear tree features, offer good commuting and foraging habitats for bats adapted to roosting in a suburban environment.

2.3 Report Objectives

- 2.3.1** The aim of the PRA is to ascertain if there is evidence of the presence of bats and/or potential for roosting bats to be present, and therefore whether further survey and/or mitigation would be required for future proposed development activities.

3 LEGISLATIVE AND POLICY BACKGROUND

3.1 Relevant Legislation

3.1.1 In England and Wales, all bat species found in the wild are fully protected under the Wildlife & Countryside Act 1981 (as amended) (WCA) and Conservation of Habitats and Species Regulations 2017 (as amended); the regulations are commonly referred to as the Habitat Regulations and hereafter referred to as such. The Habitat Regulations refer to European Protected Species (EPS) and all species of bats in the United Kingdom (UK) are EPS. Although the UK left the European Union on the 31st January 2020 and is therefore no longer tied to European legislation, the Habitat Regulations have been retained in their current format.

3.1.2 The legal framework underpinned by the WCA and Habitat Regulations makes these specific actions an offence as follows:

- Deliberately kill, injure, capture or take a wild bat;
- Deliberately, intentionally or recklessly disturb bats; in particular any disturbance which is likely to impair their ability to survive, to breed or reproduce, to rear or nurture their young, to hibernate or migrate, or to significantly affect local distribution or abundance;
- Damage or destroy a place used by a bat for breeding or resting; and
- Intentionally or recklessly obstruct access to any place used by a bat for shelter or protection.

3.2 Planning Policy

3.2.1 The biodiversity duty imposed through the Environment Act 2021 states that Local Planning Authorities (LPAs) must consider what action they can take to conserve and enhance biodiversity in England. Government planning policy, such as the ODPM Circular 06/2005, requires LPAs to account for the conservation of protected species when considering and determining planning applications.

3.2.2 The ODPM Circular 06/2005 states that *‘the presence of a protected species is a material consideration when a planning authority is considering a development proposal that, if carried out, would be likely to result in harm to the species or its habitat.’* This policy means that in instances where there is a reasonable likelihood of bats being present and affected by a development, surveys must be undertaken to inform a mitigation strategy to be agreed prior to granting planning permission.

3.3 Mitigation Licensing

3.3.1 The government's statutory nature conservation body, Natural England, is responsible for issuing European Protected Species (EPS) mitigation licences that would permit activities that would otherwise lead to an infringement of the Habitat Regulations. An EPS mitigation licence can be issued if the following three tests derived from Regulation 55 have been satisfied:

- (2)I – the derogation is for the purposes of *'preserving public health or public safety or other imperative reasons of overriding public interest, including those of a social or economic nature and beneficial consequences of primary importance for the environment.'*
- (9)(a) – there is *'no satisfactory alternative'* to the derogation; and
- (9)(b) – *'the action authorised will not be detrimental to the maintenance of the population of the species concerned at a favourable conservation status in their natural range.'*

3.3.2 LPAs have a statutory duty under Regulation 7(3)(e) of the Habitat Regulations to consider and determine whether these three tests are likely to be satisfied by planning proposals affecting EPS before granting planning permission. If an EPS mitigation licence is necessary, a licence can be sought once all the necessary planning consents have been granted. Natural England aims to issue a decision on licence applications within 30 working days of submission.

3.3.3 The Bat Mitigation Class Licence (BMCL) scheme allows ecologists to apply to become Registered Consultants to use this licence for low conservation status roosts, i.e. roosts comprising small numbers of seven commonly occurring species. A site registration form must be completed as a condition of the licence and submitted to Natural England at least three weeks before the licensable activities are due to start; Natural England aims to register sites within two weeks of submission.

3.3.4 Baseline survey information supporting EPS mitigation licence applications or BMCL site registrations must be up-to-date and have been completed within the current or most recent optimal season. A suitably experienced ecologist will be required to undertake a site walkover/check within three months prior to application/registration submission to confirm that conditions have not changed since the most recent survey.

4 SURVEY METHODOLOGY

4.1 Desk Study

4.1.1 A desk-based study for bats was undertaken to collate and review existing information about the site and the surrounding land. The study utilised the following open access resources:

- OS maps and Google Earth – maps and satellite imagery were used to identify potential flight-paths and foraging habitats for bats;
- MAGIC – examined to locate granted European Protected Species licences; and
- Pre-existing bat survey reports – any available reports were obtained from the client or relevant planning portal.

4.2 Building Inspection

Survey Details

4.2.1 A detailed inspection of the exterior and interior of the building was undertaken on the 5th March 2025 by Sarah Foot registered under Natural England Bat Survey Class Licence CL18 (Registration no. 2015-11906-CLS-CLS) and assisted by Verity West – a qualifying member of CIEEM, in accordance with good practice guidance (Collins 2023). The equipment used during the inspection comprised binoculars, a high-power (1 million candlepower) LED torch, a headtorch, ladder and PPE (facemask, gloves etc.). The inspection involved a systematic search of the exterior and interior of the structure during daylight hours to compile information on potential and actual bat access points; potential and actual bat roost sites; and any evidence of bat presence.

External Survey

4.2.2 Frequently used bat access points and/or roost sites include (but are not limited to) spaces:

- behind hanging tiles, weatherboarding, soffit boxes and barge boards;
- under lead flashing (particularly around chimneys) and roof tiles/slates; and
- in existing bat boxes.

4.2.3 It is important to note that the two most abundant and widespread bat species, common pipistrelle (*Pipistrellus pipistrellus*) and soprano pipistrelle (*Pipistrellus pygmaeus*), typically only require gaps measuring 15mm by 20mm to gain access to a roost inside a building.

4.2.4 The external survey involved a systematic search for evidence of bats including:

- live or dead specimens;
- droppings;
- urine marks;
- fur-oil staining; and
- squeaking noises.

4.2.5 It should be noted that bats can be present in a building while leaving no visible signs externally and wet weather has the potential to wash any evidence away. The search for evidence was focused on (but was not limited to) the ground, windowsills, windowpanes and walls (including cladding and hanging tiles); particularly in places near to potential bat access points and/or roost sites.

Internal Survey

4.2.6 The internal survey comprised a systematic search for evidence of bats on the upper floors of the building (i.e. checking the exterior from windows) and inside the roof and eave spaces. Evidence of bats found during an internal inspection can include:

- live or dead specimens;
- droppings;
- urine marks;
- fur-oil staining;
- feeding remains (i.e. moth wings);
- squeaking noises;
- bat-fly (Nycteribiid) pupal cases; and
- odour.

4.2.7 It should be noted that only specimens or droppings can be relied upon in isolation to confirm the presence of a bat roost.

4.2.8 Frequently used roosting locations within the roof include (but are not limited to):

- the apex of the gable end or dividing walls;
- the top of chimney breasts;

- ridge and hip beams;
- mortise and tenon joints;
- behind purlins; and
- between tiles and roof lining.

Survey Limitations and Validity

- 4.2.9** There were no significant survey limitations because PRAs can be carried out at any time of year under any weather conditions and the building was fully accessible.
- 4.2.10** It should be noted that it is not always possible to inspect all potential roost sites during a survey, particularly for bat species which typically roost in hidden crevices. Therefore, an absence of bat evidence found during a survey does not necessarily equate to evidence of bat absence in a building.
- 4.2.11** This report contains information regarding a mobile species so it will likely be valid for less than 12 months (CIEEM 2019b).

5 SURVEY RESULTS

5.1 Desk Study

- 5.1.1** The suburban surroundings of the site, with woodland, open recreational areas, linear tree features and wetland habitats, provides good quality foraging habitats for any bats roosting locally.
- 5.1.2** Bat mitigation licences that have been granted inside a 2 kilometre radius of the site are detailed in **Table 1** below.

Table 1. Granted bat mitigation licences within 2km radius (MAGIC)

Case Reference of Granted Licence	Species on the Licence	Licensable Period	Licensable Works
2016-25037-EPS-MIT	Soprano Pipistrelle Brown long-eared	03/09/2016 – 06/09/2021	Destruction of resting place
2014-4527-EPS-MIT-1	Brandt's Brown long-eared Common pipistrelle Soprano pipistrelle Whiskered	01/03/2015 – 30/03/2025	Destruction of a breeding site and resting place
2015-7775-EPS-MIT	Common pipistrelle	11/03/2015 – 31/03/2020	Destruction of a resting place
2015-8440-EPS-MIT	Brown long-eared	28/04/2015 – 30/04/2020	Damage and destruction of a resting place
2016-24162-EPS-MIT	Common pipistrelle	18/07/2016 – 18/07/2021	Destruction of a resting place
2020-45346-EPS-MIT	Common pipistrelle Soprano pipistrelle	30/03/2020 – 25/03/2025	Damage and destruction of a resting place
2017-31639-EPS-MIT	Common pipistrelle	24/10/2017 – 30/10/2027	Destruction of a resting place
2018-33541-EPS-MIT	Common pipistrelle Soprano pipistrelle	15/03/2018 – 15/03/2023	Destruction of a resting place
2018-33861-EPS-MIT	Brown long-eared	14/03/2018 – 30/11/2018	Destruction of a resting place
2017-31130-EPS-MIT	Whiskered	06/09/2017 – 30/09/2022	Destruction of a breeding roost
2017-31789-EPS-MIT	Soprano pipistrelle	19/10/2017 – 31/10/2018	Destruction of a resting place

5.2 Building Inspection

5.2.1 The findings from the external and internal inspections carried out for the property are described with photographs and annotated in a plan (**Figure 1**), as follows:

External Survey

5.2.2 The property comprises of a detached brick-built residential dwelling with single storey pitched front gable and rear two-storey flat roof extension. The interlocking tiles on the roof were flat and intact throughout apart from a chunk of mortar missing under the end tile on the western elevation, above the soffit. There was a slight mortar gap at the apex of the western verge but didn't look to extend deeply. The soffit on the rear southern elevation had a narrow gap behind, not considered suitable for use by roosting bats. Otherwise the uPVC soffits and fascias were tight to the brickwork throughout (**Photographs 1 – 6 ; Target notes 1 - 3**).




Photograph 1. Front of the property viewed from the north.




Photograph 2. Side of the property viewed from the north west.



Photograph 3. Rear of the property viewed from the south.



Photograph 4. Small gaps in mortar under roof tiles and at apex.




Photograph 5. Soffits tight to the brickwork.



Photograph 6. Flat roof fascias tight to the brickwork.

Internal Survey

- 5.2.3** Internally the eaves space was accessed via a first floor door. The void had a maximum height of approximately 1.5 metres. The roof liner was hessian reinforced bitumen with occasional tears. The floor was covered in fibreglass insulation and was part-boarded. The eaves were filled with fibreglass insulation in places. The chimney was heavily cobwebbed from floor to ridge height and tightly fitted to the surrounding felt. The blockwork gable ends had small filled gaps around the supporting timber beam, and no daylight was visible. The space was very full of stored household items. No evidence of bats was found internally (**Photographs 7 - 12; Target notes 4 - 7**).



Photograph 7. Roof void with household items stored.



Photograph 8. Eaves space with height of approx. 1.6m.



Photograph 9. Bitumen reinforced roof liner with



Photograph 10. Fibreglass insulation on part-boarded

occasional tears.



Photograph 11. Chimney tight and heavily cobwebbed.

floor, eaves filled in places.



Photograph 12. Gaps around support timber, no daylight visible.




Figure 1 – Preliminary Roost Assessment Findings

6 DISCUSSION

6.1 Assessment of Potential Roost Suitability

6.1.1 The suburban setting with similar properties and gardens with linear tree features and woodland and wetlands habitats in the wider area, offers good quality foraging habitats for any bats adapted to roosting in a suburban environment. Furthermore, the search of granted bat mitigation licences identified five species known to be roosting within a 2km radius of the site: common pipistrelle (*Pipistrellus pipistrellus*), soprano pipistrelle (*pipistrellus pygmaeus*), brown long-eared bats (*Plecotus auritus*), Brandt's (*Myotis brandti*) and Whiskered (*Myotis mystacinus*).

6.1.1 The property had limited potential bat access points in the form of a small gap in the verge mortar apex which did not extend deeply and an open, likely draughty, gap of missing mortar below an end roof tile above the soffit at the western gable end (**Photograph 4; Target notes 1 & 2**). The features offered sub-optimal conditions for supporting opportunistic individual crevice-dwelling bats and were considered to be of negligible potential suitability (see **Appendix 1** for potential suitability categories). No evidence of bats was observed internally or externally.

6.2 Assessment of Potential Roost Status

6.2.1 The potential bat access points were considered to be of sub-optimal suitability for use opportunistically by typically crevice-dwelling bat species such as the abundant and widespread soprano pipistrelle (*Pipistrellus pygmaeus*) and common pipistrelle (*P. pipistrellus*) bats. In line with good practice guidelines (Collins 2023; refer to **Appendix 3** for further survey rationale), the detailed building assessment concluded that the environmental conditions were not suitable for opportunistic use by individual bats and the lack of evidence gave a sufficient level of confidence in the absence of roosting bats.

7 IMPACT ASSESSMENT

7.1 Potential Impacts of Development Proposals

Overview

- 7.1.1** The householder planning application to be submitted to Wokingham Borough Council seeks consent for a first floor front dormer extension. The impacts of the proposals have been assessed in accordance with the mitigation hierarchy during construction and post development, as follows:

Construction Phase

- 7.1.2** The development proposals will not impact the potential crevice features, although deemed negligible potential suitability, to the side of the property at the western elevation, and they are to be retained unaffected during construction. Therefore, the proposed works are considered unlikely to result in the damage and/or destruction of a bat roost or cause disturbance and/or harm to bats. A European Protected Species (EPS) mitigation licence would not be required to allow the works to go ahead lawfully.

Post Development

- 7.1.3** The development proposals will not result in the long-term loss or damage of a bat roost that could adversely impact local bat populations.

7.2 Recommended Actions

- 7.2.1** The development proposals are considered unlikely to result in the death, injury or disturbance of bats; the damage or destruction of a bat roost; or the obstruction of access to a bat roost. As such, a European Protected Species (EPS) mitigation licence would not be required for the planned works to go ahead lawfully.
- 7.2.2** In the unlikely event that bats are encountered during the construction activities, the works must stop immediately and a licensed ecologist should be called to site to attend to the bat and provide advice on how to proceed; works should not continue until further written advice has been received. At this stage, an EPS mitigation licence may be required to permit the work to recommence lawfully.
- 7.2.3** Please note that the open gap under the tile offers a suitable nesting location for birds such as the house sparrow or starling and therefore it is recommended that if the mortar is replaced, it is done outside of the nesting season or following a check by an ecologist

to confirm an absence of nesting birds. All Please note that the open gap under the tile offers a suitable nesting location for birds such as the house sparrow or starling and therefore it is recommended that if the mortar is replaced, it is done outside of the nesting season or following a check by an ecologist to confirm an absence of nesting birds. wild birds are protected under the Wildlife and Countryside Act 1981 (as amended) making it an offence to kill, injure or take a wild bird or to damage or destroy the nest of a wild bird whilst in use or being built.

8 REFERENCES

CIEEM (2019b). *Advice Note on the Lifespan of Ecological Reports and Surveys*. CIEEM, Winchester.

Collins, J (ed.) (2023). *Bat Surveys for Professional Ecologists: Good Practice Guidelines (4th edition)*. The Bat Conservation Trust, London.

Mathews F., Kubasiewicz L.M., Gurnell J., Harrower C.A., McDonald R.A., Shore R.F. (2018). *A Review of the Population and Conservation Status of British Mammals*. A report by the Mammal Society under contract to Natural England, Natural Resources Wales and Scottish Natural Heritage. Natural England, Peterborough.

Mitchell-Jones, A. J. & McLeish, A. P. (2004). *Bat Workers' Manual (3rd edition)*. JNCC, Peterborough.

Reason, P.F. and Wray, S. (2023). *UK Bat Mitigation Guidelines: a guide to impact assessment, mitigation and compensation for developments affecting bats*. CIEEM, Ampfield.

APPENDIX 1 – POTENTIAL SUITABILITY CATEGORIES FOR ROOSTING BATS

The categories detailed in **Table 2** below are derived from the '*Bat Surveys for Professional Ecologists: Good Practice Guidelines (4th edition)*' (Collins 2023) and provide guidance for assessing the potential suitability of buildings (and other structures) for roosting bats. These categories are applied using professional judgement and irrespective of whether the presence of a bat roost has been confirmed during a survey, as additional bat roosts could be present which have not yet been discovered.

Table 2. Categories for potential suitability of buildings (and other structures) for roosting bats.

Potential Suitability	Category Justification
None	A building (or structure) that has no features likely to be used by any roosting bats at any time of the year (i.e. a complete absence of cracks, crevices or voids that could provide suitable shelter).
Negligible	A building (or structure) that has no obvious features likely to be used by roosting bats, but in this case a small element of uncertainty remains as bats will occasionally use small and apparently unsuitable features. This category may also be used where a bat could potentially roost due to one attribute, but it is considered unlikely due to another attribute (e.g. a feature that is subject to constant illumination from artificial lighting).
Low	A building (or structure) that has one or more potential roost sites suitable for opportunistic use by individual bats at any time of the year. However, these potential roost sites for bats do not provide sufficient space, shelter, protection, conditions and/or surrounding suitable habitat to be used regularly or by large numbers (i.e. unlikely to be suitable for a maternity colony and not a classic hibernation site).
Moderate	A building (or structure) that has one or more potential roost sites suitable for regular use by individual bats, or small non-breeding groups, due to sufficient space, shelter, protection, conditions and surrounding habitat. However, these potential roost sites for bats are unlikely to support a roost of high conservation status with regards to the type of roost only (i.e. maternity colonies and classic hibernation sites).
High	A building (or structure) that has one or more potential roost sites suitable for use by large numbers of bats more regularly and for longer periods of time due to sufficient space, shelter, protection, conditions and surrounding habitat. These potential roost sites for bats are capable of supporting high conservation status roosts (i.e. maternity colonies and classic hibernation sites).

APPENDIX 2 – DEFINITION OF BAT ROOST TYPES

The potential suitability of a building in conjunction with any evidence of bat presence is used to provide an initial assessment of likely roost type and importance. The types of roost considered are based on the following Natural England definitions:

- Day roost – a summer resting place used by individual bats, or small non-breeding groups, during the day;
- Night roost – a resting place used by individual bats on occasion, or by a whole colony regularly, during the night;
- Feeding perch – a resting place used by individual bats, or a few individuals, primarily for short periods of feeding during the night;
- Transitional roost – a place used by a few individual bats, or occasionally small groups, for a short period of time upon waking from hibernation or in the period prior to hibernation;
- Maternity roost – a place used by small to large groups of female bats to give birth and raise their young to independence;
- Hibernation roost – a place used by individual bats, or in groups, during winter where there is a constant cool temperature and high humidity; and
- Satellite roost – a place used by a few individuals to small groups of breeding female bats found in close proximity to the main nursery colony throughout the breeding season.

The importance of a bat roost is underpinned by the conservation status of the suspected species (i.e. the distribution/rarity of a species in a specific geographic location) and the type of roost (i.e. not all roosts have the same level of importance in supporting the local bat population). Further roost characterisation surveys may be required to fully determine the importance of a confirmed roost to allow for a robust impact assessment.

APPENDIX 3 – FURTHER SURVEY RATIONALE

In cases where no evidence of use by bats is found during a building inspection but the possibility of their presence cannot be ruled out, further presence/likely absence survey is likely to be required if the development proposals will impact potential roost sites.


Emergence surveys are carried out to establish the presence or likely absence of roosting bats in buildings (and other structures) and these are designed in accordance with the '*Bat Surveys for Professional Ecologists: Good Practice Guidelines (4th edition)*' (Collins 2023) detailed in **Table 3** below.

Table 3. Recommended further survey for establishing presence/likely absence of roosting bats in buildings (and other structures).

Potential Suitability	Further Survey
None	No further surveys are required.
Negligible	No further surveys are required.
Low	A minimum of one dusk emergence survey visit should be undertaken in the period of May to August. However, if all areas (including cracks, crevices and voids) can be thoroughly inspected and no evidence of use by bats is found, then emergence surveys may not be required. In cases where a complete inspection cannot be carried out, professional judgement and proportionality should be applied when assessing the impacts of the development proposals.
Moderate	A minimum of two dusk emergence survey visits should be undertaken in the period of May to September, with at least one of the surveys between May and August; the survey visits should be spaced at least three weeks apart.
High	A minimum of three separate dusk emergence survey visits should be undertaken in the period of May to September (inclusive), with at least two of the surveys between May and August; the survey visits should be spaced at least three weeks apart.

In cases where the PRA and/or further survey establishes the presence of roosting bats in a building (or structure), this will likely trigger the need for roost characterisation to collect sufficient information to inform the impact assessment and mitigation strategy. The roost characterisation comprises information collected during the PRA, emergence surveys and by other methods, such as DNA analysis of bat droppings, and ultimately aims to determine the bat species roosting; the number of bats the roosts support; the roost access points; the locations of the roosts and the types of roost present. This information is crucial when applying for planning permission and/or a European Protected Species mitigation licence.

APPENDIX 4 – EXISTING PLANNING DRAWINGS





1 Front Elevation




3 Side Elevation (Left)




2 Rear Elevation



4 Side Elevation (Right)

TITLE Existing Elevations	DRAWING No. 4043-02	DRAWN	ISSUE	DATE	CLIENT Mr & Mrs Wetherall	PROJECT ADDRESS 39 Greenwood Road, Crowthorne RG45 6J5.	SCALE 1:100 at A3 	 hello@arkitectly.co.uk
------------------------------	------------------------	-------	-------	------	------------------------------	---	---	---

APPENDIX 5 – PROPOSED PLANNING DRAWINGS






1 Front Elevation




3 Side Elevation (Left)



2 Rear Elevation



4 Side Elevation (Right)

TITLE Proposed Elevations	DRAWING No. 4043-04	DRAWN	ISSUE	DATE	CLIENT Mr & Mrs Wetherall	PROJECT ADDRESS 39 Greenwood Road, Crowthorne RG45 6JS.	SCALE 1:100 at A3 	 Arkitectly hello@arkitectly.co.uk
------------------------------	------------------------	-------	-------	------	------------------------------	---	---	---