



Urban Tree Experts

BS5837 – Tree Surveys – Ecological Consulting

PRELIMINARY ECOLOGICAL APPRAISAL (DBW) AT WATERS EDGE WARGRAVE



**Prepared for:
Mr & Mrs Elliott
Waters Edge
Wargrave
Reading
RG10 8HL**

15 August 2025

Ref: SPH/NP/PEA-25/05.08



Urban Tree Experts

BS5837 – Tree Surveys – Ecological Consulting

Bramley House
Newnham Bridge
Tenbury Wells
Worcestershire
WR15 8NX
Tel: 0118 976 2902
Email: info@batsurveys-uk.com

CONTENTS

Executive Summary

1. Introduction

- 1.1 Instruction
- 1.2 Aims and Objectives
- 1.3 Proposed works
- 1.4 Surveyor Background and Experience

2. Legislation and Planning Policy

- 2.1 Legislative Background

3. Site Location and Description

- 3.1 Site Location
- 3.2 Site Description

4. Survey Methodology

- 4.1 Pre-Survey Data Search
- 4.2 Daylight Survey
- 4.3 Constraints

5. Survey Findings

- 5.1 External Inspection
- 5.2 Internal Inspection

6. Evaluation

7. Conclusions

- 7.1 Interpretation
- 7.2 Contingency plan

8. References

9. Queries

Appendix 1

Appendix 2

©2025 Urban Tree Experts

All rights in this report are reserved. No part of it may be reproduced, edited or transmitted, in any form or by any means, electronic, mechanical, photocopying, recording or otherwise, or stored in any retrieval system of any nature, without our written permission. Its content and format are for the exclusive use of Mr & Mrs Elliott and their agents in dealing with this site. It may not be sold, lent, hired out or divulged to any third party not directly involved in this site without the written consent of Urban Tree Experts. It may be reproduced as part of a planning application.

This report is valid for 12 months from the site inspection. The lifespan of this report may be subject to change if the site conditions change due to unspecified works that affect the site.



Executive Summary

Urban Tree Experts was commissioned by Mr & Mrs Elliott to conduct a preliminary ecological appraisal (daytime bat walkover [DBW]), of Waters Edge, Wargrave, Reading, RG10 8HL. This is to support a forthcoming planning application to Wokingham Borough Council.

The site visit was carried out on Tuesday 5 August 2025 at 1pm, during daylight hours. An internal and external inspection of the property took place to look for signs of bats.

The preliminary ecological appraisal consists of a desk top study prior to the survey to review existing information about the site and its surroundings and to inform the design of subsequent bat surveys, if required. The desk top study was conducted based upon a minimum 2km search radius and it revealed that no statutory designates sites are located within, and no current European Protected Species Licence (EPSLs) for bats have been granted within 2km of the proposed development site. The immediate surrounding habitat provides suitable habitat for roosting, commuting and foraging bats with tree and hedge lined agricultural fields, copses, the St Patricks Stream, the River Loddon and River Thames all of which provide rich and diverse habitats suitable for a wide range of bat species.

The DBW comprised a detailed search of the interior and exterior of the building for bats, signs of bats and features suitable for use by roosting bats. This includes droppings, scratch marks, rubbing and staining at exit holes, live or dead bats and other features such as missing tiles, this list is not exhaustive.

The buildings suitability to support roosting bats was assessed and no bats or evidence of bats were detected, and no potential roost features were identified during the preliminary inspection. When the evidence is combined along with the data from the desk top study this results in the property being characterised as having negligible potential¹ to support roosting bats.

In line with best practice guidelines², no further survey effort is required.

¹ Table 4.1 Guidelines for assessing the potential suitability of proposed development sites for bats. Bat Surveys for Professional Ecologists Good Practice Guidelines 4th Edition.

² Collins, J. (ed) (2023) Bat Surveys for Professional Ecologists Good Practice Guidelines (4th Edition).



Urban Tree Experts

BS5837 – Tree Surveys – Ecological Consulting

1. Introduction

1.1 Instruction

Urban Tree Experts were instructed by Mr & Mrs Elliott to conduct a DBW of Waters Edge, Wargrave, Reading, RG10 8HL to support a forthcoming planning application to Wokingham Borough Council.

1.2 Aims and Objectives

The DBW is designed to:

- Identify the presence/likely absence of bats within the building.
- Provide information on previous bat ecological surveys/reports.
- Provide information on the status of bats using the building currently or previously).
- To add confidence where no bats are found, or to categorise the nature of a roost where evidence of bats are found.
- To establish whether further surveys, mitigation or an EPSL is required.

The preliminary ecological appraisal (bats) and report writing were carried out in accordance with Bat Surveys for Professional Ecologists Good Practice Guidelines 4th edition.

1.3 Proposed Works

The survey was commissioned in connection with a forthcoming planning application to Wokingham Borough Council that will seek to construct a first floor on the existing bungalow, see plans at Appendix 1.

1.4 Surveyor Background and Experience

The preliminary ecological appraisal for bats was completed by Nick Powell and the report was written by Simon Holmes MSc. CEnv.

Nick holds a Class 2 Bat License (CLS-11742) and has been surveying bats for 3 years with various ecological consultancies and has received training in surveying techniques, bat detector use, bat biology, identification, acoustic monitoring, echolocation analysis and netting.

Simon holds Class 3 (CL19) and 4 Bat (CL20) Licenses (Nos. 17637 and 17638) and a Science and Education license (SCI-64844). He has 35 years' experience of carrying out bat surveys and bat conservation work.

2. Legislation and Planning Policy

2.1 Legislative Background

All species of British bat are protected under the Conservation of Habitats and Species Regulations 2017 and the Wildlife and Countryside Act 1981, as amended. Under this legislation it is an offence to kill or injure a bat or interfere with any roosting or resting site. A bat roost is interpreted as "*any structure or place used for shelter or protection*" whether or not bats are present at the time. A summary of the main legislation and planning considerations are included at Appendix 2.



Urban Tree Experts

BS5837 – Tree Surveys – Ecological Consulting

Seven species of bat are also Species of Principal Importance for nature conservation in England under Section 41 of the Natural Environment and Rural Communities Act 2006. This places a duty on all government departments to have regard for the conservation of these species and on the Secretary of State to further, or promote others to further, the conservation of these species.

3. Site Location and Description

3.1 Site Location

The building is located at Grid Reference SU77587765, see Figure 1 below. An overview of the immediate area is shown on Figure 2, courtesy of Bing Maps.

Figure 1. Waters Edge, Wargrave, highlighted.





Figure 2. Waters Edge, Wargrave, overview of the immediate area.





Urban Tree Experts

BS5837 – Tree Surveys – Ecological Consulting

3.2 Site Description

The application site comprises a detached, brick-built single storey property with detached garage, garden room and outbuildings all set within its own extensive grounds which comprise a large, gravelled driveway/parking area, decking/seating area and lawns interspersed with and surrounded by mature trees, see Figure 3 below. The site itself offers good foraging and commuting habitat for bats and there is excellent ecological connectivity to bat foraging and commuting habitat in the wider landscape.

Figure 3. Gardens. Waters Edge, Wargrave. 05.08.25





4. Survey Methodology

4.1 Pre-Survey Data Search

The customer has advised that to their knowledge there have been no other bat surveys conducted at the property. Google Earth and MAGIC maps (magic.defra.gov.uk) websites were used prior to the survey to determine the suitability of the surrounding habitat to support roosting bats and to identify any statutory designated sites or EPSLs within 2km of the site. Due to urban surroundings, the scale of the proposed development, and the very local impact that may occur, no data was sought from the local records centre at this time.

The property is situated in a rural area to the southeast of Shiplake and southwest of Wargrave and is surrounded by agricultural fields/improved grassland and copses. The garden backs onto the tree lined Borough Lake/St Patricks Stream, the River Lodden winds to the east and southeast with the River Thames being located some 640 metres to the west. All of these areas are known to contain good habitat for roosting, commuting and foraging bats areas and are directly connected to the site.

No statutory designated sites lie within 2km of the proposed development site. A search of the Magic interactive website revealed that no current EPSL for bats has been granted within 2km of the site however there are six expired ones.

4.2 Daylight Survey

The DBW at Waters Edge, Wargrave, Reading, RG10 8HL was carried out by Nick Powell on Tuesday 5 August 2025 at 1pm. The weather conditions for the survey were dry and bright with a temperature of 19.4 degrees. Equipment used included a high-powered torch, a digital camera on a telescopic pole, endoscope and a ladder.

During the DBW, an external and internal inspection of the property was carried out to identify any signs of occupation by bats and features that could offer potential roosting sites following standard survey guidelines. Features investigated included:

- Construction of the building– soffits, loft space, tiles/slates, lead flashings etc.
- Building condition – structure of roof and walls.
- Internal conditions – microclimate stability, draughts etc.
- Access points – potential entry and exit points for bats.
- Roosting points – cracks and crevices, between underlay and roofing tiles/slates.

Field signs that would indicate the presence of bats were searched for. These included:

- Bat droppings on the floor and walls of the building.
- Feeding remains (particularly butterfly and moth wings).
- Evidence of urine and/or oily staining around possible roost entrances.
- Presence of areas cleared of cobwebs.
- Where a breathable roofing membrane has been fitted staining on the membrane may suggest use by bats.
- Odour can sometimes suggest the present of bats.
- Squeaking and chattering can reveal bats roosting between the tiles and roofing underlay.



Urban Tree Experts

BS5837 – Tree Surveys – Ecological Consulting

Buildings or structures that were not to be affected by the current proposals or with no bat roosting potential were not inspected. This includes the detached garage, garden room and outbuildings as they will not be affected by the proposed works and the glass/uPVC conservatory, due to the construction materials and light ingress, does not offer any roosting potential.

4.3 Constraints

Full access to the site during the visit was made possible by the client. A thorough inspection of the loft could not be undertaken due to the thick insulation and lack of boarding but given the excellent condition of the roof externally this was not considered to be a significant constraint to the survey.

5. Survey Findings

5.1 External Inspection

The external features of the property were examined for signs described in section 4.2. Windowsills, exposed features around the windows, fascias and walls were inspected for any evidence of bat droppings or staining.

The property is a detached, brick-built and painted building that is in a good condition externally. The multi-pitched roof is covered in closely fitted composite tiles, none of which are missing or broken (see Figure 4 below) and the ridge tiles and lead flashing around the chimney stack are all tightly fitted with no gaps in which roosting bats could exploit see Figure 5 on page 9. The valleys and verges are all well sealed and have no missing mortar which roosting bats could use, see Figure 6 on page 9. The uPVC soffits and fascias are tightly fitted to the walls and have no visible gaps in which bats could use for roosting, see Figure 7 on page 10. There are sections of uPVC and timber cladding, all of which are tightly fitted with no gaps that could be exploited by crevice dwelling bat species, see Figure 8 on page 10.

No bats or evidence of bats was recorded during the external inspection of the property and externally there are no access points into the building for bats in which to roost.

Figure 4. Tigh fitting roof tiles. Waters Edge, Wargrave. 05.08.25





Urban Tree Experts

BS5837 – Tree Surveys – Ecological Consulting

Figure 5. Example of sealed ridge tiles and lead flashing. Waters Edge, Wargrave. 05.08.25



Figure 6. Example sealed verges. Waters Edge, Wargrave. 05.08.25





Urban Tree Experts

BS5837 – Tree Surveys – Ecological Consulting

Figure 7. Example sealed soffits and fascias. Waters Edge, Wargrave. 05.08.25



Figure 8. Example tightly fitted cladding. Waters Edge, Wargrave. 05.08.25





5.2 Internal Inspection

An internal inspection of the property was undertaken and was examined for any signs of bats (as described in section 4.2).

The loft of the property was accessed via a ladder and was in a good condition internally. The loft was lit, partially boarded and deeply insulated restricting a thorough inspection however, given the excellent condition of the roof externally this was not considered a significant constraint to the inspection. The lining of the roof tiles that was visible consisted of a membrane, all of which appeared to be in a good condition, see Figure 9 below.

No bats or evidence of bats was recorded during the internal inspection of the property and internally there appeared to be no roosting opportunities for bats within the building.

Figure 9. Example of loft space. Waters Edge, Wargrave. 05.08.25





6. Evaluation

The bat roost potential of the features within the site have been assessed with reference to the following criteria and include seasonal variation where increased or decreased probability may arise. Where features are present, they are **highlighted in bold**.

The likelihood of bat roosts being present will be higher where structures:

- are of a pre-20th Century construction;
- are in a lowland rural setting;
- **have woodland, mature trees, species-rich grassland and/or water nearby;**
- have large dimension roof timbers with cracks, joints and holes;
- have numerous crevices in stonework and structures;
- have an uneven roof covering with gaps, though not too draughty;
- have hanging tiles or roof cladding, especially on south-facing walls;
- **have a roof warmed by the sun;**
- are disused or little used; largely undisturbed;
- provide appropriate hibernation conditions, such as abandoned mines, tunnels, kilns, or fortifications; or
- Recent and **historical records of bat roosts in the general area.**

The likelihood of bat roosts being present will be lower where structures:

- are in an urban setting with little green space;
- are subject to heavy disturbance (constant movement due to draughts and noise, also unstable microclimate);
- **have a small, cluttered roof void (particularly for brown long-eared);**
- **are of a modern construction with few gaps or crevices that bats can fly or crawl through (though pipistrelle bats may still be present);**
- are comprised of prefabricated steel or sheet materials; (some sections);
- are active industrial premises.

Please note that the above list provides generic screening criteria only and there are exceptions to consider.

7. Conclusions

7.1 Interpretation

The combined evidence from the desktop study and the internal and external inspection of the property provides a high level of confidence in support of the opinions set out in this report. There are no visible features externally on the building which could be utilised by roosting bats or in which bats could access the building to roost and internally no evidence of bats and no potential roosting opportunities for bats.

Informed by the results of the survey and the factors highlighted in Section 6, it is concluded that there is negligible potential for roosting bats within the property. Based on recommendations in the Bat Workers Manual and the Bat Surveys Good Practice Guidelines, no further survey effort is required.

7.2 Contingency Plan

In the unlikely event that bats are found during the proposed works, all work must stop, and advice sought from Urban Tree Experts or another licensed bat ecologist.



Urban Tree Experts

BS5837 – Tree Surveys – Ecological Consulting

If, for whatever reason, there is a time delay of greater than 12 months between this survey and the commencement of work, then the survey should be repeated as the condition of the building may change and bats may start roosting at the site.

8. References

Collins, J (ed.) (2023). Bat Surveys for Professional Ecologists: Good Practice Guidelines (4th Edition). The Bat Conservation Trust, London.

HM Government (2017) Conservation of Habitats and Species Regulations as (amended).

HM Government (1981) The Wildlife and Countryside Act (as amended).

HM Government (2006) Natural Environment and Rural Communities Act.

Mitchell-Jones, A.J. & McLeish, A.P. (2004). Bat Workers' Manual (3rd Edition). Joint Nature Conservation Committee.

9. Queries

Any queries regarding this report should be addressed, in the first instance, to Urban Tree Experts:

Telephone: 01189 762902
Email: info@batsurveys-uk.com

Urban Tree Experts
Bramley House
Newnham Bridge
Tenbury Wells
WR15 8NX




Simon Holmes MSc. CEnv.
Consultant, Urban Tree Experts
Natural England Licence CLS-CLS-17637, CLS-CLS-17638



Urban Tree Experts

BS5837 – Tree Surveys – Ecological Consulting

APPENDIX 1





PROPOSED FIRST FLOOR PLAN SCALE 1:100

PROPOSED FIRST FLOOR & GROUND FLOOR ADJUSTMENTS TO
WATERS EDGE LODGE DRIVE WARGRAVE FOR MR & MRS ELLIOTT

REV A Redrawn following meeting
23.6.2025 with client

SKOL A
2nd March 2025

MARTIN BUTLER PARTNERSHIP LIMITED.




REV A Amended following 27.1.15 meeting with client

**PROPOSED FIRST FLOOR & GROUND FLOOR ADJUSTMENTS TO
WATERS EDGE LODGE DRIVE WARGRAVE FOR MR & MRS ELLIOT**


MARTIN BUTLER PARTNERSHIP LIMITED
10 PRIDE STREET, WICKHAM, SUSSEX BN18 9JG Email: info@martinbutler.co.uk

**PROPOSED FIRST FLOOR & GROUND FLOOR ADJUSTMENTS TO
WATERS EDGE LODGE DRIVE WARGRAVE FOR MR & MRS ELLIOT**

SK03
4th March 2015



PROPOSED SOUTH ELEVATION



PROPOSED EAST ELEVATION

**PROPOSED FIRST FLOOR & GROUND FLOOR ADJUSTMENTS TO
WATERS EDGE LODDON DRIVE WAREHSE FOR MR & MRS BULLOFF
MARTIN BUTLER PARTNERSHIP LIMITED**

Revised amended following
11.1.15 meeting with client

sk04
5TH March 15



Urban Tree Experts

BS5837 – Tree Surveys – Ecological Consulting

APPENDIX 2

In summary, the legislation combined makes it an offence to:

- Intentionally or recklessly damage, destroy or obstruct access to a structure or place used for shelter by a bat.
- Intentionally or recklessly disturb bats; in particular any disturbance which is likely to impair the ability of bats to survive, breed or reproduce or nurture their young; or in the case of hibernating or migrating bats, to hibernate or migrate.
- Intentionally or deliberately kill, injure or take any bat.

Planning Considerations:

Government guidance to Local Planning Authorities stipulates the need to consider biodiversity and protected species during the consideration of planning applications. The NPPF makes clear that the planning system should help minimise the impacts that development can have on biodiversity and provide net gains in biodiversity where possible. In addition, the ODPM Circular 04/2005 states *“It is essential that the presence or otherwise of protected species, and the extent that they may be affected by the proposed development, is established before the planning permission is granted, otherwise all relevant material considerations may not have been addressed in making the decision”*.

Policy CP7 of the Wokingham Borough Core Strategy (planning policy relating to the site) states *“Development which may harm habitats or, species of principle importance in England for nature conservation, veteran trees or features of the landscape that are of major importance for wild flora and fauna (including wildlife and river corridors), whether directly or indirectly will be only permitted if it has been clearly demonstrated that the need for the proposal outweighs the need to safeguard the nature conservation importance, that no alternative site that would result in less or no harm is available which will meet the need, and*

- i) Mitigation measures can be put in place to prevent damaging impacts; or*
- ii) Appropriate compensation measures to offset the scale and kind of losses are provided”*.

Developments that compromise the protection afforded to bats or roosts under the provisions of the Conservation of Habitats and Species Regulations 2017 and the Wildlife and Countryside Act 1981 will require a European Protected Species (EPS) licence from Natural England (NE).

NE, the government’s statutory conservation advisory organisation, is responsible for issuing EPS licences that would permit activities that would otherwise lead to an infringement of the Habitat Regulations.

Three tests must be satisfied before this licence (to permit otherwise prohibited acts) can be issued:

- Reg 44(2)(e) – the derogation is “in the interests of public health and public safety, or for other imperative reasons of overriding public interest, including those of a social or economic nature and beneficial consequences of primary importance for the environment”.
- Reg 44(3)(a) – there is “no satisfactory alternative” to the derogation.
- Reg 44(3)(b) –the derogation is “not detrimental to the maintenance of the populations of the species concerned at a favourable conservation status in their natural range”.

Tests (a) and (e) can be met with the issue of planning permission for the proposed works. Test (b) is determined by NE’s ecology department that requires the development of a suitable mitigation strategy that would ensure that any bats present on site, are retained at the same population level or better.