Electrical duct

Pea Shingle & Car Park.
With stained gravel board edging

4.8m

6m

Existing Earth mound retained. Adjust alongside Car Park as necessary.

form new concrete access ramp & door

8m

Concrete Paving - Ramp up to doors.

Existing path

Concrete Path

900mm slabs on H/c. base.

5 No. Mahonia aquifolium 'Apollo'.

25 No. Hedera Colchica 'Arborescens

10 No. Mahonia aquifolium 'Apollo'

12 No Rosa intida.

12 No Vinca Major.

5 No Viburnum davidii.

Steps up & change of level. Paving slabs on bed.

Ramp up & Entrance & side doors

8 No Bergenia Cordifolia 'Purpurea'.

5 No Lonicera Pileata Loughgall Evergreen.

6 No Potentilla davurica 'Abbotswood'.

8 No Geranium 'Russell Prichard'.

6 No Stachys lanata

Electric ducts for future lighting

Paving

28 No Alchemilla mollis.

Grade bank & Falls

10 Rosa Grouse.

20 No Vinca Major.

20 No Lonicera Pileata 'Loughgall Evergreen.

10 No Geranium Macrorrhizum 'Ingersen's Variety'.

10 No Bergenia Cordifolia 'Purpurea'.

Relay existing slabs & consolidated H/C. base.

12 No Rosa intida.

Existing Beech Hedge.

Retaining Wall.
225 brick. - semi engineering on 300 mm thick foundations x 600 wide.
Engineering brick DPC. from foundation level above bp weep holes.
Weep holes at NMT. 1 Mass with Rylons Wall Weep built into brickwork as work proceeds.
Engineering brick. brick on edge coping.

| No. | SPECIES. | DENSITY | SIZE. |
|---|---|---|---|
| 28 | Alchemilla mollis. | 5 | Container 9 cm. |
| 18. | Bergania Cordifolia 'Purpurea'. | 6 | Container 9cm. |
| 10. | Geranium macrorrhizum Ingersens Variety. | 5 | Container 2 Lt. |
| 8. | Geranium 'Russell Prichard'. | 6 | Container 2 Lt. |
| 25 | Hedera colchica 'Arborescens'. | 5 | 30 - 40cm. 2 Lt. |
| 25. | Lonicera pileata 'Loughgall Evergreen'. | 3 | 20 - 30cm 2 Lt. |
| 15. | Mahonia aquifolwm 'Apollo'. | 4 | 20 - 30cm. 2 Lt |
| 6 | Potentilla Davurica 'Abbotswood'. | 3 | 20 - 30cm 2 Lt. |
| 12 | Rosa Grouse. | 3 | Container 2 Lt. |
| 24 | Rosa intida | 3 | Container 2 Lt. |
| 6 | Stachys Lanata. | 4 | Container 9 cm |
| 40 | Vinca Major. | 4 | 10 - 15 cm. 9 cm. |

05 APR 2000

APPROVED

A. Omit Retaining Wall. - CONTRACT.

DEREK CANN RIBA CHARTERED ARCHITECT
13 MANOR ROAD WOKINGHAM RG41 4AH. tel :- 0118 9786895

Job title
Wokingham Theatre
Cantley

client
Wokingham Theatre.

scale 1:200.

date Dec '99.

Drawing Title
Landscape Proposal.

Job no. 9829

Drg no 12 A