








INTERNAL DOOR SCHEDULE

ID Prefix	ID Label	Leaf Width	Leaf Height	Configuration	Leaf Type	Fire Rating	Notes
ID-	01	1075	2190	Pocket Single	Panel	FD30	with intumescent strip
ID-	02	762	2040	Single Leaf	Panel		
ID-	03	762	2040	Pocket Single	Panel		
ID-	04	762	2040	Single Leaf	Panel		bespoke, by Others
ID-	04	762	2040	Opening	Panel		under stairs cupboard
ID-	05	Existing	Existing	Single Leaf	Panel		existing door to cottage to be prepared and redecorated
ID-	06	834	2012	Single Leaf	Panel		utilities cupboard
ID-	07	626	2040	Single Leaf	Panel		
ID-	08	762	2040	Single Leaf	Panel		
ID-	09	762	2040	Pocket Single	Panel	FD30	with intumescent strip
ID-	10	762	2040	Single Leaf	Panel	FD30	with intumescent strip
ID-	11	762	2040	Single Leaf	Panel	FD30	with intumescent strip
ID-	12	762	2040	Single Leaf	Panel	FD30	with intumescent strip
ID-	13	Existing	Existing	Single Leaf	Panel		existing door to cottage to be prepared and redecorated

EXTERNAL DOOR SCHEDULE

Image	XD Prefix	XD Label	Structural Width	Structural Height	Configuration	Accessories	Notes
	XD-	01	1457	2100	Single Leaf	Stepped Threshold	Provisional sum of £2k for glazed front door with side screens
	XD-	02	1000	2100	Single Leaf	Stepped Threshold	New opening in extension
	XD-	02	1000	2100	Single Leaf	Stepped Threshold	New opening in porch
	XD-	04	3530	2100	Swing Complex	Stepped Threshold	New opening in extension
	XD-	04	3263	2100	Swing Complex	Stepped Threshold	New opening in extension
	XD-	05	1250	2100	Double Leaf	Juliette balcony	New opening in extension
	XD-	05	1135	2100	Double Leaf	Juliette balcony	New opening in extension


- Notes:
- Dimensions provided are structural openings. Contractor to check structural openings on site prior to fabrication of windows and doors.
 - Fabrication drawings to be issued to the Architect/ CA for review prior to manufacture of windows/ doors.
 - Installation of windows/ doors to be in accordance with manufactures recommendations.
 - Windows to achieve a whole unit thermal performance (u-value) of minimum 1.4 W/m2k.
 - Windows and door frames to the extension be PPC aluminium frame double glazed casement windows - colour 9016.
 - Matching sills to be provided as part of the window/ door system.
 - Ironmongery to be agreed with the Client.
 - For Building Regulations 2010 requirements, refer to drawing series 190.
 - Windows and doors to be PAS24 compliant to satisfy Part Q requirements.
 - Glazing to have a G-value of 0.4.
 - Windows with opening casements must have a cill min. 800mm above finished floor level unless balustrade is shown.
 - Fixed glazed windows to have toughened glass if cill is below 800mm.
 - Glazed doors and side panels within 300mm of door to have toughened glass to a height of min. 1500mm.

DRAWING NOTES

For elevations and vertical setting out, see drawing series 120.
For sections and construction specification notes, see drawing series 130.
For Building Regulations 2010 compliance notes, see drawing 190.

For all structural design specifications, refer to structural engineer’s drawings.

These details are subject to all relevant statutory approvals. If in doubt, check.
All dimensions are to be checked on site. Areas where quoted are approximate. Figured dimensions only are to be taken from this drawing.
Any discrepancies with other related information is to be reported to Absolute Architecture prior to order/construction/installation.
This document should not be relied on or used in circumstances other than those for which it was originally prepared and for which Absolute Architecture was commissioned.
Absolute Architecture accepts no responsibility for this document to any party other than the person by whom it was commissioned.

No.	Date	Revision Notes	 ABSOLUTE ARCHITECTURE	Design Firm Absolute Architecture Commercial House, 53b Kingsbridge Road, Newbury, Berkshire, RG14 6DY T: 01635 528188 E: mail@absolute-architecture.co.uk www.absolute-architecture.co.uk	Project Title Ed and Emily Levy DAMP WORKS TO COTTAGE Parkers Cottage, Hurst, Berkshire, RG10 0DS	Drawn By SM	Checked By SS
						Date 14/05/2024	
						Scale 1:50 @ A1	
						Status TECHNICAL	Sheet Title PRO. INTERNAL AND EXTERNAL DOOR SCHEDULE