HERMITAGE DRIVE

PINE GROVE

Gate repositioned

Telephone Exchange

Bowling Green

Development Site Boundary

existing recving facility relocated with acoustic wall surround

Food Store Customer Carpark 195 Spaces

(KEY: = trolley bay)

Apsley House parking 6No. spaces

Readibus drop-off

Pull-in

trolleys in

cycle parking

bin storage

Service Area 22m turnihg circle

Existing boundary

Existing wall to be lowered to ground level over this length

Existing Carparks

NOTE
EXACT LOCATION & QUANTITY OF SECURITY CAMERAS TO BE AGREED WITH SECURITY ADVISOR
EXACT LOCATION & QUANTITY OF ILLUMINATED SIGNS TO BE AGREED WITH THE ARCHITECT

FOOD STORE
20,861 sq.ft Sales
36,947 sq.ft Gross

Apsley House parking 3No. spaces

Public Square

Coffee Shop

No.39 Mita's Restaurant

No.41 PTR Assocs.

Oxlade House 45/47 49

61

1

Somer-field 9

19

25

Public House

Apsley House Grade 2 27/29

A3032

unloading/hopper bus existing bench and

1. 1.5KVA S/O MOUNTED IN WATERPROOF BOX SECURITY CAMERA SECURE ESP CCTV 10 BE SUPPLIED BY ELECTRICAL CONTRACTOR MOUNTED ON 5M FIXED COLUMN

2. 1.5KVA S/O MOUNTED IN WATERPROOF BOX SECURITY CAMERA SECURE ESP CCTV 10 BE SUPPLIED BY ELECTRICAL CONTRACTOR MOUNTED ON 5M FIXED COLUMN

3. 1.5KVA S/O MOUNTED IN WATERPROOF BOX SECURITY CAMERA SECURE ESP CCTV 10 BE SUPPLIED BY ELECTRICAL CONTRACTOR MOUNTED ON 5M FIXED COLUMN

1000X1000MM DRAW PIT

CK/DET3

CCTV EXIT

NO ENTRY

EXIT

WITH SHIELD

CP/Y2 ILLUMINATED SIGN 'EX SHOP ONLY' CONTROLLER CABLE IN TRENCH TO CP/Y3 LIGHT MOUNTED ON 3M

Rev	Date	Amendments	By
A	26/7/99	TENDER ISSUE	AMN
B	10/8/99	SECURITY CAMERAS – CCTS AMENDED	AMN
C	29/9/99	FOR CONSTRUCTION ISSUE	AMN
D	13/10/99	CCTV CAMERAS REPOSITIONED TO SECURITY REQUIREMENTS	AMN
E	22/11/99	MOVED COLUMNS & ADDED LIGHTING TO BUILDING.	
F	14/12/99	CHANGED WALL LUMINAIRES TO BUILDING.	
G	23/12/99	ADDED 1no. SINGLE HEAD LIGHT COLUMN, ADDED 1no. DOUBLE HEAD LIGHT COLUMN, CHANGED SINGLE COLUMN TO DOUBLE HEAD, ADDED ILLUMINATED SIGN BY ENTRANCE.	
H	7/1/00	ADDED 1no. SINGLE HEAD LIGHT COLUMN BY ENTRANCE.	
J	17/1/00	MOVED ILLUMINATED SIGN OVER BY APSLEY HOUSE. MOVED ILLUMINATED SIGN TO ENTRANCE.(A3032). REMOVED NOTES ON BARRIERS/KIOSK.	
K	8/2/00	REMOVED 2no. COLUMNS ON RT.HAND SIDE.ADDED 2no.TWIN SOCKET OUTLETS TO PROPOSED KIOSK POSITION.ADDED DUCT TO ALTERNATIVE KIOSK POSITION.	
L	7/4/00	OMIT 1 X 'N1' IN UNLOADING BAY (SHOWN ON EL–G01) OMIT 2no.'TB' BY COFFEE SHOP EXIT. MOVE LAMPOST TO OPPOSITE SIDE OF ROAD BY SURGERY.	

Notes

1.) No dimensions to be scaled from this drawing.

KEY

- TB — WALL MOUNTED TERIMA–812–080 RAL 6012
- WALL MOUNTED ALATUS
- COLUMN WITH DOUBLE ARM 5 METRES HIGH ALATUS
- COLUMN WITH SINGLE ARM 5 METRES HIGH ALATUS

FOR CONSTRUCTION

JOHN LEWIS PARTNERSHIP
BUILDING GROUP
171 Victoria Street London SW1E 5NN
Telephone 0171-828 1000
Fax 0171-592 6495

PLANNING SERVICES INFO
CH
PCL
DO
ATP
CS
28 OCT 2000
COPIES TO:
JOB:
FILE:

Branch: WAITROSE TWYFORD

Title: SITE PLAN ELECTRICAL REQUIREMENTS

APPROVED IN RESPECT OF POSITIONS OF CCTV AND LIGHTING ONLY.

Scale	1:200
Date	10/03/99
Drawn by	AMN
Checked by	
Drawing No.	6020/EZ–001 L
Note	

(Plot File Created On 19/10/00 At 17:24(GMT) By GINO DALIPAT)