CUT LINE — FOR CONTINUATION SEE DRAWING ITB19328-GA-105 — CUT LINE

EXISTING SPEED LIMIT ROUNDELS TO BE REPAINTED

20mph ZONE SIGNAGE & GATEWAY FEATURE

EXISTING FOOTWAY

GIVE WAY MARKINGS

EXISTING INFORMAL CROSSING

20mph ZONE SIGNAGE & GATEWAY FEATURE

PEDESTRIAN CROSSING WITH BUILD-OUT, DROPPED KERBS AND TACTILE PAVING. POTENTIAL FOR BOLLARDS TO BE PROVIDED

EXISTING KERBLINE TO BE REALIGNED TO PROVIDE WIDENED FOOTWAY

CUT LINE — FOR CONTINUATION SEE DRAWING ITB19328-GA-121 — CUT LINE

EXISTING KERBLINE TO BE REALIGNED TO PROVIDE WIDENED FOOTWAY

20mph ZONE SIGNAGE, GATEWAY FEATURE & GIVE WAY MARKINGS

PEDESTRIAN CROSSING WITH BUILD-OUT, DROPPED KERBS AND TACTILE PAVING. POTENTIAL FOR BOLLARDS TO BE PROVIDED

HOGMOOR LANE

BROADWATER LANE

TAPELA

1.2m 1.4m 1.3m 1.3m 1.2m 1.5m 1.4m 1.3m 1.5m 1.5m 1.5m 2.0m 2.75m 5.5m 5.5m 2.7m

SCALE BAR @ 1:500
0 5 10 25 50

DRAWING ISSUED FOR FEASIBILITY CONSIDERATION AND PLANNING PURPOSES ONLY. DRAWING NOT TO BE USED FOR CONSTRUCTION. I-TRANSPORT LLP ACCEPT NO RESPONSIBILITY FOR ERRORS MADE BY OTHERS IN SCALING FROM THIS DRAWING. MEASUREMENTS SHOULD BE TAKEN FROM FIGURED DIMENSIONS ONLY. CDM REQUIREMENTS CONSIDERED AT FEASIBILITY STAGE ONLY. FURTHER CONSIDERATION REQUIRED BY DETAILED DESIGN TEAM.
© CROWN COPYRIGHT 2022 OS LICENCE No. 100044286.

i-Transport
The Square, Basing View, Basingstoke, Hampshire, RG21 4EB
Tel: 01256 898366
www.i-transport.co.uk

REV	DATE	BY	DESCRIPTION	CHK	APD
B	07.11.24	JD	WBC COMMENTS INCORPORATED	MK	TW
A	16.07.24	JD	RSA COMMENTS INCORPORATED	BB	TW

STATUS: FOR INFORMATION

TITLE: POTENTIAL OFF-SITE PEDESTRIAN / CYCLIST IMPROVEMENT SCHEME
SHEET 4

PROJECT: LAND EAST OF LODGE ROAD, HURST

CLIENT: MACTAGGART AND MICKEL STRATEGIC LAND (MAC MIC)

DRAWN:	CHECKED:	APPROVED:
JD	BB	TW
PROJECT No:	**SCALE @ A2:**	**DATE:**
ITB19328	1:500	14.11.23
DRAWING No:		**REV:**
ITB19328-GA-104		B

I:\Projects\19000 Series\19328\TB - Tape Lane Hurst\Acad\i-Transport Drawings\Working Drawings\GA\100 SERIES DRAWINGS\ITB19328-GA-104B.dwg