

continued on drawing 700399-KKL-CP-00-DR-A-0302



Annotation Ground Floor

- G1 drain capped to u/s screed for future use
- G2 Porch & Level Access
- G3 Threshold drain
- G4 garden wall brick 215mm wide; top 937.5mm above FFL

EVC Electr. vehicle charger (no duct requ'd to plots with on-plot parking)

PLOT SCHEDULE

PLOT NO.	HOUSE TYPE	HANDING	TENURE
143	HT 2	AS	Social Rent
144	HT 2	AS	Social Rent
145	HT 2	AS	Social Rent
146	HT 2	AS	Social Rent
147	HT 1	AS	Social Rent
148	HT 1	AS	Social Rent


KEY to plan drawings

- SUBSTRUCTURE**
 - 100mm concrete blockwork (compressive strength to SE design) F10
 - 50mm cavity
 - 75mm insulation F30
 - 100mm concrete blockwork (compressive strength to SE design) F10
- EXTERNAL WALL**
 - 102.5mm brick (multi stock / blue; refer to elevations) F10
 - 50mm cavity
 - 75mm insulation F30
 - 100mm Aerated Concrete blockwork (compressive strength to SE design) F10
 - 12.5mm Plasterboard by Siniat on 12.5mm dabs K10
- GARDEN WALL**
 - 215mm Flemish bond brick leaf (multi-stock brick) with solid header brick laid face down (blue brick) F10
- Refer to elevations for locations of corduroy detail**
- PARTY WALL CONSTRUCTION**
 - 100mm medium dense blockwork F10
 - 125mm insulation (full fill) F30
 - 100mm medium dense blockwork F10
 - 12.5mm plasterboard and skim by Siniat on dabs to both sides K10 / Siniat pack
- INTERNAL PARTITION**
 - 140mm medium dense blockwork (1450kg/m³) F10, to SE specification
 - 12.5mm Plasterboard and skim by Siniat on dabs to both sides K10 / Siniat pack
- INTERNAL PARTITION**
 - 100mm medium dense blockwork (1450kg/m³) F10, to SE specification
 - 12.5mm Plasterboard and skim by Siniat on dabs to both sides K10 / Siniat pack
- INTERNAL PARTITION**
 - Non-loadbearing 70mm or 100mm metal partition system with 12.5mm Plasterboard and skim by Siniat on both sides. Between bedrooms or rooms containing a WC to incorporate 25mm isover acoustic partition roll (apr 1200). Refer to Siniat pack
- 30 REI fire rated floor/partition/ceiling (3-storey houses)**
- 30 R / 15 EI fire rated floor/ceiling (2-storey houses and bungalows)**
- 60 REI minutes fire rated compartment**

- WP** WIND POSTS
 - refer to drawing 330510523-STN-00-XX-DR-S-5004
- MJ** MOVEMENT JOINTS
 - note: Locations are subject to approval from the Structural Engineer
 - 700399-KKL-ZZ-00-DR-A-2102 and 2103
- steelwork / heavy duty lintel** - refer to SE drawings and details in conjunction with specialist's design
- indicates trimmer in floor OR timber girder truss to roof within ceiling void;** no downstand within the room - to specialist design and detail
- padstones** - refer to SE details; top = u/s of steels = u/s of truss = 2570 above FFL
- Heating pipework in floor below**
- Heating pipework in ceiling above**
- ASHP pipework in floor below**
- ASHP pipework in ceiling above**

PROPOSED APPLICATION

Sanitary Information: refer to drawing series 700399-KKL-ZZ-ZZ-DR-A-7400
Kitchen Information: refer to supplier's drawing (Symphony Kitchens)



Chartered Architects
Chartered Building Surveyors
Interior Designers
CDM Services

Project: Gorse Ride - S73
Client: Wates / Wokingham Borough Council

Revision: P01 09/10/2025 EP RW Roof lights amendment, HT2 PLOT 146 roof light is in different location + wind posts omitted
NY1 19/09/2025 JY RW ASHP piping taken under ground
Rev Date By Ap Note

Drawing Title: HT 1+2 v1 - Plans GF (sht 2)
Drawing Number: Plot 143-144-145-146-147-148

Proposal/Status: 250237-KKL-CP-0310
Revision: P01

Scale: Paper Size: 1:50 ISO A1
Drawing Date: 220123-HT1,2,9,10-Stage 4 PROPOSED APPLICATION
Drawing Title: HT 1+2 v1 - Plans GF (sht 2)
Drawing Number: Plot 143-144-145-146-147-148
Proposal/Status: 250237-KKL-CP-0310
Revision: P01

© Copyright: Do not scale this drawing. Check all dimensions and levels on site.
Only to be used on the site for which designed. The electronic transmission of design information contained in this drawing is carried out entirely at the user's risk and Kendall Kingscott Ltd. will have no liability for any errors or inaccuracies arising therefrom. The production of amended or updated information from the said design information by the user is entirely the responsibility of the user and Kendall Kingscott Ltd. shall have no responsibility in respect thereof.