



Darren Hewitt
4 Demark Street
Wokingham
RG40 2AZ
07/02/2025

Quote 1416

TreeRight Management Method Statement

Ref. 242929 – 36 Rose Street Planning Submission

Introduction

This document outlines the proposed methodology for the management and protection of trees in relation to the submitted planning application. The measures detailed herein are intended to ensure compliance with relevant planning and environmental requirements and will be adhered to throughout the development process.

Scope of Works

The proposed works involve:

T2 - Birch - prune secondary and tertiary scaffolds only, removing no more than a maximum of 3m in length, maintain the canopy shape of the tree as it was prior to pruning. Done by using approved techniques in accordance BS3998 and with cs39 (use of a chainsaw from rope and harness) cs40 (aerial tree pruning). Remove from site via rear access in sections and dispose of arisings using an approved waste disposal

Tree Removal and Pruning

- Tree Removal: Any tree removal will be conducted in accordance with approved plans and necessary permissions from the local planning authority.
- Pruning Works: Any required pruning will be carried out following the best arboriculture practices to maintain tree health and structure.

Prepared by: Michael Mathews

Contact Information: enquiries@treeright.co.uk